REVISIONS		
NO.	DESCRIPTION	DATE

SIGN SUMMARY (4 OF 6)

SHEET NO.	ITEM NO.	APPROXIMATE STATION	LOCATION	SIGN TYPE	POSTS TYPE	A L.F.	B L.F.	SPACING	FOOTINGS DESIGN NO.	CLASS A CONCRETE C.Y.	CLASS AA CONCRETE C.Y.	STEEL 511(A) LBS.	60" DRILLED SHAFT L.F.	STRUCTURAL CONCRETE C.Y.	STEEL 804(B) LBS.	SIGN AREA SHEET S.F.	PANEL S.F.	PANEL OVERHEAD S.F.	REMARKS
T096	184	AS SHOWN	I-35 SB	E5-1A(141), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50		
T096	185	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 174														189.00	EXISTING STRUCTURE
T096	186	AS SHOWN	I-35 SB	D10-3F(141)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T096	187	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 175														132.00	EXISTING STRUCTURE
T095	188	AS SHOWN	I-35 SB	E5-1A(140), E13-1(45)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50		
T095	189	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 177														123.00	EXISTING STRUCTURE
T095	190	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 178														200.00	EXISTING STRUCTURE
T095	191	AS SHOWN	I-35 SB	D10-3F(140)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T095	192	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 179														134.75	EXISTING STRUCTURE
T095	193	AS SHOWN	I-35 SB	E5-1A(139), E13-1(45)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50		
T095	194	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 181									35.00					279.50	NEW TYPE C MONOTUBE
T095	195	AS SHOWN	I-35 SB	SPECIAL SIGNS NO. 182, 183, 184														481.50	EXISTING STRUCTURE
T095	196	AS SHOWN	I-35 SB	D10-3F(139)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T095	197	AS SHOWN	I-35 SB	E5-1A(138D), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		63.00		
T095	198	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 186														201.50	EXISTING STRUCTURE
T094	199	AS SHOWN	I-35 SB	SPECIAL SIGNS NO. 187, 188									70.00					782.50	NEW 90' TYPE B MONOTUBE
T094	200	AS SHOWN	I-35 SB	E5-1A(138C), E13-1(45)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		63.00		
T094	201	AS SHOWN	I-35 SB	SPECIAL SIGNS NO. 190, 191, 192														619.75	EXISTING STRUCTURE
T094	202	AS SHOWN	I-35 SB	E5-1A(138B), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		63.00		
T094	203	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 194														220.25	EXISTING STRUCTURE
T094	204	AS SHOWN	I-35 SB	D10-3F(138)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T094	205	AS SHOWN	I-35 SB	E5-1A(138A), E13-1(20)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		63.00		
T094	206	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 196	4" WF @ 13	21.0	22.5	6' -4"	KC-0					0.72	130.00		63.00		REMOVE EXISTING SIGN
T094	207	AS SHOWN	I-35 SB	SPECIAL SIGNS NO. 197, 198														387.50	EXISTING STRUCTURE
T094	208	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 199														143.00	EXISTING STRUCTURE
T094	209	AS SHOWN	I-35 SB	E5-1A(137), E13-1(20)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50		
T094	210	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 201									35.00					120.75	NEW TYPE C MONOTUBE
T094	211	AS SHOWN	I-35 SB	D10-3F(137)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T093	212	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 202														126.50	EXISTING STRUCTURE
T093	213	AS SHOWN	I-35 SB	E5-1A(136), E13-1(30)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50		
T093	214	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 204														124.00	EXISTING STRUCTURE
T093	215	AS SHOWN	I-35 SB	D10-3F(136)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T093	216	AS SHOWN	I-35 SB	SPECIAL SIGNS NO. 205, 206									70.00					483.50	NEW 75' TYPE B MONOTUBE
T093	217	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 207														210.00	EXISTING STRUCTURE
T093	218	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 208														129.25	EXISTING STRUCTURE
T093	219	AS SHOWN	I-35 SB	E5-1A(135), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50		
T093	220	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 210														146.75	EXISTING STRUCTURE
T093	221	AS SHOWN	I-35 SB	D10-3F(135)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T093	222	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 211														215.25	EXISTING STRUCTURE
T093	223	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 212														148.50	EXISTING STRUCTURE
T092	224	AS SHOWN	I-35 SB	E5-1A(134), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50		
T092	225	AS SHOWN	I-35 SB	SPECIAL SIGNS NO. 214, 215														569.50	EXISTING STRUCTURE
T092	226	AS SHOWN	I-35 SB	D10-3F(134)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T092	227	AS SHOWN	I-35 SB	SPECIAL SIGNS NO. 216, 217														524.50	EXISTING STRUCTURE
T092	228	AS SHOWN	I-35 SB	SPECIAL SIGNS NO. 218, 219														524.50	EXISTING STRUCTURE
T091	229	AS SHOWN	I-35 SB	D10-3F(133)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T091	230	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 220														130.50	EXISTING STRUCTURE
T091	231	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 221														170.00	EXISTING STRUCTURE
T091	232	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 222														137.50	EXISTING STRUCTURE
T091	233	AS SHOWN	I-35 SB	E5-1A(132), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50		
T091	234	AS SHOWN	I-35 SB	D10-3F(132)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T091	235	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 224														130.50	EXISTING STRUCTURE
T091	236	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 225														170.00	EXISTING STRUCTURE
T090	237	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 226														134.75	EXISTING STRUCTURE
T090	238	AS SHOWN	I-35 SB	E5-1A(131), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50		
T090	239	AS SHOWN	I-35 SB	D10-3F(131)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T090	240	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 228														190.50	EXISTING STRUCTURE
T090	241	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 229									35.00					210.00	NEW TYPE C MONOTUBE
T089	242	AS SHOWN	I-35 SB	SPECIAL SIGN NO. 230														205.50	EXISTING STRUCTURE
T089	243	AS SHOWN	I-35 SB	D10-3F(130)	2" SQ. TUBE POST	10.0										4.00			REMOVE EXISTING SIGN
T089	244	AS SHOWN	I-35 SB	E5-1A(130), E13-1(40)	4" WF @ 13	22.0	23.5	5'-5"	KC-0					0.72	130.00		52.50		
				TOTAL									**245.00**	**10.80**	**1950.00**	**48.00**	**840.00**	**8696.50**	
					2" SQ. TUBE POST	**120.0**													
					2-1/2" PIPE POST														
					3" PIPE POST														
					3-1/2" PIPE POST														
					4" WF @ 13	**680.5**													
					6" WF @ 15														
					6" WF @ 20														
					6" WF @ 25														
					8" WF @ 31														
					10" WF @ 45														

Design	SDH	09/14/17
Drawn	GDB	09/14/17

TEC A CLEAR DIRECTION

SIGN SUMMARY (SHEET 4 OF 6)

State Job No. 32625(04) Sheet No. T004

CLEVELAND & OKLAHOMA COUNTY

09/14/17 G:\DP\Projects\T-2598 I-35 Signing Project - EC-185B, Task 1\CAD\T004-32625(04)-SIGN SUMMARY.dgn