

PAY QUANTITY SCHEDULE				
0300 TRAFFIC CONTROL				
PAY ITEM	CODE NO.		UNIT	QUANTITY
876(A)	8482	(PL)TRUCK MOUNTED ATTENUATOR (TC-52,70,76,77)	SD	20.00
880(J)	8905	CONSTRUCTION TRAFFIC CONTROL (TC-25)	LSUM	1.00
880(L)	8911	TRAFFIC SURVEILLANCE, POLICE (TC-65,70)	HR	80.00
882(A)	8306	PORT. CHANGEABLE MESSAGE SIGN (SP-1)(TC-52,84,85)	SD	20.00

PAY QUANTITY SCHEDULE				
0301 TRAFFIC SIGNING & STRIPING				
PAY ITEM	CODE NO.		UNIT	QUANTITY
855(B)	8824	TRAFFIC STRIPE(PLASTIC)(SYMBOLS) (SP-3)	EA	76.00
856(A)	8530	TRAFFIC STRIPE (MULTI-POLYMER)(4" WIDE) (TS-24)	LF	18,812.00
856(A)	8535	TRAFFIC STRIPE(MULTI-POLYMER)(6" WIDE) (SP-2)(TS-25)	LF	489,455.00
856(A)	8540	TRAFFIC STRIPE(MULTI-POLYMER)(8" WIDE) (TS-26)	LF	38,447.00
856(A)	8548	TRAFFIC STRIPE(MULTI-POLYMER)(12" WIDE) (TS-27)	LF	29,770.00
856(A)	8555	TRAFFIC STRIPE(MULTI-POLYMER)(24" WIDE) (TS-28)	LF	5,742.00
856(B)	8860	TRAFFIC STRIPE(MULTI-POLYMER)(ARROWS)	EA	381.00
856(B)	8880	TRAFFIC STRIPE(MULTI-POLYMER)(WORDS)	EA	23.00
857(F)	8006	PAVEMENT MARKING REMOVAL (TRAFFIC STRIPE) (TC-22,75)	LF	662,214.00
857(F)	8007	PAVEMENT MARKING REMOVAL (ARROWS)	EA	381.00
857(F)	8008	PAVEMENT MARKING REMOVAL (WORDS)	EA	19.00
857(F)	8009	PAVEMENT MARKING REMOVAL (SYMBOLS) (SP-4)	EA	72.00

PAY QUANTITY SCHEDULE				
0640 CONSTRUCTION				
PAY ITEM	CODE NO.		UNIT	QUANTITY
641	1552	MOBILIZATION	LSUM	1.00

TRAFFIC PAY QUANTITY NOTES

(TC-22) AMOUNT SHOWN IS AN APPROXIMATION AND THE ACTUAL AMOUNT OF REMOVAL, IF NECESSARY, SHALL BE DETERMINED BY THE ENGINEER. PRICE BID FOR PAVEMENT MARKING REMOVAL SHALL INCLUDE THE COST OF REMOVING STRIPE, ARROWS, WORDS AND SYMBOLS, AS SHOWN IN THE PLANS. THESE ITEMS MAY CONSIST OF PLASTIC, PAINT OR NON-REMOVABLE MARKING TAPE.

(TC-25) ALL CONSTRUCTION TRAFFIC CONTROL WILL BE IMPLEMENTED ACCORDING TO CONSTRUCTION PLANS, AND INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND COMPLIANT WITH APPLICABLE O.D.O.T. STANDARD DRAWINGS. PRICE BID FOR THIS ITEM SHALL BE PAYMENT IN FULL FOR THE INSTALLATION, MAINTENANCE AND SUBSEQUENT REMOVAL OF ALL NECESSARY CONSTRUCTION TRAFFIC CONTROL DEVICES AND PAVEMENT MARKINGS REQUIRED FOR COMPLETION OF THE PROJECT.

ALL SIGNS AND BARRICADES, WHICH ARE SHOWN WITH TYPE 'A' LIGHTS IN THE STANDARD DRAWINGS SHALL HAVE THE CORRESPONDING LIGHT ATTACHED DURING NON-DAYLIGHT HOURS.

(TC-52) ANY USED TRUCK MOUNTED ATTENUATOR OR PORTABLE CHANGEABLE MESSAGE SIGN TO BE PLACED ON THIS PROJECT SHALL BE SUBJECT TO INSPECTION AND APPROVAL, BY

A101