

FED. ROAD DIST. NO.	STATE	JOB PIECE NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
6	OKLA.	27050(04)	2017		

DESCRIPTION	REVISIONS	DATE

SUMMARY OF EROSION CONTROL												
ALIGNMENT	TEMPORARY							PERMANENT				
	SILT FENCE 221(C)	TEMPORARY SEDIMENT FILTER 221(D)	SILT DIKE 221(F)	TEMPORARY ROCK FILTER DAM TYPE 3 221(G)	SEEDING METHOD B 232(B)	VEGETATIVE MULCHING 233(A)	* FERTILIZING (10-20-10) (R-7C)	SOLID SLAB SODDING 230(A)	* FERTILIZING (10-20-10) (R-7B)	* WATERING (R-8)	*TYPE-A SALVAGED TOPSOIL	*FERTILIZING (18-46-0) (R-7A)
	LF	EA	LF	CY	AC	AC	TON	SY	TON	K GAL	CY	TON
RAMP A	311	5	224	-	1.88	0.94	0.29	4541	0.46	363	631	0.08
RAMP B	1552	1	385	20	4.95	2.48	0.75	11957	1.20	957	1661	0.19
RAMP C	-	2	259	-	2.90	1.45	0.44	7016	0.71	561	975	0.11
RAMP B-C	-	-	147	-	0.11	0.06	0.02	249	0.03	20	35	0.01
RAMP D-E	590	2	168	-	0.56	0.28	0.09	1347	0.14	108	188	0.03
RAMP D	593	2	259	-	1.86	0.93	0.28	4484	0.45	359	623	0.07
RAMP E	269	-	707	24	6.42	3.21	0.97	15535	1.56	1243	2158	0.25
RAMP F	-	1	609	-	4.98	2.49	0.75	12049	1.21	964	1674	0.19
ROGERS	-	-	28	-	1.24	0.62	0.19	2991	0.30	239	416	0.05
POST RD	-	-	91	-	1.65	0.83	0.25	3986	0.40	319	554	0.07
<b>TOTALS:</b>	<b>3315</b>	<b>13</b>	<b>2877</b>	<b>44</b>	<b>26.55</b>	<b>13.29</b>	<b>4.03</b>	<b>64155</b>	<b>6.46</b>	<b>5133</b>	<b>8915</b>	<b>1.05</b>

\* FOR CONTRACTORS INFORMATION ONLY, COST TO BE INCLUDED IN THE PRICE BID FOR OTHER WORK.

(R-7A) ESTIMATED AT 150 POUNDS PER ACRE OF TOPSOIL.

(R-7B) ESTIMATED AT 200 POUNDS PER 1,000 S.Y. OF SOLID SLAB SODDING.

(R-7C) ESTIMATED AT 300 POUNDS PER ACRE OF SEED.

(R-8) ESTIMATED AT 80 GALLONS PER S.Y. OF SOLID SLAB SODDING.

SUMMARY OF REMOVALS					
REMOVAL PLAN SHEET NO.	REMOVAL OF CURB AND GUTTER 619 (B)	REMOVAL OF CONCRETE PAVEMENT 619(B)	REMOVAL OF ASPHALT PAVEMENT 619(B)	REMOVAL OF 6" CONCRETE DIVIDING STRIP 619(B)	SAWING PAVEMENT 619(C)
	LF	SY	SY	SY	LF
1	-	3373	-	-	1432
2	5517	11663	115	417	1908
3	1238	4684	356	-	1373
4	1664	7242	69	-	2364
5	-	516	-	-	332
<b>TOTALS:</b>	<b>8419</b>	<b>27478</b>	<b>540</b>	<b>417</b>	<b>7409</b>

REMOVAL OF STRUCTURES & OBSTRUCTIONS 619(A)					
REMOVAL PLAN SHEET NO.	REMOVAL OF FENCE	REMOVAL OF 18" RCP	REMOVAL OF HEADWALL	REMOVAL OF INLET	REMOVAL OF MANHOLE
	LF	LF	LF	EA	EA
1	-	-	-	-	-
2	1815	594	3	8	-
3	1550	434	-	3	1
4	2320	703	1	4	1
5	247	-	-	-	-
<b>TOTALS:</b>	<b>5932</b>	<b>1731</b>	<b>4</b>	<b>15</b>	<b>2</b>

NOTE: ALL ITEMS IN THIS TABLE SHALL BE INCLUDED IN PAY ITEM "REMOVAL OF STRUCTURES AND OBSTRUCTIONS." ITEMS WILL NOT BE MEASURED OR PAID SEPERATELY.

DESIGN	AKS	9/13	1-44 & US-62 INTERCHANGE
DRAWN	AKS	9/13	
CHECKED	JES	5/16	
APPROVED			
SQUAD	<b>GARVER</b>		

**SUMMARY SHEET (ROADWAY)  
(SHEET 2 OF 2)**

STATE JOB NO. 27050(04) SHEET NO. 19