

SIGN SUMMARY

SIGN NO.	ALIGNMENT	APPROXIMATE STATION	LOCATION	SIGN TYPE	SIGNS			FOOTINGS			POSTS				(PL) REMOVAL OF GROUND MOUNTED SIGNS	(PL) REMOVAL OF EXSTING SIGNS	(PL) REMOVE & RESET EXSTING SIGNS	(PL) REMOVE & RESET GROUND MOUNTED SIGNS	REMARKS								
					0.063"	0.080"	0.100"	EXTR. ALUM. PANEL (OVERHEAD)	EXTR. ALUM. PANEL	TYPE	STRUC. CONC.	REINFORCIN G STEEL	2" SQUARE TUBE POST	3" @ 7.58 GALV. STEEL PIPE POST						WF							
					SHEET ALUMINUM SIGNS															804(A)	804(B)	851(C)		851(B)		851(A)	
					SF	SF	SF															POST A LF	POST B LF	POST A LF	POST B LF	SIZE	POST A LF
53	RAMP D	60+48	LT	E5-1a, E13-1P	-	-	-	-	55.00	KC-0	0.72	130	-	-	-	-	-	-	-	INSTALL A SIGN ASSEMBLY (EXIT 40B, 30 DEG ARROW) AND (SPEED LIMIT 25MPH)							
54	RAMP D	60+75	LT	W1-8E	-	7.5	-	-	-	-	-	-	12.0	-	-	-	-	-	-	INSTALL A SIGN ASSEMBLY (CHEVRON)							
55	NOT USED																										
56	RAMP D	61+55	LT	W1-8E	-	7.5	-	-	-	-	-	-	12.0	-	-	-	-	-	-	INSTALL A SIGN ASSEMBLY (CHEVRON)							
57	RAMP D	62+35	LT	W1-8E	-	7.5	-	-	-	-	-	-	12.0	-	-	-	-	-	-	INSTALL A SIGN ASSEMBLY (CHEVRON)							
58	RAMP D	63+16	LT	W1-8E	-	7.5	-	-	-	-	-	-	12.0	-	-	-	-	-	-	INSTALL A SIGN ASSEMBLY (CHEVRON)							
59	RAMP D	63+95	LT	W1-8E	-	7.5	-	-	-	-	-	-	12.0	-	-	-	-	-	-	INSTALL A SIGN ASSEMBLY (CHEVRON)							
60	RAMP D	64+75	LT	W1-8E	-	7.5	-	-	-	-	-	-	12.0	-	-	-	-	-	-	INSTALL A SIGN ASSEMBLY (CHEVRON)							
61	RAMP DE	52+90	LT	R5-1F, R3-2F	-	-	32	-	-	0.23	32	-	-	13.0	13.0	-	-	-	-	INSTALL (DO NOT ENTER), (NO LEFT TURN)							
R62	RAMP DE	52+93	RT	W8-13	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	REMOVE (WATCH FOR ICE ON BRIDGE)							
R63	RAMP DE	53+00	RT	ROUTE ASSEMBLY	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	REMOVE (EAST, 144, 90 DEG ARROW, NORTH 277, 281, 90 DEG ARROW)							
64	RAMP DE	53+10	LT	W4-3R	-	-	9	-	-	-	-	-	13.2	-	-	-	-	-	-	INSTALL (RIGHT LANE ADDED)							
65	RAMP DE	53+20	LT	R5-1F, R3-2F	-	-	32	-	-	0.23	32	-	-	13.0	13.0	-	-	-	-	INSTALL (DO NOT ENTER), (NO LEFT TURN)							
66	RAMP DE	53+70	LT	R5-1a	-	-	6	-	-	-	-	-	11.0	-	-	-	-	-	-	INSTALL WRONG WAY SIGN							
67	RAMP DE	53+85	LT	R5-1a	-	-	6	-	-	-	-	-	11.0	-	-	-	-	-	-	INSTALL WRONG WAY SIGN							
68	NOT USED																										
R69	RAMP DE	57+41	RT	W4-2L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	REMOVE (LEFT LANE ENDS)							
R70	RAMP DE	57+41	RT	W4-2L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	REMOVE (LEFT LANE ENDS)							
71	RAMP E	67+70	RT	W4-3R	-	-	9	-	-	-	-	-	13.2	-	-	-	-	-	-	INSTALL (RIGHT ADDED LANE)							
R72	RAMP E	72+47	RT	W4-1R	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	REMOVE (RIGHT MERGE)							
73	RAMP F	62+73	LT		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	COORDINATE TO RELOCATE THE CONCRETE BARRIERS, FENCE AND STOP SIGNS TO APPROX 215 FT NORTH OF THE EXISTING LOCATION							
74	RAMP F	63+51	RT	Sp. Sign No. 21	-	-	-	243.00	KC-3	1.98	632	-	-	-	-	W8 x 31	19.0	19.0	-	INSTALL (180 DEG ARROW EAST ROGERS LANE, 180 DEGREE ARROW USPHS INDIAN HOSPITAL, FT. SILL INDIAN SCHOOL)							
75	RAMP F	63+51	RT	R5-1F	-	-	16	-	-	-	-	-	13.0	13.0	-	-	-	-	-	INSTALL DO NOT ENTER							
76	RAMP F	63+48	LT	R5-1F	-	-	16	-	-	-	-	-	13.0	13.0	-	-	-	-	-	INSTALL DO NOT ENTER							
77	RAMP F	67+87	LT	Sp. Sign No. 15	-	-	-	51.00	KC-0	0.72	130	-	-	-	-	W4 x 13	15.5	15.5	-	INSTALL GUIDE SIGN (GATE 2, 0 DEG ARROW)							
78	RAMP F	67+95	RT	Sp. Sign No. 7	-	-	-	182.5	KC-3	1.98	632	-	-	-	-	W8 x 31	26.0	26.0	-	INSTALL (EXT 40B, US 62 WEST, CACHE, ALTUS, 45 DEG ARROW)							
79	RAMP F	73+22	RT	E5-1a, E13-1P	-	-	-	55.00	KC-0	0.72	130	-	-	-	-	W4 x 13	14.5	14.5	-	INSTALL EXT SIGN (EXT 40C, 30 DEG ARROW)(50 MPH)							
80	RAMP F	77+50	CL	Sp. Sign No. 13	-	-	-	199.25	-	-	-	-	-	-	-	-	-	-	-	INSTALL (EXT 40C, EAST, ROGERS LANE, 45 DEG ARROW) ON OVERHEAD SIGN STRUCTURE 1							
	RAMP F	77+50	CL	Sp. Sign No. 14	-	-	-	183	-	-	-	-	-	-	-	-	-	-	-	INSTALL (EXT 40B, HWY 62 WEST, CACHE, ALTUS, 1/4 MILE) ON OVERHEAD SIGN STRUCTURE 1							
	RAMP F	77+50	CL	W13-2F	-	-	20	-	-	-	-	-	-	-	-	-	-	-	-	INSTALL ON RIGHT LEG OF OVERHEAD SIGN STRUCTURE 1 (ADVISORY SPEED 50 MPH)							
81	NOT USED																										
82	ROGERS LN	48+04	RT	ROUTE ASSEMBLY 2	12.38	10	-	-	-	0.23	32	-	-	15.25	15.25	-	-	-	-	-	INSTALL ROUTE ASSEMBLY (WEST, I-44, 90 DEG ARROW)(SOUTH, US277, US281, 90 DEG ARROW)						
83	ROGERS LN	48+04	RT	Sp. Sign No. 22	-	-	-	113.75	KC-1	1.64	348	-	-	-	-	W6 x 15	16.0	16.0	-	-	INSTALL (90 DEG ARROW OKLAHOMA CITY, WICHITA FALLS 0 DEG ARROW)						
84	ROGERS LN	49+23	RT	ROUTE ASSEMBLY 3	16.38	10	-	-	-	0.23	32	-	-	15.25	15.25	-	-	-	-	-	INSTALL ROUTE ASSEMBLY (EAST, I-44, US62, 0 DEG ARROW)(NORTH US277, US281, 0 DEG ARROW)						
85	ROGERS LN	49+33	LT	ROUTE ASSEMBLY 1	12.38	10	-	-	-	0.23	32	-	-	15.25	15.25	-	-	-	-	-	INSTALL ROUTE ASSEMBLY (WEST, I-44, 270 DEG ARROW)(SOUTH, US277, US281, 270 DEG ARROW)						
86	ROGERS LN	49+33	LT	Sp. Sign No. 18	-	-	-	51.00	KC-0	0.72	130	-	-	-	-	W4 x 13	15.5	15.5	-	-	INSTALL GUIDE SIGN (GATE 2, 0 DEG ARROW)						
87	ROGERS LN	49+33	LT	Sp. Sign No. 20	-	-	-	51	KC-0	0.72	130	-	-	-	-	W4 x 13	12.5	12.5	-	-	INSTALL GUIDE SIGN (WICHITA FALLS, 180 DEG ARROW)						
R88	ROGERS LN	49+33	LT		-	-	-	-	-	-	-	-	-	-	-	-	-	-	X	-	REMOVE (WEST I44, SOUTH 277, 281, WICHITA FALLS, 270 DEG ARROW)(WEST 62, 0 DEG ARROW)						
89	ROGERS LN	49+39	CL	R4-7	-	-	-	-	-	-	-	-	11.5	-	-	-	-	-	-	1	REMOVE/RESET (KEEP RIGHT)						
90	ROGERS LN	50+04	RT	W8-13	-	-	6.25	-	-	-	-	-	12.5	-	-	-	-	-	-	-	INSTALL (BRIDGE ICES BEFORE ROAD)						
91	ROGERS LN	51+04	RT	R3-7(R)	-	-	6.25	-	-	-	-	-	11.5	-	-	-	-	-	-	-	INSTALL (RIGHT LANE MUST TURN RIGHT)						
92	ROGERS LN	51+78	LT	Sp. Sign No. 19	-	-	-	145.75	KC-1	1.52	212	-	-	-	-	W6 x 15	15.0	15.0	-	-	INSTALL (MARTIN LUTHER KING JR, 180 DEG ARROW FREEWAY)						
R93	ROGERS LN	51+78	LT		-	-	-	-	-	-	-	-	-	-	-	-	-	-	X	-	REMOVE (MARTIN LUTHER KING JR, 180 DEG ARROW FREEWAY)						
94	ROGERS LN	52+03	RT	R3-8R	-	-	6.25	-	-	-	-	-	-	-	-	-	-	-	-	-	INSTALL (LANE ARROW SIGN THRU LANE, RIGHT TURN LANE)						
95	ROGERS LN	54+50	RT	R3-7R	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	RELOCATED FROM EX NB OFF RAMP (RIGHT LANE MUST TURN RIGHT)						
R96	ROGERS LN	54+95	RT	W10-1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-	REMOVE (RAILROAD ADVANCE WARNING)						
97	ROGERS LN	55+40	RT	ROUTE ASSEMBLY 4	16.38	10	-	-	-	0.23	32	-	-	15.25	15.25	-	-	-	-	-	INSTALL ROUTE ASSEMBLY (EAST, I-44, US62, 30 DEG ARROW)(NORTH, US277, US281, 30 DEG ARROW)						
98	ROGERS LN	55+40	RT	Sp. Sign No. 8	-	-	-	182.5	KC-3	1.98	632	-	-	-	-	W8 x 31	26.0	26.0	-	-	INSTALL (EXT 40B, US 62 WEST, CACHE, ALTUS, 45 DEG ARROW)						
R99	ROGERS LN	55+75	CL	R5-1a	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-	REMOVE (DO NOT ENTER)						

DESIGN	RBH	9/13	SUMMARY SHEET (TRAFFIC) (SHEET 3 OF 4)
DRAWN	RBH	9/13	
CHECKED	JES	5/16	
APPROVED			
SQUAD	GARVER		

STATE JOB NO. 27050(04) SHEET NO. 22