

SIGN SUMMARY

SIGN NO.	ALIGNMENT	APPROXIMATE STATION	LOCATION	SIGN TYPE	SIGNS			FOOTINGS			POSTS				(PL) REMOVAL OF GROUND MOUNTED SIGNS	(PL) REMOVAL OF EXISTING SIGNS	(PL) REMOVE & RESET EXISTING SIGNS	(PL) REMOVE & RESET GROUND MOUNTED SIGNS	REMARKS							
					0.063"	0.080"	0.100"	EXTR. ALUM. PANEL (OVERHEAD)	EXTR. ALUM. PANEL	TYPE	STRUC. CONC.	REINFORCIN G STEEL	2" SQUARE TUBE POST							3" @ 7.58 GALV. STEEL PIPE POST		GALV. STEEL WIDE FLANGE BEAM POST				
					SHEET ALUMINUM SIGNS								804(A)	804(B)						851(C)		851(B)		851(A)		
					SF	SF	SF						SF	SF						CY	LB	POST A LF	POST B LF	POST A LF	POST B LF	SIZE
100	ROGERS LN	55+88	CL	W10-1	-	-	7.07	-	-	-	-	-	-	-	-	-	-	-	INSTALL (RAILROAD ADVANCE WARNING)							
R101	ROGERS LN	56+02	CL	R4-7	-	-	-	-	-	-	-	-	-	-	-	-	-	-	REMOVE (KEEP RIGHT)							
102	ROGERS LN	56+06	LT	W8-13	-	-	6.25	-	-	-	-	-	-	-	-	-	-	-	INSTALL (BRIDGE ICES BEFORE ROAD)							
R103	ROGERS LN	56+18	RT	R6-1(L)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	REMOVE (ONE WAY)							
R104	ROGERS LN	56+63	RT	R4-7	-	-	-	-	-	-	-	-	-	-	-	-	-	-	REMOVE (KEEP RIGHT)							
R105	ROGERS LN	56+66	RT	M1-4(2), M6-1(L)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	REMOVE (US62, 270 DEG ARROW)							
106	ROGERS LN	57+03	LT	W4-3R	-	-	9	-	-	-	-	-	-	-	-	-	-	-	INSTALL (RIGHT ADDED LANE)							
R107	ROGERS LN	57+04	CL	R3-2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	REMOVE (NO LEFT TURN)							
108	ROGERS LN	57+83	RT	W4-3R	-	-	9	-	-	-	-	-	-	-	-	-	-	-	INSTALL (RIGHT ADDED LANE)							
109	ROGERS LN	58+16	LT	ROUTE ASSEMBLY 6	12.38	10	-	-	-	0.23	32	-	-	15.25	15.25	-	-	-	-	INSTALL ROUTE ASSEMBLY (WEST, I-44, 0 DEG ARROW)(SOUTH, US277, US281, 0 DEG ARROW)						
110	ROGERS LN	59+33	LT	R3-7R	-	6.25	-	-	-	-	-	11.5	-	-	-	-	-	-	-	INSTALL (RIGHT LANE MUST TURN RIGHT)						
111	ROGERS LN	59+66	RT	R3-7R	-	6.25	-	-	-	-	-	11.5	-	-	-	-	-	-	-	INSTALL (RIGHT LANE MUST TURN RIGHT)						
112	ROGERS LN	59+68	CL	R3-8R	-	6.25	-	-	-	-	-	11.5	-	-	-	-	-	-	-	INSTALL A LANE ARROW SIGN (THRU LANE, RIGHT TURN LANE)						
113	ROGERS LN	60+38	LT	ROUTE ASSEMBLY 5	16.38	10	-	-	-	0.23	32	-	-	15.25	15.25	-	-	-	-	INSTALL ROUTE ASSEMBLY (EAST, I-44, US62, 30 DEG ARROW)(NORTH, US277, US281, 30 DEG ARROW)						
114	ROGERS LN	60+38	LT	Sp. Sign No. 9	-	-	-	-	117	KC-1	1.52	212	-	-	-	-	W6 x 15	16.0	16.0	-	-	-	-	INSTALL (90 DEG ARROW, WICHITA FALLS, OKLA. CITY, 45 DEG ARROW)		
115	ROGERS LN	61+00	RT	Sp. Sign No. 11	-	-	-	-	-	KC-3	1.98	632	-	-	-	-	W8 x 31	19.5	19.5	-	-	-	1	REMOVE AND RESET BEHIND CURB (USPHS INDIAN HOSPITAL, FT. SILL INDIAN SCHOOL)		
R116	ROGERS LN	61+11	LT	ROUTE ASSEMBLY	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	REMOVE (ROUTE ASSEMBLY)		
R117	ROGERS LN	61+29	LT	W10-1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	REMOVE (RAIL ROAD CROSSING)		
118	ROGERS LN	61+43	LT	W10-1	-	-	-	-	-	-	-	12.0	-	-	-	-	-	-	-	-	-	-	-	-	INSTALL (RAIL ROAD CROSSING)	
119	ROGERS LN	63+77	LT	ROUTE ASSEMBLY 7	16.72	10	-	-	-	0.23	32	-	-	15.5	15.5	-	-	-	-	-	-	-	-	-	INSTALL (JCT, I44, JCT, US62, JCT, US277, JCT, US281)	
120	ROGERS LN	64+02	RT	R2-1(35)	-	-	-	-	-	-	-	11.5	-	-	-	-	-	-	-	-	-	-	-	-	REMOVE AND RESET (SPEED LIMIT 35)	
121	EB I-44	-	RT	Sp Sign No.2	-	-	-	-	145	KC-1	1.52	212	-	-	-	-	W6 x 15	20.5	20.5	-	-	-	-	-	INSTALL (EXT 40A), (EAST, ROGERS LANE, 1/2 MILE)	
122	EB I-44	-	RT	Sp. Sign No.1	-	-	-	-	145	KC-1	1.52	212	-	-	-	-	W6 x 15	20.5	20.5	-	-	-	-	-	INSTALL (EXT 40A), (EAST, ROGERS LANE, 3/4 MILE)	
123	EB I-44	-	RT	Sp. Sign No. 3	-	-	-	-	176.25	KC-1	1.52	212	-	-	-	-	W6 x 15	17.0	17.0	-	-	-	-	-	INSTALL GUIDE SIGN (USPHS INDIAN HOSPITAL, FT. SILL INDIAN SCHOOL, NEXT RIGHT)	
124	EB I-44	-	RT	Sp. Sign No. 4	-	-	-	-	62.50	KC-0	0.72	130	-	-	-	-	W4 X 13	14.5	14.5	-	-	-	-	-	INSTALL (GATE 2, SECOND RIGHT)	
125	WB I-44	-	RT	Sp. Sign No. 10	-	-	-	-	145.00	KC-1	1.52	212	-	-	-	-	W6 x 15	20.5	20.5	-	-	-	-	-	INSTALL (EXT 40C, EAST, ROGERS LANE, 3/4 MILE)	
126	WB I-44	-	RT	Sp. Sign No. 11	-	-	-	-	223.25	KC-3	1.98	632	-	-	-	-	W8 x 31	19.5	19.5	-	-	-	-	-	INSTALL (GATE 2, USPHS INDIAN HOSPITAL, FT. SILL INDIAN SCHOOL, NEXT RIGHT)	
127	WB I-44	-	RT	Sp. Sign No. 12	-	-	-	-	145.00	KC-1	1.52	212	-	-	-	-	W6 x 15	20.5	20.5	-	-	-	-	-	INSTALL (EXT 40C, EAST, ROGERS LANE, 1/2 MILE)	
128	RAMP D	59+00	RT	Sp. Sign No. 25	-	-	-	228.75	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	INSTALL (EXT 40B, HWY 62 WEST, CACHE, ALTUS, EXT 315 DEG ARROW ONLY) ON OVERHEAD SIGN STRUCTURE 3	
	RAMP D	59+00	RT	W13-6F	-	-	28	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	INSTALL (W13-6F ON POST)	
129	RAMP E	75+45	RT	W4-2R	-	-	9	-	-	-	-	13.2	-	-	-	-	-	-	-	-	-	-	-	-	INSTALL (W4-2R, LANE ENDS)	
R130	RAMP C	46+00	LT		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	REMOVE (FT. SILL VISITOR CENTER, 270 DEG. ARROW, 2 MILES)	
SUB TOTALS:					132.10	3696.35	412.92	839.75	2917.5	-	35.81	7574	507.3	39	221.0	221.0	845.0		1	28	5	2				
TOTALS:					4241.37			839.75	2917.5	-	35.81	7574	546.3		442.0	TOTALS		1	28	5	2					

DESIGN	RBH	9/13	1-44 & US-62 INTERCHANGE SUMMARY SHEET (TRAFFIC) (SHEET 4 OF 4)
DRAWN	RBH	9/13	
CHECKED	JES	5/16	
APPROVED			
SQUAD	GARVER		
STATE JOB NO. 27050(04)			SHEET NO. 23