OKLAHOMA DEPARTMENT OF TRANSPORTATION					
FED. ROAD DIST. NO.	STATE	JOB PIECE NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
6	OKLA.	27050(04)	2017		

REVISIONS	
DESCRIPTION	DATE

0 50 100 150

SCALE

MATCH LINE REMOVALS SHEET 1

MATCH LINE REMOVALS SHEET 3

REMOVE 100.02 L.F. C&G

13.76 L.F. SAWCUT

REMOVE 284.71 L.F. C&G

REMOVE CDI

REMOVE 59.15 L.F. C&G

REMOVE 81.60 L.F. C&G

398.69 L.F. SAWCUT

2.08 L.F. SAWCUT

REMOVE 6.37 L.F. C&G

REMOVE 20.99 L.F. C&G

REMOVE 1189.52 S.Y. CONCRETE

REMOVE 1933.56 S.Y. CONCRETE

REMOVE 555.03 S.Y. ASPHALT

℄ RAMP A

203.25 L.F. SAWCUT

10.03 L.F. SAWCUT

199.55 L.F. SAWCUT

REMOVE 96 S.Y. DIVIDING STRIP

416.34 L.F. SAWCUT

38.05 L.F. SAWCUT

10.15 L.F. SAWCUT

REMOVE 493.52 S.Y. CONCRETE

CUT AND CAP DROP INLET

REMOVE 3160.24 S.Y. CONCRETE

REMOVE 124.79 L.F. C&G

℄ ROGERS LANE

REMOVE 668 L.F. C&G

REMOVE 176.54 L.F. C&G

REMOVE CDI & 35.74 L.F. 18" R.C.P. W/ HEADWALL

REMOVE CDI & 66.74 L.F. 18" R.C.P. W/ HEADWALL

℄ RAMP C

REMOVE 445.19 L.F. C&G

REMOVE CDI & 58.36 L.F. 18" R.C.P. W/ HEADWALL

REMOVE 817.23 L.F. C&G

REMOVE 81.21 L.F. C&G

3.02 L.F. SAWCUT

REMOVE 32.95 S.Y. DIVIDING STRIP

219.71 L.F. SAWCUT

REMOVE 82.06 L.F. C&G

℄ RAMP B

℄ RAMP B-C

REMOVE 162.84 L.F. C&G

REMOVE 202.98 L.F. C&G

REMOVE 81.29 L.F. C&G

℄ RAMP D-E

REMOVE 117.15 S.Y. CONCRETE

93.55 L.F. SAWCUT

23.91 L.F. SAWCUT

℄ RAMP D

REMOVE 486.88 L.F. FENCE

REMOVE 1854.89 S.Y. CONCRETE

REMOVE 171.83 L.F. FENCE

REMOVE CDI & 76.73 L.F. 18" R.C.P.

REMOVE 197.05 L.F. FENCE

11.00 L.F. SAWCUT

REMOVE 186.26 L.F. C&G

263.94 L.F. SAWCUT

REMOVE 697.28 L.F. C&G

REMOVE CDI & 333.58 L.F. 18" R.C.P.

REMOVE 491.90 L.F. FENCE

REMOVE 314.51 L.F. C&G

REMOVE 287.17 S.Y. DIVIDING STRIP

REMOVE 587.79 L.F. C&G

REMOVE CDI & 22.84 L.F. 18" R.C.P.

REMOVE 335.29 L.F. C&G

REMOVE 466.89 L.F. FENCE

REMOVE 2913.56 S.Y. CONCRETE

MATCH LINE REMOVALS SHEET 3

MATCH LINE REMOVALS SHEET 3

LEGEND

- CURB AND GUTTER REMOVAL
- SAWCUT
- FENCE REMOVAL
- DRAINAGE STRUCTURE REMOVAL
- DIVIDING STRIP REMOVAL
- CONCRETE PAVEMENT REMOVAL
- ASPHALT PAVEMENT REMOVAL

DESIGN	AKS	9/13
DRAWN	TML	9/13
CHECKED	JES	5/16
APPROVED		
SQUAD	GARVER	

I-44 & US-62 INTERCHANGE

REMOVALS (SHEET 2 OF 5)

STATE JOB NO. 27050(04) SHEET NO. 84