



SECTION A-A

SUMMARY OF WALL STAINING

STAIN DESIGNATION	UNIT	TOTAL
WF-1	S.Y.	451.00
WF-2	S.Y.	220.00

① West retaining wall only. Areas are estimated.

NOTES:
 See Sheet No. 17A for General Notes related to preparation and staining/painting of the existing bridge item.
 Water repellent shall be applied as specified in the Standard Specifications after staining operations have been completed.
 For additional information, see As-Built plans.

WEST RETAINING WALL ELEVATION

LEGEND

	Stain WF-1 Fed. Color ID No. 23717 Beige
	Stain WF-2 Fed. Color ID No. 10115 Brown

I-44 UNDER ROGERS LANE COMANCHE COUNTY BRIDGE 'C'		DESIGN	BRT	8/17
		DETAIL	S.JL	8/17
		CHECK	BRT	8/17
AESTHETIC DETAILS (SHEET 3 OF 4)		GARVER		
STATE OF OKLAHOMA	DEPARTMENT OF TRANSPORTATION	JOB PIECE NO. 27050(04)	SHEET NO. 156	