



**NOTE :**  
INTERCEPTOR DIKES SHALL BE USED AS DIRECTED BY THE ENGINEER FOR EROSION CONTROL OF CUT SLOPES GREATER THAN 15 FEET OR IN LOCATIONS DEEMED NECESSARY TO RELIEVE SLOPE EROSION.



- NOTES :**
- MATERIALS FOR THE ROCK BASE SHALL BE IN ACCORDANCE WITH 2009 STANDARD SPECIFICATIONS SEC. 713.03 STONE FILL FOR GABIONS, REVETMENT MATTRESSES, AND ROCK FILTER DAMS.
  - LOCATION OF STABILIZED CONSTRUCTION EXIT TO BE AS APPROVED BY THE ENGINEER.



INTERSECTION OF CUT AND/OR FILL SLOPES WITH GROUND LINE TO BE ROUNDED AS PART OF FINISHING OPERATIONS. ROUNDED SHALL BE 5' MIN. FOR SMALLER CUTS AND FILLS TO 15' MAX. FOR LARGER CUTS AND FILLS OR AS DESIGNATED BY THE ENGINEER. COST OF ROUNDED TO BE INCLUDED IN PRICE BID FOR OTHER ITEMS OF WORK.

Design		SH 10 OVER BIG CABIN CREEK	CRAIG COUNTY
Drawn			
Checked			
Approved			
Squad			

**MISCELLANEOUS DETAILS**

State Job No. 29068(04) Sheet No. 3