

OKLAHOMA DEPARTMENT OF TRANSPORTATION						
FED. ROAD DIST. NO.	STATE	JOB PIECE NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS	
	OKLA.	31426(04)	2018	3	10	
DESCRIPTION				REVISIONS		DATE
UPDATED QUANTITY				ADDED PAY ITEM		8/29/2017
						8/29/2017

SUMMARY OF DRAINAGE STRUCTURES										
STR. NO.	P & P SHEET NO.	STATION	DESCRIPTION	FILL HEIGHT	613(A) R.C. PIPE CLASS-III			613(M) CULVERT END TREATMENT		
					48"	28" X 18"	58" X 36"	(TYPE B4)	(TYPE E4)	(TYPE DD4)
					ROUND	ARCHED				
					FT.	L.F.				
1	8	121+86.50	28"X18"X74' RCPA	-	74.00	-	-	1.00	-	-
2	8	20+38.00	48"X76' RCP	76.00	-	-	-	-	1.00	-
3	8	130+94.00	2-58"X36"X45' RCPA	-	-	64.00	-	-	-	1.00
TOTALS:				76.00	74.00	64.00	1.00	1.00	1.00	1.00

SUMMARY OF EROSION CONTROL			
SHEET NO.	STATION TO STATION	DESCRIPTION	230(A) SOLID SLAB SOD S.Y.
10	11+00.00 TO 16+88.84	ALL DISTURBED AREAS	946.00
10	20+10.95 TO 26+50.00	ALL DISTURBED AREAS	932.00
9	119+00.00 TO 133+00.00	ALL DISTURBED AREAS	6,194.00
TOTALS			8,072.00

SUMMARY OF DRIVES									
P & P SHEET NO.	STATION	TYPE	WIDTH	LENGTH	RADIUS	402(E)	407(B)	411(B)	411(C)
						TRAFFIC BOUND SURFACE COURSE	TACK COAT	SUPERPAVE TYPE S3 (PG 64-22 OK)	SUPERPAVE TYPE S4 (PG 64-22 OK)
						TON	GAL.	TON	TON
10	22+64.00 LT.	FIELD ENTRANCE	12	94	20/20	19.00	2.00	4.00	3.00
TOTAL						19.00	2.00	4.00	3.00

SUMMARY OF TEMPORARY SEDIMENT CONTROLS			
SHEET NO.	STATION TO STATION	221(C)	221(F)
		SILT FENCE	SILT DIKE
		L.F.	L.F.
10	11+00.00 TO 16+88.84	305.00	-
10	20+10.95 TO 26+50.00	465.00	-
9	119+00.00 TO 133+00.00	-	190.00
TOTALS		770.00	190.00

SUMMARY OF GRADING				
P & P SHEET NO.	STATION TO STATION	202(A)	EMB. +15%	202(D)
		UNCL. EXCAV. C.Y.	C.Y.	UNCL. BORROW C.Y.
		10	11+00.00 TO 16+88.84	2127.00
10	20+10.95 TO 26+50.00	3.00	2187.00	2184.00
9	119+00.00 TO 133+00.00	21.00	1893.00	1872.00
9	CHANNEL	327.00	3.00	(324.00)
TOTAL		2478.00	12472.00	9994.00

SUMMARY OF SURFACING QUANTITIES						
P & P SHEET NO.	STATION TO STATION	307(K)	407(B)	408	411(B)	411(C)
		STABILIZED SUBGRADE	TACK COAT	PRIME COAT	SUPERPAVE TYPE S3 PG 64-22 OK	SUPERPAVE TYPE S4 PG 64-22 OK
		S.Y.	GAL.	GAL.	TON	TON
10	11+00.00 TO 16+88.84	1,309.00	118.00	491.00	271.00	226.00
10	20+10.95 TO 26+50.00	1,421.00	128.00	533.00	294.00	245.00
9	119+00.00 TO 133+00.00	3,112.00	280.00	1,167.00	643.00	536.00
TOTAL		5,842.00	526.00	2,191.00	1,208.00	1,007.00

SUMMARY OF STRIPING				
P & P SHEET NO.	STATION TO STATION	856(A)		856(A) Δ
		TRAFFIC STRIPE (MULTI-POLYMER) (4" WIDE)		TRAFFIC STRIPE (MULTI-POLYMER) (24" WIDE)
		L.F.		L.F.
10	11+00.00 TO 16+88.84	1,178.00	1,178.00	11.00
10	20+10.95 TO 26+50.00	1,279.00	1,279.00	11.00
9	119+00.00 TO 133+00.00	2,800.00	2,800.00	0.00
TOTALS		5,257.00	5,257.00	22.00

SUMMARY OF REMOVALS				
P & P SHEET NO.	STATION TO STATION	619(B)	619(B)	619(C)
		REMOVAL OF ASPHALT PAVEMENT	REMOVAL OF GUARDRAIL	SAWING PAVEMENT
		S.Y.	L.F.	L.F.
10	11+00.00 TO 16+88.84	1,170.00	-	14.00
10	20+10.95 TO 26+50.00	1,413.00	-	18.00
9	119+00.00 TO 133+00.00	2,583.00	156.00	39.00
TOTAL		5,166.00	156.00	71.00

SCHEDULE OF GUARD RAIL					
LOCATION	623(F) GUARDRAIL (TYPE D-BF)		623(F) GUARDRAIL (TYPE A)	TOTAL PANEL LENGTH (TYPE A)	
	LT.	RT.	EA.	EA.	L.F.
123+50.63 TO 124+25.63	X		-	1.00	75.00
124+25.63 TO 124+50.63	X		1.00	-	25.00
124+21.92 TO 124+40.16		X	-	1.00	75.00
124+40.16 TO 124+65.16		X	1.00	-	25.00
127+24.84 TO 127+49.84	X		1.00	-	25.00
127+49.84 TO 127+68.16	X		-	1.00	75.00
127+39.37 TO 127+64.37		X	1.00	-	25.00
127+64.37 TO 128+39.37		X	-	1.00	75.00
TOTALS			4.00	4.00	325.00

SUMMARY OF SIGNS							
SIGN NO.	APPROXIMATE SIGN LOCATION	ASSEMBLY TYPE	TYPE OF SIGN	DESCRIPTION	BLANKS	850(A)	851(C)
						SHEET ALUMINUM SIGNS S.F.	2 1/4" SQ. TUBE POSTS
1	20+42.00, 21' LT.	STOP SIGN WITH STREET NAMES	R1-1	STOP	B-30(O)	5.18	15.00
			D3-1	STREET NAME (NS 305)	B-2406	1.00	
			D3-1	STREET NAME (EW 153)	B-2406	1.00	
			W4-4P	"CROSS TRAFFIC DOES NOT STOP"	B-2412	2.00	
2	16+63.00, 21' RT.	STOP SIGN WITH STREET NAMES	R1-1	STOP	B-30(O)	5.18	15.00
			D3-1	STREET NAME (NS 305)	B-2406	1.00	
			D3-1	STREET NAME (EW 153)	B-2406	1.00	
			W4-4P	"CROSS TRAFFIC DOES NOT STOP"	B-2412	2.00	
Δ 3	122+00.00, 21' LT.	SINGLE SIGN	R2-1(45)	SPEED LIMIT SIGN (45 MPH)	B-2430	5.00	15.00
Δ 4	129+93.00, 21' RT.	SINGLE SIGN	R2-1(45)	SPEED LIMIT SIGN (45 MPH)	B-2431	5.00	15.00
TOTAL						28.36	60.00