

| SUMMARY OF TEMPORARY SEDIMENT CONTROL |   |                             |                            |                            |
|---------------------------------------|---|-----------------------------|----------------------------|----------------------------|
| STATION EXTENTS                       | LOCATION AND DESCRIPTION                            | TEMPORARY SILT FENCE 221(C) | TEMPORARY SILT DIKE 221(F) | VEGETATIVE MULCHING 233(A) |
|                                       |   | L.F.                        | L.F.                       | AC.                        |
| STA. 553+10.00 TO STA. 559+00.00      | ACROSS TEMP. SLOPES RT.                             |                             |                            | 0.25                       |
| STA. 554+50.00                        | ACROSS TEMP. DITCH RT.                              |                             | 7                          |                            |
| STA. 556+00.00                        | ACROSS TEMP. DITCH RT.                              |                             | 7                          |                            |
| STA. 557+25.00                        | ACROSS TEMP. DITCH RT.                              |                             | 7                          |                            |
| STA. 558+50.00                        | ACROSS TEMP. DITCH RT.                              |                             | 7                          |                            |
| STA. 559+00.00 TO STA. 574+00.00      | ALONG TOE LT. & RT.                                 | 960                         | 7                          |                            |
| STA. 559+00.00 TO STA. 574+00.00      | ACROSS TEMP. SLOPES RT. & MEDIAN                    |                             |                            | 1.53                       |
| STA. 559+75.00                        | ACROSS TEMP. DITCH RT.                              |                             | 7                          |                            |
| STA. 561+00.00                        | ACROSS TEMP. DITCH RT.                              |                             | 7                          |                            |
| STA. 566+50.00                        | ACROSS DITCH LT. AND TEMP. MEDIAN DITCH             |                             | 14                         |                            |
| STA. 568+00.00                        | ACROSS DITCH LT. & RT. AND TEMP. DITCH RT. & MEDIAN |                             | 42                         |                            |
| STA. 569+50.00                        | ACROSS DITCH LT. & RT. AND TEMP. DITCH RT. & MEDIAN |                             | 42                         |                            |
| STA. 571+00.00                        | ACROSS DITCH LT. & RT. AND TEMP. DITCH RT. & MEDIAN |                             | 42                         |                            |
| STA. 572+50.00                        | ACROSS DITCH LT. & RT. AND TEMP. DITCH RT. & MEDIAN |                             | 42                         |                            |
| STA. 574+00.00                        | ACROSS DITCH LT. & RT. AND TEMP. DITCH RT. & MEDIAN |                             | 42                         |                            |
| STA. 574+00.00 TO STA. 589+00.00      | ACROSS TOE LT.                                      | 617                         |                            |                            |
| STA. 574+00.00 TO STA. 589+00.00      | ACROSS TEMP. SLOPES RT. & MEDIAN                    |                             |                            | 0.48                       |
| STA. 575+50.00                        | ACROSS TEMP. MEDIAN DITCH                           |                             | 7                          |                            |
| STA. 576+00.00                        | ACROSS DITCH LT. & RT. AND TEMP. DITCH RT.          |                             | 35                         |                            |
| STA. 577+50.00                        | ACROSS DITCH RT. AND TEMP. DITCH RT. & MEDIAN       |                             | 28                         |                            |
| STA. 579+00.00                        | ACROSS DITCH RT. AND TEMP. DITCH RT. & MEDIAN       |                             | 28                         |                            |
| STA. 580+18.00                        | ACROSS DITCH LT.                                    |                             | 14                         |                            |
| STA. 580+50.00                        | ACROSS DITCH RT. AND TEMP. DITCH RT. & MEDIAN       |                             | 28                         |                            |
| STA. 581+50.00                        | ACROSS DITCH RT. AND TEMP. DITCH RT. & MEDIAN       |                             | 28                         |                            |
| STA. 582+50.00                        | ACROSS DITCH RT. AND TEMP. DITCH RT.                |                             | 21                         |                            |
| STA. 589+00.00 TO STA. 604+00.00      | ALONG TOE LT. & RT.                                 | 1,514                       |                            |                            |
| STA. 589+00.00 TO STA. 604+00.00      | ACROSS TEMP. SLOPES RT. & MEDIAN                    |                             |                            | 0.71                       |
| STA. 592+76.00                        | ACROSS DITCH LT. AND TEMP. MEDIAN DITCH             |                             | 28                         |                            |
| STA. 594+50.00                        | ACROSS DITCH LT. AND TEMP. MEDIAN DITCH             |                             | 28                         |                            |
| STA. 596+00.00                        | ACROSS DITCH LT. AND TEMP. MEDIAN DITCH             |                             | 28                         |                            |
| STA. 597+40.00                        | ACROSS TEMP. MEDIAN DITCH                           |                             | 7                          |                            |
| STA. 597+50.00                        | ACROSS DITCH LT.                                    |                             | 21                         |                            |
| STA. 597+60.00                        | ACROSS TEMP. MEDIAN DITCH                           |                             | 7                          |                            |
| STA. 599+00.00                        | ACROSS DITCH LT. AND TEMP. MEDIAN DITCH             |                             | 28                         |                            |
| STA. 600+50.00                        | ACROSS DITCH LT.                                    |                             | 21                         |                            |
| STA. 602+00.00                        | ACROSS DITCH LT. AND TEMP. MEDIAN DITCH             |                             | 21                         |                            |
| STA. 603+30.00                        | ACROSS TEMP. MEDIAN DITCH                           |                             | 7                          |                            |
| STA. 603+50.00                        | ACROSS DITCH LT. & RT. AND TEMP. MEDIAN DITCH       |                             | 35                         |                            |
| STA. 604+00.00 TO STA. 619+00.00      | ACROSS TOE LT.                                      | 579                         |                            |                            |
| STA. 604+00.00 TO STA. 619+00.00      | ACROSS TEMP. SLOPES RT. & MEDIAN                    |                             |                            | 0.84                       |
| STA. 605+00.00                        | ACROSS DITCH LT. & RT. AND TEMP. DITCH RT. & MEDIAN |                             | 42                         |                            |
| STA. 606+50.00                        | ACROSS DITCH LT. & RT. AND TEMP. DITCH RT. & MEDIAN |                             | 42                         |                            |
| STA. 608+00.00                        | ACROSS DITCH LT. & RT. AND TEMP. DITCH RT. & MEDIAN |                             | 42                         |                            |
| STA. 609+60.00                        | ACROSS DITCH RT. AND TEMP. DITCH RT.                |                             | 21                         |                            |
| STA. 611+00.00                        | ACROSS DITCH RT. AND TEMP. DITCH RT.                |                             | 21                         |                            |
| STA. 612+50.00                        | ACROSS DITCH RT. AND TEMP. DITCH RT.                |                             | 21                         |                            |
| STA. 614+50.00                        | ACROSS DITCH RT. AND TEMP. DITCH RT.                |                             | 21                         |                            |
| STA. 616+00.00                        | ACROSS TEMP. DITCH RT.                              |                             | 7                          |                            |
| STA. 617+50.00                        | ACROSS TEMP. DITCH RT.                              |                             | 7                          |                            |
| STA. 619+00.00                        | ACROSS TEMP. DITCH RT.                              |                             | 7                          |                            |
| STA. 619+00.00 TO STA. 623+75.00      | ACROSS TOE RT.                                      | 355                         |                            |                            |
| STA. 619+00.00 TO STA. 623+75.00      | ACROSS TEMP. SLOPES RT.                             |                             |                            | 0.12                       |
| <b>TOTALS</b>                         |   | 4,025                       | 924                        | 3.93                       |

| SUMMARY OF DRIVES    |                 |              |           |           |                         |                  |                |  |  |
|----------------------|-----------------|--------------|-----------|-----------|-------------------------|------------------|----------------|--|--|
| STATION AND LOCATION | WIDTH x LENGTH  | TYPE         | RADI (R1) | RADI (R2) | * 4" TBSC TYPE E 402(E) | TACK COAT 407(B) | PRIME COAT 408 | 3" SUPERPAVE. TYPE S3 (PG 64-22 OK) 411(B) | 2" SUPERPAVE. TYPE S4 (PG 64-22 OK) 411(C) |
|                      |                 |              |           |           | TON                     | GAL.             | GAL.           | TON  | TON  |
| STA. 574+58 - LT.    | 12.00' x 40.00' | SL. RETURN Δ | 25'       | 25'       | 55.29                   |                  |                |  |  |
| STA. 574+71 - RT.    | 21.00' x 94.66' | 1            | 40'       | 40'       | 121.14                  | 49.64            | 117.13         | 55.91                                      | 36.93                                      |
| STA. 609+10 - RT.    | 16.00' x 75.14' | 1            | 10'       | 10'       | 64.12                   | 21.11            | 50.50          | 23.94                                      | 15.63                                      |
| STA. 613+98 - RT.    | 14.00' x 59.17' | SL. RETURN Δ | 50'       | 25'       | 50.07                   |                  |                |  |  |
| STA. 613+97 - LT.    | 12.00' x 29.08' | 1            | 25'       | 25'       | 23.47                   | 10.36            | 24.43          | 11.67                                      | 7.71                                       |
| STA. 621+35 - LT.    | 12.00' x 37.82' | 1            | 10'       | 10'       | 24.20                   | 8.52             | 20.75          | 9.75                                       | 6.27                                       |
| <b>TOTALS</b>        |                 |              |           |           | 338.29                  | 89.63            | 212.81         | 101.27                                     | 66.54                                      |

\* TBSC QUANTITIES ARE FOR TEMPORARY DRIVES

Δ SURFACING QUANTITIES INCLUDED IN MAINLINE SURFACING QUANTITIES

| SUMMARY OF EROSION CONTROL       |                          |                           |                              |                                |
|----------------------------------|--------------------------|---------------------------|------------------------------|--------------------------------|
| STATION EXTENTS                  | LOCATION AND DESCRIPTION | SOLID SLAB SODDING 230(A) | TYPE 1-A PLAIN RIPRAP 601(B) | TYPE 1-A FILTER BLANKET 601(C) |
|                                  |                          | S.Y.                      | TON                          | TON                            |
| <b>SH 30</b>                     |                          |                           |                              |                                |
| STA. 553+07.00 TO STA. 559+00.00 | LT. & RT. OF ROADWAY     | 5,098.21                  |                              |                                |
| STA. 559+00.00 TO STA. 574+00.00 | LT. & RT. OF ROADWAY     | 24,733.09                 | 11.66                        | 2.78                           |
| STA. 574+00.00 TO STA. 589+00.00 | LT. & RT. OF ROADWAY     | 16,561.48                 | 2.21                         | 1.05                           |
| STA. 589+00.00 TO STA. 604+00.00 | LT. & RT. OF ROADWAY     | 52,266.31                 |                              |                                |
| STA. 604+00.00 TO STA. 619+00.00 | LT. & RT. OF ROADWAY     | 17,498.45                 | 11.04                        | 3.94                           |
| STA. 619+00.00 TO STA. 623+75.14 | LT. & RT. OF ROADWAY     | 3,010.49                  |                              |                                |
| <b>TOTALS</b>                    |                          | 119,168.03                | 24.91                        | 7.77                           |

| SUMMARY OF REMOVAL QUANTITIES    |                  |                                     |                                    |                             |                        |
|----------------------------------|------------------|-------------------------------------|------------------------------------|-----------------------------|------------------------|
| STATION EXTENTS                  | REMOVAL OF FENCE | REMOVAL OF CONCRETE PAVEMENT 619(B) | REMOVAL OF ASPHALT PAVEMENT 619(B) | REMOVAL OF GUARDRAIL 619(B) | SAVING PAVEMENT 619(C) |
|                                  | L.F.             | S.Y.                                | S.Y.                               | L.F.                        | L.F.                   |
| <b>S.H. 30</b>                   |                  |                                     |                                    |                             |                        |
| STA. 552+68.00 TO STA. 574+00.00 | 4,349.34         |                                     | 8,450.61                           |                             | 2,119.41               |
| STA. 574+00.00 TO STA. 604+00.00 | 4,603.68         | 5.05                                | 9,951.34                           | 525.56                      | 1,678.38               |
| STA. 604+00.00 TO STA. 623+73.00 | 2,759.58         |                                     | 7,846.43                           |                             | 2,012.30               |
| <b>TOTALS</b>                    | 11,712.60        | 5.05                                | 26,248.38                          | 525.56                      | 5,810.09               |

• FOR INFORMATION PURPOSES ONLY. PRICE BID TO BE INCLUDED IN OTHER ITEMS.

**SUMMARY SHEET**