

| SUMMARY OF DISTURBED DRAINAGE AREAS |                    |                            |                                     |                        |  |  |                      |
|-------------------------------------|--------------------|----------------------------|-------------------------------------|------------------------|--|--|----------------------|
| ALIGNMENT                           | DISTURBED AREA NO. | OUTFLOW LOCATION (STATION) | DISTURBED AREA (STATION TO STATION) | DIRECTION FROM OUTFALL | DESCRIPTION OF AREA                                | EROSION CONTROL MEASURES                                       | DISTURBED AREA (AC.) |
| SH 30                               | D1                 | 566+24.83                  | STA. 553+07 TO STA. 566+75          | S.                     | ROADWAY AND DITCH RT.                              | SILT FENCE, SILT DIKE, SOLID SLAB SOD, AND VEGETATIVE MULCHING | 1.53                 |
| SH 30                               | D2                 | 566+51.00                  | STA. 563+30 TO STA. 567+00          | E.                     | ROADWAY AND FORESLOPE LT.                          | SILT FENCE, SILT DIKE, AND SOLID SLAB SOD                      | 0.56                 |
| SH 30                               | D3                 | 575+75.00                  | STA. 563+79.97 TO STA. 576+00       | S.                     | MEDIAN DITCH BETWEEN PROPOSED AND EXISTING ROADWAY | SILT DIKE AND VEGETATIVE MULCH                                 | 0.60                 |
| SH 30                               | D4                 | 574+71.00                  | STA. 566+75 TO STA. 574+71          | S.                     | ROADWAY AND DITCH RT.                              | SILT DIKE, SOLID SLAB SOD, AND VEGETATIVE MULCH                | 1.48                 |
| SH 30                               | D5                 | 574+34.00                  | STA. 567+00 TO STA. 574+58          | S. & E.                | ROADWAY AND DITCH LT.                              | SILT DIKE AND SOLID SLAB SOD                                   | 1.10                 |
| SH 30                               | D6                 | 580+18.00                  | STA. 574+58 TO STA. 582+26          | S. & E.                | ROADWAY, DITCH LT., AND SPUR DIKE                  | SILT FENCE, SILT DIKE, AND SOLID SLAB SOD                      | 1.85                 |
| SH 30                               | D7                 | 582+62.00                  | STA. 574+71 TO STA. 582+69          | S.                     | ROADWAY AND DITCH RT.                              | SILT DIKE, SOLID SLAB SOD, AND VEGETATIVE MULCH                | 1.17                 |
| SH 30                               | D8                 | 581+50.00                  | STA. 576+00 TO STA. 582+62          | S.                     | MEDIAN DITCH BETWEEN PROPOSED AND EXISTING ROADWAY | SILT DIKE AND VEGETATIVE MULCH                                 | 0.50                 |
| SH 30                               | D9                 | 592+76.00                  | STA. 591+27 TO STA. 609+00          | N. & E.                | ROADWAY, DITCH LT., AND SPUR DIKE                  | SILT FENCE, SILT DIKE, AND SOLID SLAB SOD                      | 4.28                 |
| SH 30                               | D10                | 597+50.00                  | STA. 592+03 TO STA. 601+00          | N. & S.                | MEDIAN DITCH BETWEEN PROPOSED AND EXISTING ROADWAY | SILT DIKE AND VEGETATIVE MULCH                                 | 0.65                 |
| SH 30                               | D11                | N/A                        | STA. 592+03 TO STA. 609+10          | S. & W.                | ROADWAY AND DITCH RT.                              | SILT FENCE, SILT DIKE, SOLID SLAB SOD, AND VEGETATIVE MULCHING | 2.58                 |
| SH 30                               | D12                | 603+38.00                  | STA. 601+00 TO STA. 613+00          | N. & S.                | MEDIAN DITCH BETWEEN PROPOSED AND EXISTING ROADWAY | SILT DIKE AND VEGETATIVE MULCH                                 | 0.42                 |
| SH 30                               | D13                | N/A                        | STA. 609+00 TO STA. 614+80          | E.                     | ROADWAY AND FORESLOPE LT.                          | SILT FENCE AND SOLID SLAB SOD                                  | 0.60                 |
| SH 30                               | D14                | 609+10.00                  | STA. 609+10 TO STA. 613+98          | N.                     | ROADWAY AND DITCH RT.                              | SILT DIKE, SOLID SLAB SOD, AND VEGETATIVE MULCH                | 0.58                 |
| SH 30                               | D15                | 613+98.00                  | STA. 613+98 TO STA. 623+75          | N.                     | ROADWAY AND DITCH RT.                              | SILT FENCE, SILT DIKE, SOLID SLAB SOD, AND VEGETATIVE MULCHING | 0.87                 |
| TOTAL                               |                    |                            |                                     |                        |  |  | 18.77                |

**NOTES:**

1) SEE SEQUENCE OF CONSTRUCTION NOTES SHEET NO. 5 FOR PLACING SOLID SLAB SODDING.

**SUMMARY OF DISTURBED DRAINAGE AREAS**