

SUMMARY OF FENCE		
STATION EXTENTS AND LOCATION	FENCE - STYLE SWF (5 BARBED WIRE) 624(C)	FENCE - STYLE SWF (4 BARBED WIRE) 624(C)
	L.F.	L.F.
S.H. 74D		
STA. 66+76.00 RT.	33.00	
STA. 66+76.00 LT.	38.00	
STA. 68+48.00 LT.		167.00
STA. 68+48.00 RT.	50.00	
TOTALS	121.00	167.00

SUMMARY OF TEMPORARY SEDIMENT CONTROL				
STATION EXTENTS	LOCATION AND DESCRIPTION	TYPE	TEMPORARY SILT FENCE 221(C)	TEMPORARY FIBER LOG 221(K)
			L.F.	L.F.
S.H. 74D				
STA. 63+88.00 TO STA. 66+55.00	FIBER LOG LT. & RT.			412
STA. 63+88.00 TO STA. 71+00.00	SILT FENCE RT.		611	
STA. 68+68.00 TO STA. 71+00.00	FIBER LOG LT. & RT.			466
STA. 64+50.00 TO STA. 71+00.00	SILT FENCE LT.		512	
EW 69				
STA. 313+01.83 TO STA. 316+90.59	FIBER LOG LT.			254
STA. 312+55.29 TO STA. 316+91.33	FIBER LOG RT.			367
TOTALS			1,123	1,499

SUMMARY OF SURFACING				
STATION EXTENTS	STABILIZED SUBGRADE 307(K)	TACK COAT 407(B)	SUPERPAVE, TYPE S3 (PG 64-22 OK) 411(B)	SUPERPAVE, TYPE S4 (PG 64-22 OK) 411(C)
	S.Y.	GAL.	TONS	TONS
S.H. 74D				
STA. 63+00.00 TO STA. 71+00.00	1,602.29	498.19	466.53	193.63
DETOUR				
STA. 313+02.00 TO STA. 316+91.00		396.96	258.72	114.64
TOTALS	1,602.29	895.15	725.25	308.27

NOTE: QUANTITIES INCLUDE ASPHALT COAT QUANTITIES FOR GUARDRAIL WIDENING

SUMMARY OF GUARDRAIL					
STATION EXTENTS AND LOCATION	GUARDRAIL CURBING 623	GUARDRAIL W-BEAM SINGLE 623(A)	GUARDRAIL ANCHOR UNIT (TYPE D-BF) 623(F)	GUARDRAIL END TREATMENT (31") 623(G)	GUARDRAIL DELINEATORS (TYPE 2, CODE 1) 853
	EA.	L.F.	EA.	EA.	EA.
S.H. 74D					
STA. 64+76.75 TO STA. 66+64.25 - RT.	1	112.50	1	1	5
STA. 65+76.75 TO STA. 66+64.25 - LT.	1	12.50	1	1	3
STA. 68+59.75 TO STA. 69+59.75 - RT.	1	25.00	1	1	3
STA. 68+59.75 TO STA. 69+97.25 - LT.	1	62.50	1	1	4
EW 69					
STA. 313+66.03 TO STA. 314+41.03 - LT.	1		1	1	3
STA. 313+50.96 TO STA. 314+25.96 - RT.	1		1	1	3
STA. 314+89.03 TO STA. 315+64.03 - LT.	1		1	1	3
STA. 314+73.96 TO STA. 315+48.96 - RT.	1		1	1	3
TOTALS	8	212.50	8	8	27

NOTE: ASPHALT AND PRIME COAT QUANTITIES FOR GUARDRAIL WIDENING ARE INCLUDED IN THE MAINLINE SURFACING QUANTITIES

SUMMARY OF REMOVAL QUANTITIES				
STATION EXTENTS	REMOVAL OF FENCE	REMOVAL OF ASPHALT PAVEMENT 619(B)	REMOVAL OF GUARDRAIL 619(B)	SAWING PAVEMENT 619(C)
	L.F.	S.Y.	L.F.	L.F.
S.H. 74D				
STA. 64+50.00 TO STA. 71+00.00	391.00	1,296.00	211.00	44.00
EW 69				
STA. 314+18.74 TO STA. 314+98.79		98.00		39.00
TOTALS	391.00	1,394.00	211.00	83.00

• FOR INFORMATION PURPOSES ONLY. PRICE BID TO BE INCLUDED IN OTHER ITEMS.
 φ TO BECOME THE PROPERTY OF LOGAN COUNTY.

SUMMARY OF DRIVES					
STATION AND LOCATION	WIDTH x LENGTH	TYPE	RADII (R1)	RADII (R2)	4" TBSC TYPE E 402(E)
					TON
EW 69					
STA. 313+37 - LT.	16.00' x 23.77'	1	20'	20'	14.24
TOTALS					14.24

SUMMARY OF EARTHWORK QUANTITIES				
STATION EXTENTS	UNCLASSIFIED EXCAVATION 202(A)	EMBANKMENT +15%	EXCESS EXCAVATION	UNCLASSIFIED BORROW 202(D)
	C.Y.	C.Y.	C.Y.	C.Y.
S.H. 74D				
STA. 63+88.00 TO STA. 71+00.00	179	2,373		2,194
EW 69				
STA. 312+55.37 TO STA. 316+91.00	325	623		298
TOTALS	504	2,996		2,492

SUMMARY OF EROSION CONTROL		
STATION EXTENTS	LOCATION AND DESCRIPTION	SOLID SLAB SODDING 230(A)
		S.Y.
S.H. 74D		
STA. 63+88.00 TO STA. 66+55.00	SOD LT. & RT.	859.00
STA. 68+68.00 TO STA. 71+00.00	SOD LT. & RT.	1,675.00
EW 69		
STA. 312+55.29 TO STA. 314+09.85	SOD LT. & RT.	172.00
STA. 314+85.85 TO STA. 316+91.00	SOD LT. & RT.	427.00
TOTALS		3,133.00

LOGAN COUNTY S.H. 74D