

**GENERAL CONSTRUCTION NOTES**

- (C-152) ALL BROKEN CONCRETE, WASTE MATERIAL, AND DEBRIS SHALL BECOME THE PROPERTY OF THE CONTRACTOR, AND SHALL BE REMOVED FROM THE LIMITS OF THE PROJECT AND DISPOSED OF IN AN AREA APPROVED BY THE ENGINEER. NO PAYMENT WILL BE MADE FOR THE DISPOSAL OF THIS MATERIAL.
- (C-155) THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE HE MAY INFLICT TO THE EXISTING UNDERGROUND UTILITIES WITHIN THE PROJECT AREA AS A RESULT OF HIS DIGGING, TRENCHING, BORING, ETC..... PRIOR TO DIGGING NEAR THE UTILITIES, THE CONTRACTOR SHALL CALL FOR A LIST OF ALL UNDERGROUND FACILITIES REGISTERED IN THE AREA OF CONSTRUCTION LISTED WITH THE FOLLOWING AGENCIES:  
THE "OKIE" NOTIFICATION CENTER 811 OR (405)522-6543 OR WWW.CALLOKIE.COM OR THE LOCAL COUNTY CLERK'S OFFICE.

**PAY QUANTITY NOTES**

- (TS-24) QUANTITY SHOWN INCLUDES 2,780 L.F. TRAFFIC STRIPE (MULTI-POLYMER) (WHITE) AND 1,670 L.F. TRAFFIC STRIPE (MULTI-POLYMER) (YELLOW) AND WILL BE MEASURED BY THE LINEAR FOOT OF FOUR INCH (4")WIDE TRAFFIC STRIPE.
- (TS-33) INCLUDED IN THIS PAY ITEM IS ALL HARDWARE ASSOCIATED WITH PROPERLY ANCHORING AND MOUNTING THE HIGHWAY SIGN IN ACCORDANCE WITH O.D.O.T. PLANS AND STANDARD DRAWINGS SSA1-1 AND SSP1-1- (LATEST REVISION).
- (1) PRICE BID FOR THIS ITEM SHALL INCLUDE THE REMOVAL OF EXISTING SIGNS ON THIS PROJECT. ALL REMOVED SIGNS, POSTS AND FOOTINGS SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE PROJECT, AS APPROVED BY THE ENGINEER.

**PAY QUANTITIES**

0300 SIGNING AND STRIPING			
ITEM	DESCRIPTION	UNIT	TOTAL
850(A) 8110	SHEET ALUMINUM SIGNS (1)	SF	24.75
851(C) 8324	2" SQUARE TUBE POST (TS-33)	LF	46.00
856(A) 8530	TRAFFIC STRIPE (MULTI-POLYMER)(4" WIDE) (TS-24)	LF	4450.00

**SIGN SUMMARY**

SHEET NO.	ITEM NO.	APPROXIMATE LOCATION		SIGN TYPE	POSTS				FOOTINGS			SIGN AREA			REMARKS
					TYPE	A L.F.	B L.F.	SPACING	DESIGN NO.	CONCRETE C.Y.	STEEL LBS.	SHEET S.F.	PANEL S.F.	PANEL OVERHEAD S.F.	
	1	66+24	(SH 74D)	W4-1(L), W13-1P(45)	2" SQ. TUBE POST	12.0						8.50			
	2	66+53	(SH 74D)	I-3 (ROCK CREEK)	2" SQ. TUBE POST	11.0						5.00			
	3	68+81	(SH 74D)	I-3 (ROCK CREEK)	2" SQ. TUBE POST	11.0						5.00			
	4	69+80	(SH 74D)	W1-2(L)	2" SQ. TUBE POST	12.0						6.25			
<b>TOTAL</b>					<b>2" SQ. TUBE POST</b>	<b>46.0</b>						<b>24.75</b>			

