

**TRAFFIC CONSTRUCTION PAY QUANTITY NOTES**

- (TR-24) ALL TRAFFIC SIGNAL EQUIPMENT REMOVED SHALL BECOME THE PROPERTY OF THE CITY. THE CONTRACTOR SHALL NEATLY STACK SUCH REMOVED MATERIAL AT A LOCATION ON THE JOB SITE AS DIRECTED BY THE ENGINEER. THE PRICE BID SHALL INCLUDE THE REMOVAL OF ALL FOOTINGS BELOW GROUND LEVEL OR AS DIRECTED BY THE ENGINEER. FOOTINGS TO BECOME THE PROPERTY OF THE CONTRACTOR.
- (TC-1) THE CONTRACTOR SHALL FURNISH AND INSTALL SUCH LIGHTS, SIGNS, BARRICADES, AND PROVIDE FLAGGERS NECESSARY FOR THE CONTROL, SAFETY AND MAINTENANCE OF TRAFFIC WHEN INSTALLING, RELOCATING, OR DELIVERING PORTABLE LONGITUDINAL BARRIER.
- (TC-26) ALL CONSTRUCTION TRAFFIC CONTROL WILL BE IMPLEMENTED ACCORDING TO CONSTRUCTION PLANS, AND INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND COMPLIANT WITH APPLICABLE O.D.O.T. STANDARD DRAWINGS. PRICE BID FOR THIS ITEM SHALL BE PAYMENT IN FULL FOR THE INSTALLATION, MAINTENANCE AND SUBSEQUENT REMOVAL OF ALL NECESSARY CONSTRUCTION TRAFFIC CONTROL DEVICES REQUIRED FOR COMPLETION OF THE PROJECT.
- ALL SIGNS AND BARRICADES WHICH ARE SHOWN WITH TYPE 'A' LIGHTS IN THE STANDARD DRAWINGS SHALL HAVE THE CORRESPONDING LIGHT ATTACHED DURING NON-DAYLIGHT HOURS.
- (TC-28) INCLUDED IN THIS ITEM ARE ALL S.C.S. (SPECIAL CONSTRUCTION SIGNING) SIGNS WHICH ARE BETWEEN 0.00 S.F. AND 6.25 S.F. ALSO INCLUDED IN THIS ITEM SHALL BE THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF THESE SIGNS.
- (TC-29) INCLUDED IN THIS ITEM ARE ALL S.C.S. (SPECIAL CONSTRUCTION SIGNING) SIGNS WHICH ARE BETWEEN 6.26 S.F. AND 15.99 S.F. ALSO INCLUDED IN THIS ITEM SHALL BE THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF THESE SIGNS.
- (TC-30) INCLUDED IN THIS ITEM ARE ALL S.C.S. (SPECIAL CONSTRUCTION SIGNING) SIGNS WHICH ARE BETWEEN 16.00 S.F. AND 32.99 S.F. ALSO INCLUDED IN THIS ITEM SHALL BE THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF THESE SIGNS.
- (TC-33) ALL CONSTRUCTION WORK ZONE SIGNS SHALL HAVE FLUORESCENT SHEETING. THE FLUORESCENT SHEETING SHALL MEET THE REQUIREMENTS OF ASTM D4956 (LATEST REVISION)
- THE MANUFACTURER SHALL FURNISH A TYPE 'D' CERTIFICATION IN ACCORDANCE WITH O.D.O.T. STANDARD SPECIFICATIONS (CURRENT EDITION) SUBSECTION 106.04. THE CERTIFICATION SHALL INCLUDE TEST RESULTS ON MATERIAL SUBMITTED FOR APPROVAL.
- (TC-70) THIS ITEM IS AN ESTIMATED QUANTITY TO BE USED AS DEEMED NECESSARY BY THE ENGINEER.
- (TC-84) 310 CONSTRUCTION CALENDAR DAYS WERE USED TO COMPUTE THE SIGN DAY PAY ITEMS. THE AMOUNT OF CALENDAR DAYS USED TO COMPUTE THE SIGN DAY PAY ITEMS IS AN ESTIMATED QUANTITY ONLY, BASED ON THE CURRENT O.D.O.T. STANDARDS AND SUGGESTED CONSTRUCTION SEQUENCE FOR THIS PROJECT. THESE ESTIMATED SIGN DAY QUANTITIES MAY CHANGE AS THE PROJECT'S CONSTRUCTION TRAFFIC CONTROL IS MODIFIED DURING CONSTRUCTION.

**TRAFFIC CONSTRUCTION GENERAL NOTES**

THE CONTRACTOR SHALL COORDINATE WITH OKLAHOMA CITY PUBLIC WORKS DEPARTMENT TO OBTAIN A WORK ZONE PERMIT PRIOR TO CLOSING OR RESTRICTING TRAFFIC ON ANY CITY STREETS."

THE CONTRACTOR SHALL COMPLETE THE OKLAHOMA CITY "APPLICATION FOR WORK PERMIT" FORM. SUBMIT COMPLETED FORM TO:

DEBBIE MILLER ASSISTANT CITY ENGINEER  
CITY OF OKLAHOMA CITY  
PUBLIC WORKS DEPARTMENT  
420 W MAIN, 7TH FLOOR  
OKC, OK. 73102  
DEBBIE.MILLER@OKC.GOV

RICK HOWLAND  
OKLAHOMA CITY CONSTRUCTION RESIDENCY  
OKLAHOMA DEPT. OF TRANSPORTATION  
701 S.E. 82ND  
OKLAHOMA CITY, OK. 73149  
(405) 522-5576

PLEASE SUBMIT THE ABOVE FORM VIA U.S. MAIL OR E-MAIL TWO (2) WEEKS BEFORE CLOSING ANY STREET OR RAMP FOR THE PURPOSE OF EMERGENCY RESPONSE PERSONNEL NOTIFICATION.

CONTRACTOR SHALL COORDINATE ALL ROAD AND LANE CLOSURES WITH THE CITY OF OKLAHOMA CITY TO MINIMIZE IMPACT TO SPECIAL EVENTS IN THE PROJECT AREA

**TRAFFIC SPECIAL PAY QUANTITY NOTES**

- (1) PRICE BID TO INCLUDE COST TO REMOVE AND DELIVER TO THE CITY, ALL TRAFFIC CONTROL EQUIPMENT.

TRAFFIC CONTROL 0300		SUMMARY OF QUANTITIES			JP# 17428(88)
ITEM NO.	DP NO.	DESCRIPTION	NOTES	UNIT	QUANTITY
805(A)	8726	(PL) REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	(TR-24), (1)	LSUM	1.00
880(B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	(TC-26,33,84)	SD	3255.00
880(B)	8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	(TC-26,33,84)	SD	5890.00
880(B)	8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	(TC-26,33,84)	SD	852.50
880(C)	8842	CONSTRUCTION BARRICADES (TYPE III)	(TC-21,26,84)	SD	5967.50
880(F)	8878	DRUMS	(TC-21,26,84)	SD	2557.50

TRAFFIC CONTROL & SEQUENCING							
Phase / Stage		Barricade (Type III)	Signs 0 to 6.25 SF	Signs 6.26 to 15.99 SF	Signs 16.00 to 32.99 SF	Type "A" Lights	Drums
		880(C)	880(B)	880(B)	880(B)	880(E)	880(F)
		EA	EA	EA	EA	EA	EA
Phase 1		11	8	10	3	22	
Phase 2		16	12	15	3	32	33
Phase 3		18	14	19	3	36	
Phase 4		32	8	32	2	64	
All Phases							
Phase	Sign Days	S.D.	S.D.	S.D.	S.D.	S.D.	S.D.
Phase 1	77.5	853	620	775	233	1,705	-
Phase 2	77.5	1,240	930	1,163	233	2,480	2,558
Phase 3	77.5	1,395	1,085	1,473	233	2,790	-
Phase 4	77.5	2,480	620	2,480	155	4,960	-
All Phases	232.5	-	-	-	-	-	-
TOTAL	310	5,968	3,255	5,890	853	11,935	2,558

PRINT DATE: 9/11/2017 T:\1024-05\Drawings\Traffic\Sum-Tr.dgn

OKLAHOMA CITY BOULEVARD OKLAHOMA CO.

DESIGN	KBA	MMPC	OKLAHOMA DEPARTMENT OF TRANSPORTATION
DRAWN	ISFM	RWH	
CHECKED	KBA		
APPROVED			
SQUAD	MacArthur		

**SUMMARY OF PAY QUANTITIES (TRAFFIC)**

STATE JOB NO. 17428(88) SHEET NO. 9