

SANITARY SEWER 0500			PAY QUANTITIES			JP# 17428(88)
OKC STD.	ITEM NO.		DESCRIPTION	NOTES	UNIT	QUANTITY
626	611(A)	2659	MANHOLE (6' DIAMETER)		EA	3.00
626	611(B)	2682	ADD'L DEPTH IN MANHOLE (6' DIAMETER)		VF	12.00
628	612(A)	0641	MANHOLES ADJUST TO GRADE	(1)	EA	11.00
610	615(A)	6134	24" POLYVINYL CHLORIDE (PVC) PIPE	(2)	LF	250.00
625	615(D)	0410	SEWER LEAKAGE TEST(> OR = 24" DIAM.)		LF	250.00
623	615(E)	0475	DEFLECTION TEST (> OR = 24" DIAMETER)		LSUM	1.00
618	615(F)	0600	SEWER FLOW CONTROL		LSUM	1.00

NOTE: CONTRACTOR PERFORMING THIS WORK SHALL BE PRE-QUALIFIED BY THE CITY OF OKLAHOMA CITY.

PAY ITEM NOTES

- (1) PRICE BID FOR THIS ITEM SHALL INCLUDE COST TO ADJUST EXISTING MANHOLE TO GRADE (COMPLETE) INCLUDING MANHOLE FRAME AND COVER OF THE SIZE REQUIRED FOR EXIST MANHOLE. CONTRACTOR TO VERIFY ELEVATION ADJUSTMENT REQUIRED TO MEET TOP OF PROPOSED PAVING SURFACE.
- (2) PRICE BID TO INCLUDE THE COST OF ALL TRENCHING AND BEDDING.

GENERAL CONSTRUCTION NOTES

ALL CONSTRUCTION OF WATER AND SANITARY SEWER SHALL BE IN ACCORDANCE WITH THE CITY OF OKLAHOMA CITY STANDARD SPECIFICATIONS FOR CONSTRUCTION OF PUBLIC IMPROVEMENTS. ALL CONSTRUCTION MATERIALS PERTAINING TO WATER AND SANITARY SEWER SHALL BE APPROVED BY THE CITY OF OKLAHOMA CITY.

THE CONTRACTOR SHALL KEEP THE OPEN TRENCH DRAINED. COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

NO PAYMENT WILL BE MADE FOR THE REMOVAL OF ABANDONED UTILITY PIPE LINES THAT INTERFERE WITH CONSTRUCTION. ALL COST TO BE INCLUDED IN OTHER ITEMS.

ALL WORK AND/OR MATERIALS NOT CLASSIFIED AS A "CONTRACT PAY ITEM" SHALL BE CONSIDERED INCIDENTAL AND THE COST THEREOF SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEMS WHICH ARE CLASSIFIED FOR PAYMENT.

(CAUTION) THE LOCATION OF ALL UTILITIES AS SHOWN ARE APPROXIMATE. DUE TO RELOCATIONS PLANNED OR PRESENTLY UNDER CONSTRUCTION THERE ARE SOME UTILITIES THAT WILL BE RELOCATED AND NOT SHOWN ON THESE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO ALL UTILITIES.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE HE MAY INFLICT TO THE EXISTING UNDERGROUND UTILITIES WITHIN THE PROJECT AREA AS A RESULT OF HIS DIGGING, TRENCHING, BORING, ETC., PRIOR TO DIGGING NEAR THE UTILITIES. THE CONTRACTOR SHALL CALL FOR A LIST OF ALL UNDER GROUND FACILITIES REGISTERED IN THE AREA OF CONSTRUCTION LISTED WITH THE FOLLOWING AGENCIES:
THE "OKIE" NOTIFICATION CENTER (405) 840-5021 OR 1-800-522-6543.

DEPTH AND LOCATION OF EXISTING UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.

IN THE EVENT THE EXISTING SECTION LINE ROADS OR PUBLIC ROAD ARE IN ANY WAY DISTURBED AS A RESULT OF THE CONTRACTORS EFFORTS, IT SHALL BE THE RESPONSIBILITY OF SAID CONTRACTOR TO RETURN THE AREA TO ITS ORIGINAL CONDITION WITH NO ADDITIONAL COMPENSATION AS DIRECTED AND TO THE SATISFACTION OF THE ENGINEER.

A CONTRACTOR'S PROGRESS SCHEDULE SHALL BE PREPARED IN ACCORDANCE WITH SECTION 108A OF THE 1999 STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

ALL MATERIAL REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF IN A MANNER APPROVED BY THE ENGINEER.

THE MATERIAL USED FOR BACKFILLING OF THE TRENCHES ABOVE THE STANDARD BEDDING PIPE INSTALLATION SHALL BE AS PER ODOT ROADWAY STANDARD SPB-1

OKLAHOMA CITY BOULEVARD OKLAHOMA CO.

DESIGN	KBA	MMPC	OKLAHOMA DEPARTMENT OF TRANSPORTATION SUMMARY OF PAY QUANTITIES AND NOTES SANITARY SEWER LINE RELOCATION (ROADWAY) STATE JOB NO. 17428(88) SHEET NO. 11
DRAWN	ISFM	RWH	
CHECKED	KBA		
APPROVED			
SQUAD	MacArthur		