

SUMMARY OF REMOVAL																				
P&P Sht. No.	Location CRL Station to Station	Removal of Asphalt Pavement	Removal of Concrete Pavement	Removal of Curb and Gutter	Removal of Sidewalk	Sawing Pavement	Removal of Traffic Signal Equipment	Manholes Adjust To Grade	Valve Box Adjust To Grade	Fire Hydrant Reset	Removal of Structures & Obstructions									
		619(B)	619(B)	619(B)	619(B)	619(C)	805(A)	612(A)	612(E)	612(G)	Fences	Manholes	Inlets	Pipes			Trees	Signs		
		619(B) SY	619(B) SY	619(B) LF	619(B) SY	619(C) LF	**L.SUM	612(A) EA	612(E) EA	612(G) EA	*LF	*EA	*EA	*LF	12"	15"	18"	36" X 4'	*EA	*EA
	California Avenue	1,632.00	45.00	1,082.00	298.00	56.00	2.00			1.00	314.00		2.00		24.00				6.00	1.00
	Classen Boulevard	389.00	9,929.00	3,191.00	482.00	500.00	11.00	3.00		1.00	337.50								5.00	26.00
	W. Reno Avenue	4,321.00	7,557.00	3,692.00	1214.00	210.00	39.00	9.00		3.00	599.00	3.00	6.00	162.00		55.00			11.00	18.00
	N. Western Ave.	4,918.00		1,277.00	574.00	94.00	12.00	6.00	4.00	1.00	365.00						220.00			11.00
	W. Sheridan Ave.	642.00	1,030.00	631.00	182.00	810.00	7.00		1.00	1.00										1.00
	S. Lee Avenue		768.00	409.00	176.00	53.00		7.00			196.00		4.00		53.00					
	Shartel Avenue	1,244.00	515.00	1,211.00	452.00	142.00	2.00	3.00	1.00	1.00		1.00	2.00		20.00	120.00				6.00
	S.W. 2nd Street		2,367.00	1,155.00	439.00	53.00		2.00			584.00									
	TOTAL	13,146.00	22,211.00	12,648.00	3,817.00	1,918.00	73.00	30.00	7.00	8.00	2,395.50	4.00	14.00	162.00	97.00	175.00	220.00	22.00	63.00	

*Estimates to be included in payment for Removal of Structures and Obstructions
 **Quantities provided for information only, pay item to be paid for as one lump sum.

SUMMARY OF DRIVEWAYS										
P&P Sht. No.	Station	LT	RT	Type	Width	Radius	Surface Area	6" Concrete Driveway	Tactile Warning Device	
					FT	FT	SY	610(B) SY	610(I) SY	
					Reno					
	11+23.86		X	Const. Conc. Type 2 Dr.	26	15	27.07	27.07	12.00	
	11+38.34	X		Const. Conc. Type 2 Dr.	57	10	94.13	94.13	12.00	
	14+04.50	X		Const. Conc. Type 2 Dr.	8	10	28.27	28.27	24.00	
	14+30.00		X	Const. Conc. Type 2 Dr.	25	10	32.55	32.55	24.00	
	14+96.00	X		Const. Conc. Type 2A Dr.	96	10	230.99	230.99		
	15+62.00		X	Const. Conc. Type 2 Dr.	19	10	23.74	23.74	24.00	
	15+92.00	X		Const. Conc. Type 2A Dr.	80	5	192.98	192.98		
	16+42.00		X	Const. Conc. Type 2 Dr.	30	10	33.74	33.74	24.00	
	16+82.00	X		Const. Conc. Type 2 Dr.	84	5	183.10	183.10	12.00	
	19+98.00		X	Const. Conc. Type 2 Dr.	33	15	92.51	92.51	24.00	
	24+34.00	X		Const. Conc. Type 2 Dr.	17	5	42.18	42.18	24.00	
	24+69.00	X		Const. Conc. Type 2 Dr.	12	5	29.58	29.58	24.00	
	25+26.00	X		Const. Conc. Type 2 Dr.	13	5	30.49	30.49	24.00	
Western Culdesac										
	10+13.87		X	Const. Conc. Type 2 Dr.	40	20	136.44	136.44		
	10+78.36	X		Const. Conc. Type 2 Dr.	15	10	25.60	25.60	12.00	
	11+26.52	X		Const. Conc. Type 2 Dr.	40	10	66.54	66.54	24.00	
	11+30.88		X	Const. Conc. Type 2 Dr.	34	15	226.77	226.77	24.00	
	12+20.37	X		Const. Conc. Type 2 Dr.	30	10	51.35	51.35	24.00	
Western/Classen										
	7+93.49		X	Const. Conc. Type 2 Dr.	9	5	13.98	13.98	12.00	
	10+88.50	X		Const. Conc. Type 2 Dr.	36	10	70.64	70.64	24.00	
	10+96.00		X	Const. Conc. Type 2 Dr.	18	10	24.39	24.39	24.00	
	11+55.00		X	Const. Conc. Type 2 Dr.	20	10	27.46	27.46	24.00	
	11+76.50	X		Const. Conc. Type 2 Dr.	19	10	45.00	45.00	24.00	
	16+61.18	X		Const. Conc. Type 2 Dr.	40	15	67.15	67.15	24.00	
	16+77.80		X	Const. Conc. Type 2 Dr.	19	10	158.80	158.80	24.00	
	17+21.00		X	Const. Conc. Type 2 Dr.	23	10	67.40	67.40	24.00	
Sheridan										
	16+18.00	X		Const. Conc. Type 2 Dr.	24	15	139.59	139.59	24.00	
2nd Street										
	10+56.11		X	Const. Conc. Type 2 Dr.	22	10	38.05	38.05	24.00	
Lee										
	15+10.00		X	Const. Conc. Type 2 Dr.	18	15	44.06	44.06	24.00	
	11+87.77	X		Const. Conc. Type 2 Dr.	29	10	54.22	54.22		
	TOTAL							2,298.77	564.00	

SUMMARY OF EARTHWORK								
Plan Sht. No.	Location Station to Station	Unclassified Excavation	Embankment +15%	Volumes Per Sheet		Sheet Balance		Remarks
		CY	CY	Borrow	Excess Excav.	Uncl. Borrow	Waste	
		202(A)		CY	CY	CY	CY	
	Oklahoma City Boulevard	13,984.80	57,396.40	43,411.60	-	31,276.3		
	W. Reno Ave.	5,208.40	89.90	-	5,118.50			
	Western Ave.	595.30	27.20	-	568.10			
	Western Ave. / Classen Blvd.	5,217.80	85.10	-	5,132.70			
	S. Shartel Ave.	677.50	7.50	-	670.00			
	2nd Street	695.70	49.70	-	646.00			
	subtotal	26,379.50	57,655.80					
	TOTAL	26,379.50	57,655.80	n/a	n/a	31,276.30	0.00	

T:\1024-05\Drawings\Roadway\Sum-Rd-02.dgn

SUMMARY OF SURFACING QUANTITIES																									
P&P Sht. No.	Roadway	Location Station to Station	Aggregate Base Type A	Stabilized Subgrade	Cement Treated Base	Separator Fabric	Tack Coat	Superpave, Type S3 (PG 76-28 OK)	Superpave, Type S3 (PG 64-22 OK)	Superpave, Type S4 (PG 76-28 OK)	Superpave, Type S5 (PG 70-28 OK)	Dowel Jointed P.C. Concrete Pavement (Placement)	P.C. Concrete for Pavement	Diamond Grinding Concrete Pavement	42" F-Shaped Parapet	Class AA Concrete	Epoxy Coated Reinforcing Steel	Concrete Curb (8" Barrier-Integral)	2'-8" Comb. Curb & Gutter (6" Barrier-Notched)	2'-8" Comb. Curb & Gutter (8" Barrier-Notched)	4" Concrete Sidewalk	6" Concrete Sidewalk	Tactile Warning Device	Edge Drain Conduit - Perforated	Sawing Pavement
			303(A)	307(K)	317	325	407(B)	411(B)	411(B)	411(C)	411(D)	414(B)	414(G)	425	504(E)	509(A)	511(B)	609(A)	609(B)	609(B)	610(A)	610(A)	610(I)	613(J)	619(C)
			CY	SY	SY	SY	GAL	TON	TON	TON	TON	TON	SY	CY	SY	LF	CY	LB	LF	LF	LF	SY	SY	SF	LF
	Oklahoma City Boulevard	Sta. 155+00 to Sta. 164+00	879.61	5412.36	4607.92	6522.35						4406.29	1101.57		620.00	99.20	4176.32	1322.08						362.00	
	Oklahoma City Boulevard	Sta. 164+00 to Sta. 173+00	1729.89	8679.67	7281.78	11187.13						6963.16	1740.79		1000.00	160.00	6736.00	3215.68					2562.80	138.00	1132.00
	Oklahoma City Boulevard	Sta. 173+00 to Sta. 182+00	1840.38	9193.58	7857.28	10979.47						7462.27	1865.57					3562.49					2549.69	296.00	1870.00
	Oklahoma City Boulevard	Sta. 182+00 to Sta. 191+00	1103.11	5430.97	4485.74	6612.97						4198.77	1049.69					2421.30					1664.62	72.00	1287.00
	W. Reno Ave.	Sta. 10+00 to Sta. 19+00	1726.39	6966.88	7780.95							5716.20	1429.05						1569.89			920.90		120.00	1532.00
	W. Reno Ave.	Sta. 19+00 to Sta. 28+00	871.39	3544.15	4201.46							2534.31	633.58						1267.58			661.43		120.00	900.00
	Western Ave.	Sta. 9+00 to Sta. 14+00	396.89	1564.29	1943.75							981.31	245.33						731.77			220.40			731.00
	Western Ave. / Classen Blvd.	Sta. 7+00 to Sta. 14+00	936.71	3712.07	4270.66							2853.88	713.47						1077.22			736.04			1002.00
	Western Ave. / Classen Blvd.	Sta. 14+00 to Sta. 19+00	810.81	3313.08	3833.16							2514.06	628.52						1002.95			520.10			808.00
	W. Sheridan Ave.	Sta. 10+00 to Sta. 19+00	429.44	1525.80	1939.81							889.74	222.44						798.40			612.47		96.00	745.00
	S. Shartel Ave.	Sta. 0+00 to Sta. 5+00	233.48	822.31	1009.48							534.76	133.69						360.94			353.56		96.00	352.00
	S. Lee Ave.	Sta. 9+00 to Sta. 16+00	13.22								123.57								147.70			147.70		72.00	148.00
	2nd Street	Sta. 9+00 to Sta. 15+00	360.82	1444.46	1760.49							958.94	239.74						609.44			175.63		96.00	605.00
	Klein Exchange		293.34	1468.25				166.97	222.62	111.31															734.00
	TOTAL		11,864.60	54,108.51	24,232.72	63,225.13	71.92	166.97	222.62	111.31	123.57	40,809.61	10,202.40	1,103.34	1,620.00	259.20	10,912.32	10,521.55	7,860.53	595.47	4,200.53	6,777.11	1,202.00	11,769.00	734.00

OKLAHOMA CITY BOULEVARD OKLAHOMA CO.

DESIGN	KBA	MMPC
DRAWN	ISFM	RWH
CHECKED	KBA	
APPROVED		
SQUAD	MacArthur	

OKLAHOMA DEPARTMENT OF TRANSPORTATION

SUMMARY SHEET (1)

STATE JOB NO. 17428(88) SHEET NO. 18