				RE	TAINING W	ALL NO. 3 (QUANTITIES				
	PAY ITEMS			NON-PAY ITEMS							
PANEL NO.	RETAINING WALL (S.Y.)	PILES FURNISHED (HP10X42)	PILES DRIVEN (HP10X42)	CLASS A CONCRETE (C.Y.)	REINFORCING STEEL (GRADE 60) (LB.)	6" PERF. PIPE UNDERDRAIN ROUND (L.F.)	SUBSTRUCTURE EXCAVATION COMMON (C.Y.)	UNCLASSIFIED BACKFILL (C.Y.)	GRANULAR BACKFILL (C.Y.)	PIPE UNDERDRAIN COVER MATERIAL (C.Y.)	
1	18.5	303	303	26.8	3,220	20	125	65	35	5	
2	19.9	303	303	27.4	3,220	20	95	50	45	5	
3	21.4	303	303	27.9	3,220	20	100	50	55	5	
4	22.9	303	303	28.5	3,220	20	110	55	55	10	
5	24.4	303	303	29.1	3,220	20	110	60	65	10	
6	25.9	303	303	29.6	3,220	20	120	60	75	10	
7	27.4	306	306	34.1	4,160	20	135	65	90	15	
8	29.0	306	306	34.7	4,160	20	135	65	100	15	
9	30.6	362	362	38.2	4,620	20	145	70	120	15	
10	32.2	362	362	38.8	4,620	20	150	70	135	15	
11	33.7	362	362	39.4	4,620	20	135	65	145	20	
12	39.7	399	399	49.8	5,740	20	170	75	220	25	
13	48.1	471	471	61.5	7,370	20	170	75	320	35	
14	56.7	486	486	71.4	8,860	20	160	65	450	40	
15	58.6	566	566	79.5	10,210	20	130	50	485	45	
16	62.7	624	624	95.1	12,330	20	165	60	575	50	
17	64.3	621	621	95.7	12,330	20	155	60	600	50	
18	65.8	609	609	90.5	11,800	20	145	55	625	50	
TOTAL	681.8	7,292	7,292	898.0	110,140	360	2,455	1,115	4,195	420	

RETAINING WALL NO. 4 QUANTITIES												
		PAY ITEMS			NON-PAY ITEMS							
PANEL NO.	RETAINING WALL (S.Y.)	PILES FURNISHED (HP10X42)	PILES DRIVEN (HP10X42)	CLASS A CONCRETE (C.Y.)	REINFORCING STEEL (GRADE 60) (LB.)	6" PERF. PIPE UNDERDRAIN ROUND (L.F.)	SUBSTRUCTURE EXCAVATION COMMON (C.Y.)	UNCLASSIFIED BACKFILL (C.Y.)	GRANULAR BACKFILL (C.Y.)	PIPE UNDERDRAIN COVER MATERIAL (C.Y.)		
1	71.4	708	708	140.9	14,440	20	165	55	710	55		
2	71.0	712	712	140.8	14,440	20	175	60	700	55		
3	70.2	621	621	117.2	13,120	20	165	60	665	55		
4	69.2	624	624	116.8	13,120	20	165	60	645	55		
5	68.0	639	639	116.3	13,120	20	145	50	625	55		
6	66.6	639	639	115.8	13,120	20	175	65	605	50		
7	65.1	639	639	96.0	12,330	20	215	85	575	50		
8	63.4	639	639	95.3	12,330	20	230	90	545	50		
9	59.4	579	579	79.8	10,210	20	195	80	460	45		
10	57.4	579	579	79.0	10,210	20	220	90	430	45		
11	48.6	474	474	61.7	7,370	20	125	50	295	35		
12	46.3	432	432	54.9	7,010	20	120	50	265	30		
13	44.0	432	432	54.0	7,010	20	135	55	235	30		
14	41.7	383	383	50.5	5,740	20	130	55	220	25		
15	39.5	383	383	49.7	5,740	20	125	55	195	25		
16	37.2	383	383	44.4	4,910	20	125	55	165	25		
17	35.1	383	383	43.6	4,910	20	130	55	150	20		
18	33.1	341	341	39.2	4,620	20	125	60	125	20		
19	31.4	341	341	38.5	4,620	20	130	60	115	15		
20	29.9	291	291	35.0	4,160	20	135	65	100	15		
21	26.2	297	297	33.6	4,160	20	115	55	75	10		
22	24.9	297	297	29.2	3,220	20	115	60	65	10		
23	23.7	297	297	28.8	3,220	20	115	60	55	10		
24	22.7	297	297	28.4	3,220	20	120	65	50	10		
TOTAL	1,146.0	11,410	11,410	1,689.4	196,350	480	3,595	1,495	8,070	795		

DESCRIPTION	REVISIONS	DAT

ESIGN	B.J.K.		CROSSTO
RAWN	R.A.P.		OVER CL
HECKED	B.J.K.		F
PPROV.	T.A.C.		
QUAD	CE	EC	

CROSSTOWN BOULEVARD OVER CLASSEN BLVD.

OKLAHOMA COUNTY

RETAINING WALL QUANTITIES (SHEET 2 OF 2)

JOB PIECE NO. 17428(88) SHEET NO. 132