


 PAVT. STRUCTURE
 DRIVING/PARKING LANES
 TRAIL

 SURFACE COURSE
 9" DOWEL JOINTED P.C. CONC. PAV.
 6" CLASS A P.C. CONC.

 BASE COURSE
 4" CEMENT TREATED BASE
 4" AGGREGATE BASE TYPE A

- (1) THIS AREA TO BE BACKFILLED AND COMPACTED AS PART OF FINAL FINISHING OPERATIONS. COST TO BE INCLUDED IN OTHER ITEMS OF WORK.
- (2) DECORATIVE BRICK PAVERS
- (3) INSTALLATION OF EDGE DRAIN, SEE ODOT STANDARD DETAIL PED-3-2
- (4) TOPSOIL NOTE:
  THE CONTRACTOR SHALL STRIP ALL OF THE
  AVAILABLE TOPSOIL, STOCKPILE IT, AND PLACE IT BACK ON
  THE SECTION IN ACCORDANCE WITH SECTION 205 OF THE
  STANDARD SPECIFICATION. RESERVED TOPSOIL SHALL BE
  SPREAD APPROX. 5" THICK FIRST ON THE COMPLETED SLOPES
  OF THE CUT SECTIONS AND THE REMAINDER ON COMPLETED
  FILL SLOPES OR OTHER PRIORITY AREAS LOCATED BY THE
  ENGINEER. ALL ADDITIONAL COSTS ASSOCIATED WITH OPERATION
  SHALL BE INCLUDED IN THE PAY ITEM FOR TYPE A SALVAGED TOPSOIL,

THE GRADING LINE AS SHOWN ON THE TYPICAL AND CROSS SECTIONS IS TO THE TOP OF THE TOPSOIL. EARTHWORK QUANTITIES WERE NOT ADJUSTED FOR SALVAGE AND THE TOPSOIL QUANTITY IS INCLUDED IN THE EARTHWORK SUMMARY.



PAVT. STRUCTURE	DRIVING/PARKING LANES	TRAIL
SURFACE COURSE	9" DOWEL JOINTED P.C. CONC. PAV.	6" CLASS A P.C. CONC.
BASE COURSE	4" CEMENT TREATED BASE	4" AGGREGATE BASE TYPE A

 DESIGN
 KBA
 MMPC

 DRAWN
 ISFM
 RWH

 CHECKED
 MM
 TYPICAL SECTIONS (1)

 APPROVED
 SQUAD
 MacArthur

 STATE JOB NO
 17428(89)
 SHEET NO

11/19/2015 1.024-00/DIBWIIJS/INOBUWAY/1024-00-11F-01-00IIC.UGII