

REVISIONS		
NO.	DESCRIPTION	DATE
1	REV. QUANTITIES & NOTE	04-06-16
2	REV. NOTES	11-06-17

LIGHTING GENERAL CONSTRUCTION NOTES

SYMBOLS AND LEGENDS ARE DIAGRAMMATIC ONLY AND LOCATIONS SHALL BE ADJUSTED FOR EXISTING FIELD CONDITIONS, BUT NO MAJOR ALTERATIONS OR RELOCATIONS WILL BE MADE WITHOUT FIRST CONSULTING WITH THE TRAFFIC ENGINEERING DIVISION AT (405)521-2861.

THIS PROJECT SHALL BE CONSTRUCTED WITHOUT CLOSING THE EXISTING ROAD TO LOCAL AND THROUGH TRAFFIC. SEE STANDARD SPECIFICATIONS FOR MAINTENANCE OF LOCAL AND THROUGH TRAFFIC.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE HE MAY INFLICT TO THE EXISTING UNDERGROUND UTILITIES WITHIN THE PROJECT AREA AS A RESULT OF HIS DIGGING, TRENCHING, BORING, ETC.... PRIOR TO DIGGING NEAR THE UTILITIES, THE CONTRACTOR SHALL CALL FOR A LIST OF ALL UNDERGROUND FACILITIES REGISTERED IN THE AREA OF CONSTRUCTION LISTED WITH THE FOLLOWING AGENCIES:
THE "OKIE" NOTIFICATION CENTER 811 OR (405)522-6543 OR WWW.CALLOKIE.COM OR THE LOCAL COUNTY CLERK'S OFFICE.

LIGHTING PAY QUANTITY NOTES

- (1) POLYMER CONCRETE PULL BOXES SHALL BE USED.
- △ (2) PRICE BID FOR THIS ITEM SHALL INCLUDE THE COST OF INSTALLING 27 - 30' MH POLES AND 21 - 16' MH POLES AS SHOWN IN THE PLANS.

THE POLES TO BE SUPPLIED ON THIS PROJECT SHALL BE IN ACCORDANCE WITH THE LIGHTING DETAILS IN THESE PLANS, WHICH ARE IDENTICAL TO THE LIGHT POLES SUPPLIED ON PROJECT 180. THE LATEST STANDARDS AND SPECIFICATIONS FOR PROJECT 180 ARE TO BE USED ON THIS PROJECT. FOR ADDITIONAL INFORMATION ON THE SPECIAL PROVISIONS FOR THIS EQUIPMENT CONTACT CHAD HARRISON WITH THE CITY OF OKLAHOMA CITY AT (405)297-2058.
- △ (3) PRICE BID FOR THIS ITEM SHALL INCLUDE THE COST OF INSTALLING 27 - 140W ROADWAY FIXTURES AND 42 - 32W PEDESTRIAN FIXTURES AS SHOWN IN THE PLANS.


THE LUMINAIRES TO BE SUPPLIED ON THIS PROJECT SHALL BE IN ACCORDANCE WITH THE LIGHTING DETAILS IN THESE PLANS, WHICH ARE IDENTICAL TO THE LUMINAIRES SUPPLIED ON PROJECT 180. THE LATEST STANDARDS AND SPECIFICATIONS FOR PROJECT 180 ARE TO BE USED ON THIS PROJECT. FOR ADDITIONAL INFORMATION ON THE SPECIAL PROVISIONS FOR THIS EQUIPMENT CONTACT CHAD HARRISON WITH THE CITY OF OKLAHOMA CITY AT (405)297-2058.
- △ (4) THE CONTRACTOR SHALL CONTACT NORMAN LEE WITH OG&E AT (405)740-7750 TO DETERMINE THE LOCATION AND TYPE OF POWER SUPPLY THAT WILL BE REQUIRED ON THIS PROJECT.
- △ (5) OMITTED
- △ (6) OMITTED
- △ (7) OMITTED
- (TP-1) PAYMENT FOR THIS ITEM WILL BE BASED ON PLAN QUANTITY. SEE THE 2009 SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

LIGHTING PAY QUANTITIES				
Oklahoma City Blvd. at Walker Ave., Hudson Ave. and Robinson Ave. in OKC, OK				
0302 TRAFFIC				
ITEM	DESCRIPTION	UNIT	TOTAL	
802(B) 8340	2" PVC SCH. 40 PLASTIC CONDUIT BORED	(TP-1) LF	1250	
802(B) 8342	2" PVC SCH. 40 PLASTIC CONDUIT TRENCHED	(TP-1) LF	5950	
803(A) 8065	PULL BOX (SIZE I)	(1) EA	61	
804(A) 2915	STRUCTURAL CONCRETE	(TP-1) CY	34.32	△
804(B) 2916	REINFORCING STEEL	(TP-1) LB	2026.56	△
806(C) 8270	30' MTG & HLMA (SPECIAL)	(2) EA	48	
809(C) 8399	POST TOP LUMINAIRE	(3) EA	69	
810(A) 3118	SERVICE POLE	(4) EA	1	
811 8038	1/C NO. 4 ELECTRICAL CONDUCTOR	(TP-1) LF	21600	
811 8046	1/C NO. 12 ELECTRICAL CONDUCTOR	(TP-1) LF	3880	△

I:\07\17 G:\0\Projects\1-24\17B Downtown Blvd WP 51C Task 6\CAD\QUANT LIGHT.dgn

R. Wayne Russell
R. WAYNE RUSSELL, P.E. # 16030
C.A. # 1160, RENEWAL 06-30-17

11-13-15
DATE



Traffic Engineering Consultants, Inc.
6000 S. Western, Suite 300 - Oklahoma City, OK 73139,
Ph: 405-720-7721, Fax: 405-720-9848, Web: www.tecok.com

Design	RWR	11/07/17
Drawn	SB	11/07/17



LIGHTING
PAY QUANTITIES AND NOTES

State Job No. 17428(89) Sheet No. 10