REVISIONS		
REV. NO.	DESCRIPTION	DATE
1	REVISED QUANTITIES	11-15-2016

SUMMARY OF SURFACING QUANTITIES

P&P Sht. No.	Roadway	Location Station to Station	Stabilized Subgrade	Separator Fabric	Unclassified Borrow	Concrete Curb (6" Barrier-Integral)	Concrete Curb (8" Barrier-Integral)	6" Concrete Sidewalk	Dowel Jointed P.C. Concrete Pavement (Placement)	P.C. Concrete for Pavement	Cement Treated Base	Aggregate Base Typa A	Superpave, Type S4 (PG 70-28 OK)	Cold Milling Pavement	Concrete Pavers	Tactile Warning Device	Sawing Pavement
			307(K)	325	202(D)	609(A)	609(A)	610(A)	414(B)	414(G)	317	303(A)	411(C)	412	610(E)	601(I)	619(C)
			SY	SY	CY	LF	LF	SY	SY	CY	SY	CY	TON	SY	SF	SF	LF
	BOULEVARD	188+00 to 195+00	7,438.87	13,640.0	895.94		2,480.00	2,092.93	6,198.87	1,549.72	6,552.25	1,372.85			9,849.90	300.00	128.00
	BOULEVARD	195+00 to 204+00	8,616.79	16,733.6	650.28		1,800.00	1,735.70	7,716.79	1,929.20	7,966.98	1,556.76			5,039.26	304.00	198.00
	BOULEVARD	204+00 to 213+00	7,847.54	15,117.3	939.29		2,600.00	2,391.33	6,547.54	1,636.89	6,982.45	1,469.30			7,774.72	350.00	154.00
	BOULEVARD	213+00 to 214+85.71	1,913.25	3,620.2	268.36		742.84	496.01	1,541.83	385.46	1,621.63	344.18			2,335.24		74.00
	WALKER	10+43.18 to 13+95.50	393.99	759.4	37.21	711.00			342.49	85.62	295.69					134.00	755.00
	WALKER	15+52.52 to 20+65.17											167.68	1,497.14			132.00
	ROBINSON	10+35.05 to 13+58.75	455.99	879.3	42.45	117.50			397.24	99.31	339.43		344.87	3,079.22		24.00	138.00
	ROBINSON	14+67.81 to 21+00				883.00							195.89	1,748.99			1,024.00
	BROADWAY	10+54.02 to 13+67.45	393.07	355.6	48.73	391.90			0.00	0.00	281.07					24.00	431.90
	3RD STREET	18+25.00 to 19+01.02	345.27	648.3	54.93	152.04			269.25	67.31	290.17		124.98	1,115.93		24.00	33.00
		TOTAL	27,404.77	51,753.61	2,937.20	2,255.44	7,622.84	6,715.97	23,014.01	5,753.50	24,329.67	4,743.10	833.42	7,441.28	24,999.12	1,160.00	3,067.90

1

SUMMARY OF EARTHWORK

Plan Sht. No.	Location Station to Station **Oklahoma City Boulevard**	Unclassified Excavation	Embankment +15%	Volumes Per Sheet Borrow	Volumes Per Sheet Excess Excav.	Sheet Balance Uncl. Borrow	Sheet Balance Waste	Remarks
		CY	CY	CY	CY	CY	CY	
		202(A)				202(D)		
	Phase I							
	188+00 to 195+00	6,238.00	130.70	-	6,107.30		22,712.50	
	195+00 to 204+00	7,193.30	41.70	-	7,151.60			
	204+00 to 213+00	5,884.90	121.40	-	5,763.50			
	213+00 to 214+85.71	3,703.40	13.30	-	3,690.10			
	TOTAL							
		23,019.60	**307.10**	**n/a**	**n/a**	**0.00**	**22,712.50**	

SUMMARY OF DRIVEWAYS

P&P Sht. No.	Station Oklahoma City Boulevard	Type	Return Radius	Width	Additional Length Beyond Return	Surface Area	6" Concrete Driveway	Tactile Warning Device
							610(B)	610(I)
			FT	FT	FT	SF	SY	SF
	213+20.00, RT	CONC. COMM. DR.	15	22	24	1,125.30	125.03	48.00
	TOTAL						125.03	48.00

SUMMARY OF EROSION CONTROL

Plan Sht. No.		Station to Station	Permanent Topsoil	Permanent Solid Slab Sodding	Temporary Seeding Method B	Temporary Vegetative Mulching	Temporary Silt Fence	Temporary Sediment Filter
			202(D)	230(A)	232(B)	233(A)	221(C)	221(D)
			CY	SY	AC	AC	LF	EA
	BOULEVARD	188+00 to 195+00	775.89	5,586.42	1.15	1.15	1,400.00	6.00
	BOULEVARD	195+00 to 204+00	1,726.58	12,431.40	2.57	2.57	1,800.00	4.00
	BOULEVARD	204+00 to 213+00	1,593.10	11,470.34	2.37	2.37	1,800.00	12.00
	BOULEVARD	213+00 to 214+85.71	435.16	3,133.17	0.65	0.65	371.42	2.00
	ROBINSON	14+67.91 to 21+00	663.10	4,774.35	0.99	0.99		
		TOTAL	5,193.85	37,395.69	7.73	7.73	5,371.42	24.00

SUMMARY OF REMOVAL

P&P Sht. No.	Location CRL Station to Station	Removal of Asphalt Pavement	Removal of Concrete Pavement	Removal of Curb and Gutter	Removal of Sidewalk	Removal of Traffic Signal Equipment	Remove and Reset Fire Hydrants and Appurtenances	Removal of Structures & Obstructions: Fences	Removal of Structures & Obstructions: Storm Sewer Pipe	Removal of Structures & Obstructions: Signs
		619(B)	619(B)	619(B)	619(B)	805(A)	612(G)	619(A)		
		SY	SY	LF	SY	**L.SUM	EA.	*LF	*LF	*EA
	Oklahoma City Boulevard	23,672.00	3,661.00	5,986.00	2053.00	3.00	3.00	1,278.00	1,758.00	11.00
	Oklahoma City Boulevard	18,674.00	5,303.00	3,451.00	967.00	1.00	3.00	1,491.00	1,016.00	41.00
	Robinson		1,770.00	1,065.00				278.00	103.00	2.00
	TOTAL	42,346.00	10,734.00	10,502.00	3,020.00	4.00	6.00	3,047.00	2,877.00	54.00

*Estimates to be included in payment for Removal of Structures and Obstructions
**Quantities provided for information only, pay item to be paid for as one lump sum.

PRINT DATE: 11/15/2016 T:\1024-06\Drawings\Roadway\1024-06-Sum-Rd-02.dgn

OKLAHOMA CITY BOULEVARD OKLAHOMA CO.

DESIGN	KBA	MMPC
DRAWN	ISFM	RWH
CHECKED	MM	
APPROVED		
SQUAD	MacArthur	

OKLAHOMA DEPARTMENT OF TRANSPORTATION

SUMMARY SHEET (1)

STATE JOB NO. 17428(89) SHEET NO. 11