

REVISIONS		
NO.	DESCRIPTION	DATE

SIGN SUMMARY


SHEET NO.	ITEM NO.	APPROXIMATE LOCATION		STATION	SIGN TYPE	POSTS			FOOTINGS			SIGN AREA			REMARKS
						TYPE	A L.F.	B L.F.	SPACING	DESIGN NO.	CONCRETE C.Y.	STEEL LBS.	SHEET S.F.	PANEL S.F.	
T12	1	189+00	(OKC BLVD.)		R2-1(25)	2" PIPE POST	11.5			A-2	0.06		5.00		
T12	2	190+90	(OKC BLVD.)		R4-7	2" PIPE POST	12.0			A-2	0.06		5.00		
T12	3	191+95	(OKC BLVD.)		R4-7	2" PIPE POST	12.0			A-2	0.06		5.00		
T12	4	192+70	(OKC BLVD.)		R7-8(MOD), R7-8P	1-1/2" PIPE POST	11.0			A-1	0.06		2.80		EXACT SIGN TO MATCH P180 SIGNS
T12	5	193+50	(OKC BLVD.)		R2-1(25)	2" PIPE POST	11.5			A-2	0.06		5.00		
T12	6	194+15	(OKC BLVD.)		R4-7	2" PIPE POST	12.0			A-2	0.06		5.00		
T12	7	197+45	(OKC BLVD.)		R7-8(MOD), R7-8P	1-1/2" PIPE POST	11.0			A-1	0.06		2.80		EXACT SIGN TO MATCH P180 SIGNS
T12	8	200+20	(OKC BLVD.)		R7-8(MOD)	1-1/2" PIPE POST	11.0			A-1	0.06		1.30		EXACT SIGN TO MATCH P180 SIGNS
T12	9	203+98	(OKC BLVD.)		R7-8(MOD)	1-1/2" PIPE POST	11.0			A-1	0.06		1.30		EXACT SIGN TO MATCH P180 SIGNS
T13	10	205+00	(OKC BLVD.)		R7-8(MOD), R7-8P	1-1/2" PIPE POST	11.0			A-1	0.06		2.80		EXACT SIGN TO MATCH P180 SIGNS
T13	11	209+05	(OKC BLVD.)		R4-7	2" PIPE POST	12.0			A-2	0.06		5.00		
T13	12	213+00	(OKC BLVD.)		R2-1(25)	2" PIPE POST	11.5			A-2	0.06		5.00		
T13	13	214+82	(OKC BLVD.)		R4-7	2" PIPE POST	12.0			A-2	0.06		5.00		
T14	14	10+47	(SW 3RD ST.)		R1-1	2" PIPE POST	12.0			A-2	0.06		5.18		
T14	15	10+75	(SW 3RD ST.)		W6-3	2-1/2" PIPE POST	13.0			A-3	0.20	24.00	9.00		
T14	16	12+50	(SW 3RD ST.)		R2-1(25)	2" PIPE POST	11.5			A-2	0.06		5.00		
T14	17	16+00	(SW 3RD ST.)		R3-7(R)	2" PIPE POST	12.0			A-2	0.06		6.25		
T14	18	12+50	(SW 3RD ST.)		R2-1(25)	2" PIPE POST	11.5			A-2	0.06		5.00		
T14	19	18+00	(SW 3RD ST.)		R3-7(R)	2" PIPE POST	12.0			A-2	0.06		6.25		
T14	20	18+78	(SW 3RD ST.)		R1-1	2" PIPE POST	12.0			A-2	0.06		5.18		
T15	21	12+50	(WALKER AVE.)		R2-1(30)	2" PIPE POST	11.5			A-2	0.06		5.00		
T15	22	16+50	(WALKER AVE.)		R2-1(30)	2" PIPE POST	11.5			A-2	0.06		5.00		
T15	23	17+48	(WALKER AVE.)		R1-1	2" PIPE POST	12.0			A-2	0.06		5.18		
T15	24	18+00	(WALKER AVE.)		R1-1	2" PIPE POST	12.0			A-2	0.06		5.18		
T16	25	13+10	(HUDSON AVE.)		R1-1	2" PIPE POST	12.0			A-2	0.06		5.18		
T16	26	13+85	(HUDSON AVE.)		R1-1	2" PIPE POST	12.0			A-2	0.06		5.18		
T17	27	AS SHOWN	(ROBINSON AVE.)		R1-1	2" PIPE POST	12.0			A-2	0.06		5.18		
T17	28	17+45	(ROBINSON AVE.)		R4-7	2" PIPE POST	12.0			A-2	0.06		5.00		
T18	29	10+31	(BROADWAY AVE.)		R1-1	2" PIPE POST	12.0			A-2	0.06		5.18		
T18	30	13+63	(BROADWAY AVE.)		R1-1	2" PIPE POST	12.0			A-2	0.06		5.18		
TOTAL						1-1/2" PIPE POST	55.0				1.94	24.00	144.12		
						2" PIPE POST	284.5								
						2-1/2" PIPE POST	13.0								



HANDICAP SIGN DETAIL

R7-8 (MODIFIED) 12"x 18"
R7-8a 12"x 6"

R. Wayne Russell
R. WAYNE RUSSELL, P.E. # 16030
C.A. # 1160, RENEWAL 06-30-17



Design	RWR	11-13-15
Drawn	SB	11-13-15



SIGN SUMMARY

G:\0\Projects\1-24\7B Downtown Blvd WP 51C Task 6\CAD\SIGN_SUM.dgn 11-13-15