

REVISIONS		
REV. NO.	DESCRIPTION	DATE
△	ADDED NOTE	12-21-2015
△	ADDED NOTE	3-15-2016

TRAFFIC CONTROL 0304		SUMMARY OF QUANTITIES			JP# 17428(89)
ITEM NO.	DP NO.	DESCRIPTION	NOTES	UNIT	QUANTITY
877(B)	8484	DELIVER PORTABLE LONGITUDINAL BARRIER	(TC-1)	LF	50
880(B)	8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	(TC-26, 29, 33, 84)	SD	1080
880(B)	8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	(TC-26, 30, 33, 84)	SD	4320
880(C)	8842	CONSTRUCTION BARRICADES (TYPE III)	(TC-26, 70, 84)	SD	2880
880(C)	8850	PERMANENT BARRICADE UNIT		EA	1
880(E)	8860	WARNING LIGHTS (TYPE A)	(TC-26, 84)	SD	5760
880(G)	8890	CHANNELIZER CONE	(TC-33, 84)	SD	6750

TRAFFIC CONSTRUCTION PAY QUANTITY NOTES

- (TC-1) THE CONTRACTOR SHALL FURNISH AND INSTALL SUCH LIGHTS, SIGNS, BARRICADES, AND PROVIDE FLAGGERS NECESSARY FOR THE CONTROL, SAFETY AND MAINTENANCE OF TRAFFIC WHEN INSTALLING, RELOCATING, OR DELIVERING PORTABLE LONGITUDINAL BARRIER.
- (TC-26) ALL CONSTRUCTION TRAFFIC CONTROL WILL BE IMPLEMENTED ACCORDING TO CONSTRUCTION PLANS, AND INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND COMPLIANT WITH APPLICABLE O.D.O.T. STANDARD DRAWINGS. PRICE BID FOR THIS ITEM SHALL BE PAYMENT IN FULL FOR THE INSTALLATION, MAINTENANCE AND SUBSEQUENT REMOVAL OF ALL NECESSARY CONSTRUCTION TRAFFIC CONTROL DEVICES REQUIRED FOR COMPLETION OF THE PROJECT.
- ALL SIGNS AND BARRICADES WHICH ARE SHOWN WITH TYPE 'A' LIGHTS IN THE STANDARD DRAWINGS SHALL HAVE THE CORRESPONDING LIGHT ATTACHED DURING NON-DAYLIGHT HOURS.
- (TC-28) INCLUDED IN THIS ITEM ARE ALL S.C.S. (SPECIAL CONSTRUCTION SIGNING) SIGNS WHICH ARE BETWEEN 0.00 S.F. AND 6.25 S.F. ALSO INCLUDED IN THIS ITEM SHALL BE THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF THESE SIGNS.
- (TC-29) INCLUDED IN THIS ITEM ARE ALL S.C.S. (SPECIAL CONSTRUCTION SIGNING) SIGNS WHICH ARE BETWEEN 6.26 S.F. AND 15.99 S.F. ALSO INCLUDED IN THIS ITEM SHALL BE THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF THESE SIGNS.
- (TC-30) INCLUDED IN THIS ITEM ARE ALL S.C.S. (SPECIAL CONSTRUCTION SIGNING) SIGNS WHICH ARE BETWEEN 16.00 S.F. AND 32.99 S.F. ALSO INCLUDED IN THIS ITEM SHALL BE THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF THESE SIGNS.
- (TC-33) ALL CONSTRUCTION WORK ZONE SIGNS SHALL HAVE FLUORESCENT SHEETING. THE FLUORESCENT SHEETING SHALL MEET THE REQUIREMENTS OF ASTM D4956 (LATEST REVISION)
- THE MANUFACTURER SHALL FURNISH A TYPE 'D' CERTIFICATION IN ACCORDANCE WITH O.D.O.T. STANDARD SPECIFICATIONS (CURRENT EDITION) SUBSECTION 106.04. THE CERTIFICATION SHALL INCLUDE TEST RESULTS ON MATERIAL SUBMITTED FOR APPROVAL.
- (TC-70) THIS ITEM IS AN ESTIMATED QUANTITY TO BE USED AS DEEMED NECESSARY BY THE ENGINEER.
- (TC-84) 180 CONSTRUCTION CALENDAR DAYS WERE USED TO COMPUTE THE SIGN DAY PAY ITEMS. THE AMOUNT OF CALENDAR DAYS USED TO COMPUTE THE SIGN DAY PAY ITEMS IS AN ESTIMATED QUANTITY ONLY, BASED ON THE CURRENT O.D.O.T. STANDARDS AND SUGGESTED CONSTRUCTION SEQUENCE FOR THIS PROJECT. THESE ESTIMATED SIGN DAY QUANTITIES MAY CHANGE AS THE PROJECT'S CONSTRUCTION TRAFFIC CONTROL IS MODIFIED DURING CONSTRUCTION.

TRAFFIC CONSTRUCTION GENERAL NOTES

- THE CONTRACTOR SHALL COORDINATE WITH OKLAHOMA CITY PUBLIC WORK DEPARTMENT TO OBTAIN A WORK ZONE PERMIT PRIOR TO CLOSING OR RESTRICTING TRAFFIC ON ANY CITY STREETS."
- △ THE CONTRACTOR SHALL COMPLETE THE OKLAHOMA CITY "APPLICATION FOR WORK PERMIT" FORM. SUBMIT COMPLETED FORM TO:
- DEBBIE MILLER TERRY HOWELL
 ASSISTANT CITY ENGINEER OKLAHOMA CITY CONSTRUCTION RESIDENCY
 CITY OF OKLAHOMA CITY OKLAHOMA DEPT. OF TRANSPORTATION
 PUBLIC WORKS DEPARTMENT 701 S.E. 82ND
 420 W MAIN, 7TH FLOOR OKLAHOMA CITY, OK, 73149
 OKC, OK, 73102 THOWELL@ODOT.ORG
 DEBBIE.MILLER@OKC.GOV
- PLEASE SUBMIT THE ABOVE FORM VIA U.S. MAIL OR E-MAIL TWO (2) WEEKS BEFORE CLOSING ANY STREET OR RAMP FOR THE PURPOSE OF EMERGENCY RESPONSE PERSONNEL NOTIFICATION.
- △ CONTRACTOR SHALL COORDINATE ALL ROAD AND LANE CLOSURES WITH THE CITY OF OKLAHOMA CITY TO MINIMIZE IMPACT TO SPECIAL EVENTS IN THE PROJECT AREA

PRINT DATE: 3/15/2016 T:\1024-06\Drawings\Traffic\1024-06-Sum-Tr.dgn

DESIGN			KBA	MMPC	OKLAHOMA CITY BOULEVARD	OKLAHOMA CO.
DRAWN			ISFM	RWH		
CHECKED			MM			
APPROVED						
SQUAD			MacArthur			
OKLAHOMA DEPARTMENT OF TRANSPORTATION						
SUMMARY OF PAY QUANTITIES						
(TRAFFIC CONTROL)						
STATE JOB NO. 17428(89) SHEET NO. 7						