

SUMMARY OF DRAINAGE STRUCTURES

STR NO.	STATION	DESCRIPTION	DESIGN	STRUCTURAL INSTALLATION						CLASS AA CONCRETE 509(A)	REINFORCING STEEL 511(A)	REINFORCED CONCRETE PIPE CLASSIII 613(A)			PREFAB. CULVERT END SECTION 613(L)			REM. OF HDWL. 619(B)
				FILL HEIGHT FT	UNCL. EXCAV. 202(A) CY	STRUCT. EXCAV. 501(A) CY	TRENCH EXCAV. 613(V) CY	STD. BED. MAT'L.				24"	36"	42"	ROUND			
								CLASS A 613(R) CY	CLASS B 613(S) CY						24"	36"	42"	
1	STA. 341+32.50 BL LINE 3	EXTEND EXIST. 24" RCP 24' RT. W/ PCES	PCES-4, SPI-4, SPB-1	1			12.80		6.72			24			1			1
2	STA. 343+21.46 BL LINE 3	EXTEND EXIST. 36" RCP 16' RT. W/ PCES	PCES-4, SPI-4, SPB-1	1			15.48		10.08				16			1		1
3	STA. 349+03.25 BL LINE 4	REMOVE EXIST. HDWL. OF 36" RCP & CONST. PCES	PCES-4, SPI-4, SPB-1	1			3.87		2.52							1		1
TOTALS:					0.00	0.00	32.15	0.00	19.32	0.00	0.00	24.00	16.00	0.00	1.00	2.00	0.00	3.00

SUMMARY OF TEMPORARY SEDIMENT CONTROL

LOCATION		DESCRIPTION	TEMPORARY SILT FENCE 221(C) L.F.	TEMPORARY SILT DIKE 221(F) L.F.	TEMPORARY INLET SEDIMENT FILTER 221(H) EA	VEGETATIVE MULCHING 233(A) AC	DISTURBED AREA AC
STATION TO STATION	LEFT RIGHT						
LINE 3							
STA. 334+75.96 TO STA. 372+03.89	X		490	30	2	0.20	0.24
STA. 334+75.96 TO STA. 372+03.89		X	5654			3.61	5.34
LINE 4							
STA. 334+76.47 TO STA. 374+74.70	X		693			0.23	0.24
STA. 334+76.47 TO STA. 374+74.70		X	1735	90	4	2.07	4.09
MISCELLANEOUS			700	30			
TOTALS			9272	150	6	6.11	9.91

SUMMARY OF EROSION CONTROL

STATION LOCATION	SALVAGED TOPSOIL (TYPE A) 205(A) (1) C.Y.	SOLID SLAB SODDING 230(A) S.Y.	FERTILIZING (10-20-10) 234(A) TON	FERTILIZING (18-46-0) 234(A) (1) TON	WATERING 230(F) K-GAL.	MOWING 241 AC.
STA. 334+75.96 TO STA. 372+03.89	2560.00	18426.00	1.84	0.29	1474.10	3.81
LINE 4						
STA. 334+76.47 TO STA. 374+74.70	1550.00	11154.00	1.12	0.17	892.30	2.30
TOTALS	4,110.00	29,580.00	2.96	0.46	2,366.40	6.11

(1) FOR INFORMATION ONLY.

SUMMARY OF REMOVALS

STATION LOCATION	REMOVAL OF HEADWALL 619(B) (1) EA	REMOVAL OF CONCRETE PAVEMENT 619(B) S.Y.	REMOVAL OF ASPHALT PAVEMENT 619(B) S.Y.	REMOVAL OF GUARDRAIL 619(B) S.Y.	REMOVAL OF CONCRETE SLOPE PROTECTION 619(B) S.Y.	REMOVAL OF CONCRETE DITCH LINER 619(B) L.F.	REMOVAL OF 6" CONCRETE DIVIDING STRIP 619(B) S.Y.	REMOVAL OF EXISTING PARAPET 619(B) LF	SAWING PAVEMENT 619(C) L.F.
	LINE 3								
STA. 334+75.96 TO STA. 347+00.00	4	311	242.20		220	0			973
STA. 347+00.00 TO STA. 362+00.00	3	1722	29.00						1499
STA. 362+00.00 TO STA. 372+03.86	3	1032							1010
LINE 4									
STA. 334+76.47 TO STA. 347+00.00				125	715	170	1027	18	160
STA. 347+00.00 TO STA. 362+00.00		1264		125					1124
STA. 362+00.00 TO STA. 374+74.70	1	1467							1284
TOTALS	11	5796	271.20	250	935	170	1027	18	6050

(1) INCLUDES UNDERDRAIN OUTLET HEADWALLS

SUMMARY OF STRIPING

TYPE	TRAFFIC STRIP (MULTI-POLYMER)							
	TRAFFIC STRIPE LF	WHITE LF	YELLOW LF	BLACK LF	6" WIDE 856(A) LF	8" WIDE 856(A) LF	12" WIDE 856(A) LF	ARROW 856(B) EA
	6" SOLID EDGE LINE	25849	13318	12531		25849		
6" (DASHED)	42750	11400		11400	22800			
8" WHITE GORE	4424					4424		
8" (DOTTED)	7245	1449		1449		2898		
12" WHITE GORE	5591						5591	
TOTALS	85859	26167	12531	12849	48649	7322	5591	78

\$DATE\$ \$TIME\$ H:\PROJECTS\203078 0001 EC-1611\Roadway\Drawings\30444106_Summary Sheets.dgn

DESIGN	
DRAWN	
CHECKED	
APPROVED	
SQUAD	POE

SUMMARY SHEET

STATE JOB NO. 30444106 SHEET NO. 12

OKLAHOMA COUNTY