# SURVEY CONTROL DATA

1. HORIZONTAL DATUM IS THE OKLAHOMA STATE PLANE COORDINATE SYSTEM, N.A.D. 83(2011) LAMBERT PROJECTION, NORTH ZONE ADJUSTED TO N.G.S. STATE PLANE COORDINATES, UTILIZING OPUS.

A. ACCURACY - 3RD ORDER OR BETTER

2. BEARINGS:

THE BEARINGS SHOWN HEREIN OR HEREON ARE GRID BEARINGS DERIVED FROM THE USC & GS OKLAHOMA PLANE COORDINATE SYSTEM AND ARE NOT ASTRONOMICAL.

3. VERTICAL CONTROLS:

A. LEVEL DATUM IS NGS, NAVD 88, TAKEN FROM ADJUSTED PRIMARY CONTROL UTILIZING DIFFERENTIAL LEVELING TECHNIQUES.
B. ACCURACY - 3RD ORDER OR BETTER

	36"	00'	57
LONGITUDE	94	32'	53
LONGHODE		OL.	-

# **DESIGN DATA**

ADT 2017	-	100
ADT 2037	57	149
V	-	45 M.P.H.
Flex. ESALs	-	0,11M
	ADT 2017 ADT 2037 V Flex. ESALs	ADT 2017 - ADT 2037 - V - Flex. ESALs -



2009 OKLAHOMA STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION GOVERN, APPROVED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION, JANUARY 4, 2010.

# STATE OF OKLAHOMA

# DEPARTMENT OF TRANSPORTATION

# PLAN OF PROPOSED BRIDGE

BRIDGE AND APPROACH PLANS

# **BALLARD CREEK ADAIR COUNTY**

PROJECT NO. STP-201C(032)CI

STATE JOB NO. 29823(04)

LOCATION: 01N4750E0690001

REMOVE NBI NO. 10065 CONSTRUCT NBI NO. 31971



PROJ	ECT LENGTH BASED ON C.R.L	
ROADWAY LENGTH:	1,183.50 FT	0.224 MILES
BRIDGE "A" LENGTH:	116.50 FT	0.022 MILES
PROJECT LENGTH:		0.246 MILES
EQUATIONS:	NONE	
EXCEPTIONS:	NONE	

A	DESCRIPTION	VISIONS	DATE
<u>/1</u>	TITLE BLOCK UPDATED		10/11/17
INIT			
IN	JEX OF SHEETS		
SHEET NO.	DESCRIPTION	l .	
0001.	TITLE SHEET		
0002.	TYPICAL SECTION A	ND MISCELLANEO	US DETAILS
AR01AR02.	SUMMARY OF PAY	QUANTITIES AND	GENERAL NOTES
B001.	BRIDGE "A" GENERA	L PLAN & ELEVA	ATION
B002.	BRIDGE "A" GEOTEC	HNICAL INFORMAT	TION
B003.	ABUTMENT DETAILS		
B004.	SUBSTRUCTURE EXC	AVATION & PIPE	ASSEMBLY DETAILS
R001.	STORM WATER MAN	AGEMENT PLAN	
R002.	EROSION CONTROL	PLAN	
R003R004.	PLAN AND PROFILE,	CRL	
R005.	PLAN AND PROFILE,	SHOOFLY	
X001X012.	X - SECTIONS		

THE FOLLOWING STANDARDS WILL BE REQUIRED FOR THIS PROJECT.

ROADWAY 2009	TRAFFIC 2009	2009 COUNTY BRIDGE
SSS-1-1	GRAU1-1-00	CB26-I-SKO-ABUT-PC5-01E
TSC2-3-2	GRH1-1-00	CB26-I-SK0-XSECT-PC5-01E
TSD-2-0	GRH2-1-00	CB26-I-SK0-LSECT-PCB-01E
TRFD-1-2	TCS1-1-01	CB26-I-SK0-DKSLB-BLIST-PCB-01E
PSE-1-0	TCS2-1-00	CB26-I-SK0-PCB-J-115-1-01E
PCES-4-1	TCS4-1-01	CB26-I-SK0-PCB-J-115-2-01E
SPI-4-1	TCS5-1-00	CB26-I-SKO-DIA-INTPR-PCB-01E
SPB-1-4	TCS6-1-02	CB26-I-SKO-BRG-PC5-01E
FHTMPP-1-0	TCS7-1-02	CB26-I-SKO-SPR-QUAN-PCB-1-01E
FHTCP-3-1	TCS8-1-00	CB26-I-SKO-AS-01E
PUD-3-2	TCS9-1-01	CB2632-I-SK0-WING-PC5-01E
RDI-3-1	TCS10-1-00	CB2632-CI-SK030-PCB-DTL-1-01E
		CB2632-CI-SK030-PCB-DTL-2-01E
		CB2632-CI-SK030-GRAU-BC-00E

2009 STATE BRIDGE TR3-2-01E HP1-2-01E

APPROVED

ADAIR COUNTY BOARD OF COMMISSIONERS

DATE

-24-177 DATE





0100 -	ROADWA	Y ROADWAY PAY QUANT	TITIES		
ITE	M	DESCRIPTION		UNITS	QUANTITY
201(A)	0102	CLEARING AND GRUBBING	(R-1)	LSUM	1.00
202(A)	0183	UNCLASSIFIED EXCAVATION	(7)	CY	3,474.00
202(C)	0182	ROCK EXCAVATION	(18)	CY	1,000.00
202(D)	0184	UNCLASSIFIED BORROW	(8)(15)(19)	CY	6,764.00
221(C)	2801	TEMPORARY SILT FENCE	(9)	LF	2,000.00
221(F)	0100	TEMPORARY SILT DIKE	(9)	LF	300.00
221(G)	0151	TEMPORARY ROCK FILTER DAM TYPE 2	(9)	CY	20.00
230(A)	2806	SOLID SLAB SODDING	(R-7)(R-8)	SY	20,581.00
233(A)	2817	VEGETATIVE MULCHING	(R-11)(17)	AC	8.50
310(B)	0149	SUBGRADE, METHOD B		SY	3,421.00
402(E)	0225	TRAFFIC BOUND SURFACE COURSE TYPE E	(10)(14)	TON	706.00
411(B)	5945	SUPERPAVE, TYPE S3 (PG 64-22 OK)	(R-31)(R-32)	TON	684.00 /
411(C)	5960	SUPERPAVE, TYPE S4 (PG 64-22 OK)	(R-30)(R-32)(11)	TON	447.00
509(D)	0325	CLASS C CONCRETE	(R-41)	CY	10.00
601(A)	0297	TYPE I PLAIN RIPRAP	(1)(12)	TON	475.00 /
613(A)	4438	88" X 54" R.C.PIPE ARCH CLASS A-III		LF	64.00
613(B)	0694	48" CORR. GALV. STEEL PIPE		LF	200.00
613(B)	4528	28" X 20" CORR. GALV. STEEL PIPE ARCH		LF	130.00
613(B)	4529	35" X 24" CORR. GALV. STEEL PIPE ARCH		LF	86.00
613(L)	4516	28" X 20" PREFAB. CULVERT END SECTION, ARCH		EA	6.00
613(L)	4522	35" X 24" PREFAB. CULVERT END SECTION, ARCH		EA	6.00
613(L)	4569	88" X 54" PREFAB. CULVERT END SECTION, ARCH		EA	2.00
619(A)	0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	(R-48)(R-49)	LSUM	1.00
856(A)	8530	TRAFFIC STRIPE (MULTI-POLYMER) (4" WIDE)	(13)	LF	5,200.00

0200 -	BRIDGE	BRIDGE "A" PAY QUA	NTITIES		
		115' X 26' CLEAR ROADWAY INTEGRAL PCB	SPAN ZERO DEGREE	SKEW	
ITE	М	DESCRIPTION		UNITS	QUANTITY
501(B)	1307	SUBSTRUCTURE EXCAVATION COMMON	(R-1)	CY	120.00
501(G)	6309	CLSM BACKFILL	(R-1)	CY	104.00 /
503(A)	6290	PRESTRESSED CONCRETE BEAMS (TYPE J BT)	(R-1)	LF	344.00
504(A)	1304	APPROACH SLAB	(B1)	SY	115.00
504(B)	1305	SAW-CUT GROOVING	(R-1)	SY	371.20
504(D)	6239	CONCRETE RAIL (TR3)	(R-1)	LF	306.60
506(A)	1322	STRUCTURAL STEEL	(R-1)	LB	820.00
507(A)	6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	10 CC	EA	6.00
509(A)	1326	CLASS AA CONCRETE	(R-1)	CY	129.00
509(B)	1328	CLASS A CONCRETE	(R-1)	CY	48.20
509(D)	1331	CLASS C CONCRETE		CY	9.30
511(A)	1332	REINFORCING STEEL	(R-1)	LB	29,390.00
514(A)	6010	PILES, FURNISHED (HP 10X42)		LF	416.00
514(B)	6292	PILES, DRIVEN (HP 10X42)	Project of a later	LF	80.00
514(K)	6260	(PL)PILOT HOLES	(B2)	LF	304.00 /
514(L)	6220	PILE SPLICE, H-PILE (NON-BIDDABLE)		EA	1.00
601(B)	1353	TYPE I-A PLAIN RIPRAP	(1)	TON	944.00
601(C)	1355	TYPE I-A FILTER BLANKET	(2)	TON	239.00
613(H)	6204	6" PERFORATED PIPE UNDERDRAIN ROUND	(B3)	LF	52.00
613(1)	6207	6" NON-PERF.PIPE UNDERDRAIN RND.	(B4)	LF	50.00
619(D)	1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	(R-49)(3)	LSUM	1.00
623(F)	5686	GUARDRAIL ANCHOR UNIT (TYPE D-BF)		EA	4.00
623(F)	6029	GUARDRAIL ANCHOR UNIT (TYPE A)	(4)	EA	4.00
880(J)	8905	CONSTRUCTION TRAFFIC CONTROL	(5)	LSUM	1.00
0640	CONSTR		s		
220	2800	SWPPP DOCUMENTATION AND MANAGEMENT		ISUM	1.00
641	1399	MOBILIZATION		LSUM	1.00

0600 -	STAKING	PAY	QUANTITIES			97
642(B)	0096 CONSTRUCTION	I STAKING LEVEL II	(	6)(16)	LSUM	1.00

					DES	CRIPTION	REV	ISIONS		DATE
					ADD	ED SUBGRA	DE. METHO	D B. ROCK	< EX	10/12/17
					AND	UNCLASSIF	TED EX.		1.50 1.05.07.525	
						SED QTIES:	TYPE 1 R	PAVE S4	SM, TBSC,	10/12/17
					AUPD	ATED PAY	TEM NUMB	FR - UNC	LASS. BORROW	10/12/17
					ADD	ED COLUMN	FOR ASP	HALT DRIVE	S	10/12/17
		SUMMARY		CE STRU	TUPES				1	
		SOMMART		LUC STRO	STORES	DODA		DOEC		
	CTATION	DECODIDITION	CGSP	08"200"	SPA	RCPA	00"200"	PUES	00"454"	
SIR. NU.	STATION	DESCRIPTION	(FEET)	(FEET)	(FEET)	(FEET)	(EACH)	(EACH)	(EACH)	
1	23+75.00 LT	CGSP SIDE DRAIN		30			2	j		
2	24+54.00 RT	CGSP SIDE DRAIN		38			2			
3	26+50.00 RT	CGSP SIDE DRAIN			30			2		
4	26+74.00 LT	CGSP SIDE DRAIN			28			2		
5	27+88.00 LT	CGSP SIDE DRAIN		32			2			
6	28+16.00 LT	TEMPORARY		30						
7	28+82.30 LT	TEMPORARY	200							
8	30+35 X-ING	RCPA CROSS DRAIN				64			2	
9	32+00.00 RT	CGSP SIDE DRAIN			28			2		
			200	130	86	64	6	6	2	

	SUMMAR	Y OF DRIVES			
STATION	DESCRIPTION	SIZE	TBSC (TON)	AC (TON)	
23+75.00 LT	RURAL DRIVE	10' x 35'		17.00	
24+54.00 RT	RURAL DRIVE	18' X 34'		27.00	
26+50.00 RT	RURAL DRIVE	12' X 26'	14.00		
26+74.00 LT	RURAL DRIVE	12' X 207'	77.00	13.00	
32+00.00 RT	RURAL DRIVE	12' X 25'	14.00		
		TOTALS	105.00	57.00	

CONSTRUCT ALL DRIVES PER STD. RDI-3, LATEST REVISION.

	SUMN	IARY	OF GUARDRA	AILS	
STATION TO STATION	LT.	RT.	TYPE D-BF (EACH)	TYPE A (EACH)	LENGTH INCLUDING ANCHOR UNITS (FEET)
26+97.72 - 27+97.72	X		1	1	100.00
26+97.72 - 27+97.72		X	1	1	100.00
29+48.88 - 30+48.88	×		1	1	100.00
29+48.88 - 30+48.88		X	1	1	100.00
	TOT	ALS	4	4	400.00

STATION TO STATION	LT.	RT.	TYPE 1 RIPRAP (TON)
26+00 - 26+54	X		3
26+00 - 26+31		X	2
26+67 - 27+94		X	7
26+91 - 27+94	X		6
31+50 - 34+00	×		14
31+50 - 31+82		X	2
32+18 - 34+00		X	10
	TOT	ALS	44

# BALLARD CREEK ADAIR COUNTY SUMMARY OF PAY QUANTITIES AND GENERAL NOTES (SHEET 1 OF 2) JOB PIECE NO. 29823(04) SHEET NO. AR01

# ENVIRONMENTAL MITIGATION NOTES:

### AMERICAN BURYING BEETLE NOTE

THE AMERICAN BURYING BEETLE IS A LARGE CARRION BURYING BEETLE THAT OCCURS WITHIN THE ACTION AREA. NO ARTIFICIAL LIGHTING SHALL BE USED DURING CONSTRUCTION. CARCASSES AND ALL FOOD TRASH SHALL BE REMOVED FROM THE PERMANENT ROW AND TEMPORARY ROW THROUGHOUT PROJECT ACTIVITIES. FOLLOWING CONSTRUCTION, TOPSOIL SHALL BE PLACED ON TOP OF ALL AREAS OF GROUND DISTURBANCE, PRIOR TO RE-VEGETATION.

BAT BRIDGE SEASONAL RESTRICTION NOTE: THE GRAY BAT, INDIANA BAT, OZARK BIG-EARED BAT AND THE NORTHERN LONG-EARED BAT ARE LISTED BAT SPECIES THAT OCCUR WITHIN THE PROJECT'S ACTION AREA. IN ORDER TO AVOID AND MINIMIZE ADVERSE IMPACTS TO LISTED BAT SPECIES, BRIDGE DEMOLITION SHALL BE RESTRICTED TO BETWEEN NOVEMBER 16, AND MARCH 31, OUTSIDE OF THE ACTIVE SEASON. IF BRIDGE DEMOLITION DURING THE ACTIVE SEASON (BETWEEN APRIL 1, AND NOVEMBER 15) CANNOT BE AVOIDED, THE RESIDENT ENGINEER SHALL CONTACT THE ODOT BIOLOGIST AT 405-521-2515 TO SCHEDULE A BAT BRIDGE INSPECTION, PRIOR TO ANY BRIDGE WORK INSPECTION SURVEYS CAN ONLY BE CONDUCTED BETWEEN MAY 15. AND AUGUST 15. IF THE SURVEY FINDS LISTED BAT SPECIES WITHIN THE PROJECT'S ACTION AREA, BRIDGE DEMOLITION SHALL ONLY BE PERMITTED BETWEEN NOVEMBER 16, AND MARCH 31 (WHEN BATS ARE HIBERNATING IN CAVES).

### BAT TREE REMOVAL SEASONAL RESTRICTION NOTE:

THE GRAY BAT, INDIANA BAT, OZARK BIG-EARED BAT AND NORTHERN LONG-EARED BAT ARE LISTED BAT SPECIES THAT OCCUR WITHIN THE PROJECT'S ACTION AREA. IN ORDER TO AVOID ADVERSE IMPACTS TO THE SPECIES, ALL TREE REMOVAL SHALL BE RESTRICTED TO BETWEEN NOVEMBER 16, AND MARCH 31 (OUTSIDE THE BATS' ACTIVE SEASON). IF TREE REMOVAL DURING THE ACTIVE SEASON (BETWEEN APRIL 1, AND NOVEMBER 15) CANNOT BE AVOIDED, THE RESIDENT ENGINEER SHALL CONTACT THE ODOT BIOLOGIST AT 405-521-2515 TO SCHEDULE A BAT ACOUSTIC SURVEY, PRIOR TO ANY TREE REMOVAL. ACOUSTIC SURVEYS CAN ONLY BE CONDUCTED BETWEEN MAY 15 AND AUGUST 15. IF THE SURVEY FINDS LISTED BAT SPECIES WITHIN THE PROJECT'S ACTION AREA, TREE REMOVAL SHALL ONLY BE PERMITTED BETWEEN NOVEMBER 16, AND MARCH 31 (WHEN BATS ARE HIBERNATING IN CAVES).

### BAT TREE REMOVAL LIMITS NOTE:

THE GRAY BAT, INDIANA BAT, OZARK BIG-EARED BAT AND NORTHERN LONG-EARED BAT ARE LISTED SPECIES THAT OCCUR WITHIN THE PROJECT'S ACTION AREA. IN ORDER TO AVOID AND MINIMIZE ADVERSE IMPACTS TO THESE SPECIES, THE REMOVAL OF TREES AND SHRUBS SHALL BE RESTRICTED TO AREAS WITHIN THE ACTUAL LIMITS OF CONSTRUCTION (TOE OF SLOPE/TOP OF CUT). THE RESIDENT ENGINEER SHALL INSTALL BRIGHT-COLORED FLAGGING/FENCING TO INDICATE WHICH TREES ARE NOT TO BE REMOVED AND ENSURE LIMITS OF TREE REMOVAL ARE VISIBLY AND CLEARLY DEFINED FOR THE CONTRACTOR. THE RESIDENT ENGINEER SHALL ALSO PROVIDE BEFORE AND AFTER PHOTO-DOCUMENTATION TO THE ODOT BIOLOGIST OF EXTENT OF TREE CLEARING WITHIN THE PROJECT AREA.

### BAT WATER QUALITY NOTE:

THE GRAY BAT, INDIANA BAT, OZARK BIG-EARED BAT AND NORTHERN LONG-EARED BAT ARE LISTED SPECIES THAT OCCUR WITHIN THE PROJECT'S ACTION AREA. IN ORDER TO AVOID AND MINIMIZE ADVERSE IMPACTS TO LISTED BAT SPECIES, APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE IMPACTS FROM STORM WATER DISCHARGES, AS ESTABLISHED BY THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY, SHALL BE CONSCIENTIOUSLY IMPLEMENTED THROUGHOUT THE PROPOSED CONSTRUCTION PERIODS. THE EFFECTIVENESS OF EROSION CONTROLS SHALL BE MAINTAINED FOR THE DURATION OF CONSTRUCTION ACTIVITIES. HAZARDOUS MATERIALS, CHEMICALS, FUELS, LUBRICATING OILS, AND OTHER SUCH SUBSTANCES SHALL BE STORED AT LEAST 100 FEET FROM THE OHWMS. REFUELING OF CONSTRUCTION EQUIPMENT SHALL ALSO BE CONDUCTED AT LEAST 100 FEET FROM THE OHWMS. SEDIMENT AND EROSION CONTROLS SHALL BE INSTALLED AROUND STAGING AREAS TO PROHIBIT DISCHARGE OF MATERIALS FROM THESE SITES. CONSTRUCTION WASTE MATERIALS AND DEBRIS SHALL BE STOCKPILED AT LEAST 25 FEET OUTSIDE OF THE OHWMS, AND THESE MATERIALS SHALL BE REMOVED AND DISPOSED OF PROPERLY FOLLOWING COMPLETION OF THE PROJECT.

### BAT LIGHTING NOTE:

THE GRAY BAT, INDIANA BAT, OZARK BIG-EARED BAT AND NORTHERN LONG-EARED BAT ARE LISTED SPECIES THAT OCCUR WITHIN THE PROJECT'S ACTION AREA. IN ORDER TO AVOID AND MINIMIZE ADVERSE IMPACTS TO LISTED BAT SPECIES, IF ANY PERMANENT LIGHTING IS INSTALLED OR REPLACED, DOWNWARD-FACING FULL CUT-OFF LENS LIGHTS SHALL BE INSTALLED AND DIRECTED AWAY FROM WOODED AREAS AND STREAMS

KARST NOTE

ALTHOUGH A SURVEY HAS BEEN COMPLETED TO IDENTIFY KARST FEATURES, SUCH AS CAVES, SINKHOLES, LOSING STREAMS AND SPRINGS, PRIOR TO THE PROJECT, THERE IS A POTENTIAL TO UNCOVER KARST FEATURES DURING CONSTRUCTION. KARST FEATURES ARE POTENTIAL HABITAT FOR FEDERALLY THREATENED AND ENDANGERED SPECIES, INCLUDING BATS. UNDISCOVERED UNDISCOVERED KARST FEATURES MAY OCCUR ON OR NEAR PROJECT SITES, EVEN IN PREVIOUSLY DEVELOPED AREAS. IF KARST FEATURES ARE ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL ESTABLISH A BUFFER AREA OF 300 FEET AROUND THE NEWLY DISCOVERED FEATURE, AND THE RESIDENT ENGINEER SHALL CONTACT THE ODOT BIOLOGIST AT 405-521-2515. THE ODOT BIOLOGIST SHALL CONTACT THE US FISH AND WILDLIFE SERVICES (USFWS) TO FURTHER EVALUATE THE KARST FEATURE. NO FILL MATERIAL SHALL BE PLACED INTO THE KARST FEATURE OPENING, AND ALL PARKING, MAINTENANCE, STAGING, FUELING, STORM WATER MANAGEMENT ACTIVITIES, GROUND-DISTURBING, TREE-CLEARING, OR ANY OTHER CONSTRUCTION ACTIVITY SHALL BE ALLOWED WITHIN THE 300-FOOT BUFFER, UNTIL EVALUATION BY USFWS IS COMPLETE. IF KARST FEATURES ARE DETERMINED TO BE HABITAT FOR FEDERALLY-LISTED OR SENSITIVE SPECIES, A FORMAL CONSULTATION WITH USFWS SHALL BE REQUIRED BEFORE THE CONSTRUCTION CAN RESUME. THIS CONSULTATION MAY TAKE UP TO 180 DAYS AFTER THE INITIAL EVALUATION OF THE KARST FEATURES AND THE CONTRACTOR SHALL NOT BE COMPENSATED FOR ANY DELAYS DURING THAT TIME. IN SOME CASES, MODIFICATION TO THE PROJECT MAY BE NECESSARY THAT WOULD RESULT IN A CHANGE ORDER.

## MIGRATORY BIRD NOTE

MIGRATORY BIRDS ARE PROTECTED BY THE FEDERAL MIGRATORY BIRD TREATY ACT. MANY BIRDS COMMONLY USE BRIDGES AND CULVERTS FOR NESTING. THE NESTING SEASON FOR MOST MIGRATORY BIRD SPECIES EXTENDS FROM MARCH 1 TO AUGUST 31. MIGRATORY BIRD NESTING USE OF THE NS-475 BALLARD CREEK BRIDGE (NBI: 10065) WAS OBSERVED. PAINTING, REPAIR. RETROFIT, REHABILITATION OR DEMOLITION OF THE EXISTING BRIDGE SHALL BE CONDUCTED BETWEEN SEPTEMBER 1, AND FEBRUARY 28, WHEN MIGRATORY BIRD NESTS ARE NOT OCCUPIED. IF PAINTING, REPAIR, RETROFT, REHABILITATION OR DEMOLITION CANNOT 28, WHEN MIGRATORY BIRD NESTS ARE NOT OCCUPIED. IF PAINTING, REPAIR, RETROFT, REHABILITATION OR DEMOLITION CANNOT BE COMPLETED BETWEEN SEPTEMBER 1 AND FEBRUARY 28, THE BRIDGE SHALL BE PROTECTED FROM NEW NEST ESTABLISHMENT PRIOR TO MARCH 1, BY MEANS THAT DO NOT RESULT IN BIRD DEATH OR INJURY. OPTIONS INCLUDE THE EXCLUSION OF ADULT BIRDS FROM SUITABLE NEST SITES ON OR WITHIN A STRUCTURE BY THE PLACEMENT OF WEATHER-RESISTANT POLYPROPYLENE NETTING WITH 0.25-INCH OR SMALLER OPENINGS, PRIOR TO MARCH 1. METHODS OTHER THAN NETTING MUST BE PRE-APPROVED WE THE OPOL DEVOLUTION. BY THE ODOT BIOLOGIST

CULTURAL RESOURCES PLAN NOTE: LOCATIONS OUTSIDE THE PROJECT AREA IN THE FOLLOWING AREA MUST NOT BE UTILIZED FOR BORROW, EQUIPMENT STAGING, HAUL ROADS, SPOIL DUMPS OR ANY OFF-SITE PROJECT-RELATED ACTIVITY.

T18N R26E:

SECTION	16:	SW1/4 SW1/4 SW1/4
SECTION	20:	S1/2 SE1/4
SECTION	29:	NE1/4 SW1/4 NE1/4
		SE1/4 SE1/4 SW1/4
SECTION	32:	SE1/4 NW1/4 NE1/4
		NE1/4 SW1/4 NE1/4

- (1) ESTIMATED AT 110 LBS./CU. FT.
- (2) ESTIMATED AT 105 LBS./CU. FT.
- (3) ITEM "REMOVAL OF EXISTING BRIDGE STRUCTURE" CONSISTS OF REMOVAL AND DISPOSAL OF A 5-10' CONCRETE SLAB SPAN BRIDGE. COST OF REMOVAL SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR "REMOVAL OF EXISTING BRIDGE STRUCTURE." REMOVAL AND DISPOSAL SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR IN ACCORDANCE WITH SECTION 619.04 (b)2 OF THE SPECIFICATIONS AND IN A MANNER APPROVED BY THE ENGINEER.
- (4) PRICE BID TO INCLUDE THE COST OF 4 TYPE 1 CODE 3 DELINEATORS (AMBER COLOR).

- CONSTRUCTION TRAFFIC CONTROL SHALL INCLUDE ALL BARRICADES AND SIGNS REQUIRED ON EACH (5) END OF THE CONSTRUCTION AREA AND OTHER AREAS DESIGNATED BY THE ENGINEER. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION SIGNS, BARRICADES, LIGHTS, ETC ACCORDING TO THE STANDARDS SET FORTH IN THE <u>MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES</u>, CURRENT EDITION, AND AS SHOWN ON THE STANDARD DRAWINGS. COST OF ALL NECESSARY CONSTRUCTION SIGNING WILL BE INCLUDED IN THE LUMP SUM PRICE BID FOR "CONSTRUCTION TRAFFIC CONTROL
- (6) IN ADDITION TO THE RESPONSIBILITIES SHOWN IN THE SPECIFICATIONS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND/OR REESTABLISHING THE SURVEY CONTROL POINTS SHOWN ON THE PLANS, STAKING THE CENTERLINE OF CONSTRUCTION AND REESTABLISHING RIGHT-OF-WAY STAKES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND VERIFYING BENCH MARKS SHOWN ON THE PLANS AND FOR ESTABLISHING NEW BENCH MARKS AS NEEDED TO CONSTRUCT THE PROJECT. (7) INCLUDES COST TO BREAK UP EXISTING ASPHALT PAVEMENT TO A SIZE OF NOT MORE THAN THREE
- INCHES TO BE INCORPORATED INTO ROADWAY EMBANKMENT.
- INCLUDES COST OF SALVAGING AND PLACING TOPSOIL APPROXIMATELY 28 FEET WIDE TAPERING TO 100 FEET WIDE BY 5 INCHES DEEP FROM STA. 20+00 TO STA. 35+40 AND 18-46-0 FERTILIZER (ESTIMATED AT 150 LBS PER ACRE). SEE TOPSOIL NOTE, SHEET NO. 0002.
- (9) PRICE BID TO INCLUDE COST OF TEMPORARY SEDIMENT REMOVAL.
- (10) INCLUDES 105 TONS FOR RURAL DRIVES AND 461 TONS FOR SHOOFLY (INCLUDES TEMPORARY DRIVE).
- (11) INCLUDES 61 TONS FOR FOR GUARD RAIL WIDENING AND 57 TONS FOR DRIVES.
- ▲ (12) PRICE BID TO INCLUDE EXCAVATION FOR PLACEMENT IN ACCORDANCE WITH SPECIAL DETAIL, SHEET NO. 0002. (ESTIMATED AT 0.67 C.Y./TON)
- (13) INCLUDES 2,600 L.F. YELLOW FOR DOUBLE CENTER STRIPE AND 2,600 L.F. WHITE FOR EDGE STRIPES. (14) ESTIMATED AT 140 LBS/C.F.
- (15) THE CONTRACTOR MUST PROVIDE TESTING RESULTS FROM A CERTIFIED LAB THAT THE BORROW SITE IS FREE FROM DISPERSIVE CLAYS AS REQUIRED IN SECTION 202.02(A) IN THE 2009 SPEC. BOOK BEFORE ANY MATERIAL CAN BE PLACED ON THE PROJECT.
- (16) ESTABLISHMENT AND RE-ESTABLISHMENT OF HORIZONTAL AND VERTICAL CONTROL, INCLUDING THE SETTING AND RE-SETTING OF BENCHMARKS AND THE STAKING AND RE-STAKING OF RIGHT-OF-WAY, WILL BE INCLUDED IN THE PRICE BID FOR STAKING.
- (17) QUANTITY BASED ON 4.25 ACRES AT TWO APPLICATIONS.
- (18) TO BE USED IF ROCK ENCOUNTERED IN CUT SECTIONS IS NOT RIPPABLE ACCORDING TO SECTION 202.03 OF THE SPECIFICATIONS, OR AT THE DISCRETION OF THE ENGINEER. CONTRACTOR SHALL REVIEW GEOTECHNICAL REPORT AND VERIFY SITE CONDITIONS BEFORE BIDDING.
- (19) INCLUDES 500 C.Y. TO ACCOUNT FOR REPAIR OF OVER EXCAVATION WHICH MAY OCCURE IF ROCK IS ENCOUNTERED.

## PAY QUANTITY NOTES

- (R-1) PAYMENT FOR THIS ITEM WILL BE BASED ON PLAN QUANTITY ONLY. SEE SECTION 109.01B OF THE STANDARD SPECIFICATIONS.
- (R-7) FOR 230(A) PRICE BID TO INCLUDE COST OF 10-20-10 FERTILIZER, ESTIMATED AT 200 LBS. PER 1,000 SQUARE YARDS.
- (R-8) FOR 230(A) PRICE BID TO INCLUDE COST OF WATERING, ESTIMATED AT 80 GALLONS PER SQUARE YARD
- (R-11) THE QUANTITY ESTIMATED FOR TEMPORARY EROSION AND SEDIMENT CONTROL IS 4.25 ACRES. ▲(R-30) PRICE BID TO INCLUDE COST OF 570 GALLONS OF TACK COAT MEETING THE REQUIREMENTS OF
- SECTION 407 OF THE STANDARD SPECIFICATIONS. ▲(R-31) PRICE BID TO INCLUDE COST OF 1,210 GALLONS OF PRIME COAT MEETING THE REQUIREMENTS
- OF SECTION 408 OF THE STANDARD SPECIFICATIONS AND ESTIMATED AS 0.35 GAL. PER SQ. YD. ON TOP OF COMPLETED SUBGRADE AND 0.25 GAL PER SQ. YD. ON TOP OF AGGREGATE BASE. THE ACTUAL CUTBACK PRIME COAT REQUIRED FOR PLACEMENT OPERATIONS WILL BE DETERMINED BY THE CONTRACTOR AND SHALL CONSIDER THE RESIDUE FROM DISTILLATION PERCENTAGE SHOWN IN SECTION 708.03 OF THE STANDARD SPECIFICATIONS.
- (R-32) ESTIMATED AT 112 LBS. PER SQ. YD. PER 1" THICK.
- (R-41) QUANTITY INCLUDES AN ESTIMATED 10 C.Y. TO BE USED AS DIRECTED BY THE ENGINEER. (R-48) INCLUDES REMOVAL OF ALL EXISTING ROADWAY DRAINAGE STRUCTURES, HEADWALLS (UNLESS
- OTHERWISE SPECIFIED), INLETS, FENCES AND OTHER STRUCTURES WITHIN THE RIGHT-OF-WAY. (R-49) TO BECOME THE PROPERTY OF AND BE DISPOSED OF BY THE CONTRACTOR IN A MANNER APPROVED BY THE ENGINEER.
- THE APPROACH SLABS CONTAIN AN ESTIMATED TOTAL OF 41.5 C.Y. OF CLASS AA CONCRETE AND 8,900 LB. OF REINFORCING STEEL. INCLUDE ALL COSTS FOR CONSTRUCTING THE APPROACH B1 LABS, INCLUDING CONCRETE, REINFORCING STEEL, BACKER ROD, RAPID CURE JOINT SEALANT, POLYETHYLENE, POLYSTYRENE, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK, IN THE CONTRACT UNIT PRICE OF "APPROACH SLAB".
- B2 PAY ITEM "(PL) PILOT HOLES" CONSISTS OF DRILLING 16 PILOT HOLES, 19 FT. DEEP, FOR ABUTMENT BRIDGE SEATS. SEE STAKING DIAGRAM FOR DETAILS OF PILOT HOLES. ALL COST INCLUDING LABOR, EQUIPMENT, CLASS C CONCRETE, GRANULAR BACKFILL, CASING AND INCIDENTALS NECESSARY TO COMPLETE THE WORK SHALL BE INCLUDED IN THE UNIT PRICE BID PER LINEAR FOOT OF "(PL) PILOT HOLES."
- B3 INCLUDE ALL COSTS ASSOCIATED WITH PROVIDING AND INSTALLING THE PERFORATED PIPE AND PIPE UNDERDRAIN COVER MATERIAL (BOTH FILTER SAND AND COARSE), INCLUDING ALL MATERIAL, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK, IN THE CONTRACT UNIT PRICE OF "6" PERFORATED PIPE UNDERDRAIN ROUND". INSTALLATION SHALL BE AS SHOWN IN THE PLANS AND ON STD. PUD-3.
- EXTENT, LOCATION AND DEPTH OF NON-PERFORATED PIPE UNDERDRAIN MAY BE ADJUSTED BY Β4 THE ENGINEER DURING CONSTRUCTION. INCLUDE ALL COSTS ASSOCIATED WITH PROVIDING AND INSTALLING THE NON-PERFORATED PIPE, AND STANDARD BEDDING MATERIAL, INCLUDING ALL TRENCH EXCAVATION, MATERIAL, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK IN THE CONTRACT UNIT PRICE OF "6" NON-PERF. PIPE UNDERDRAIN RND. INSTALLATION SHALL BE AS SHOWN IN THE PLANS AND ON STD. PUD-3.

SPECIFICATIONS: COMPLY WITH THE REQUIREMENTS OF THE 2009 OKLAHOMA STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, AS APPROVED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION JANUARY 4, 2010, EXCEPT AS MODIFIED BY THE PLANS AND SPECIAL PROVISIONS.

ALL FLOWLINES THAT ARE TO BE FILLED SHALL BE THOROUGHLY TAMPED BEFORE CONSTRUCTION OR EXTENSION OF DRAINAGE STRUCTURES. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

CREEK AND RIVER BANKS SHALL BE KEPT IN THEIR NATURAL STATE AS MUCH AS POSSIBLE. THE CONTRACTOR SHALL NOT UNDULY STRIP EXISTING PROTECTIVE VEGETATION IN THE VICINITY OF THE STREAM BANKS AND SHALL SO CONDUCT HIS OPERATIONS AS NOT TO DAMAGE THE BANKS WITH HIS FOUIPMENT NO BANK UPSTREAM OR DOWNSTREAM SHALL BE EXCAVATED EXCEPT AS APPROVED. FOR AND AS SHOWN ON THE PLANS. NO WORK ROADS SHALL BE CONSTRUCTED UPSTREAM WHERE IS NECESSARY TO CUT THE STREAM OR RIVER BANKS EXCEPT BY THE APPROVAL OF THE ENGINEER. BANK CUTS FOR WORK ROADS SHALL BE LOCATED DOWNSTREAM AND REPLACED BY THE CONTRACTOR TO THEIR ORIGINAL SHAPE AND DENSITY. UNNECESSARY STRIPPING OF VEGETATION GROWTH ALONG BANKS IN THE CONSTRUCTION AREA IS NOT PERMITTED.

THE FOLLOWING ITEMS WILL BE THE RESPONSIBILITY OF THE COUNTY AND NOT A PART OF THIS CONTRACT: (1) ACQUISITION AND STAKING OF RIGHT-OF-WAY; (2) UTILITY RELOCATION; (3) REMOVAL AND RESETTING OF MAIL BOXES; (4) DETOUR SIGNING, IF REQUIRED; (5) TEMPORARY AND PERMANENT FENCING, (6) REMOVAL AND RESETTING OF CATTLE GUARDS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION SIGNING.

CONTRACTOR SHALL PROVIDE ACCESS TO ADJACENT LAND OWNERS AND TENANTS. (CAUTION) THE LOCATION AND DEPTH OF ALL UTILITIES AS SHOWN ON THE PLANS ARE APPROXIMATE AND SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES HE MAY INFLICT TO THE EXISTING UNDERGROUND UTILITIES WITHIN

THE PROJECT AREA AS A RESULT OF HIS DIGGING, TRENCHING, BORING, ETC. PRIOR TO DIGGING NEAR UTILITIES. IN ACCORDANCE WITH THE OKLAHOMA UNDERGROUND FACILITIES DAMAGE PREVENTION ACT THE CONTRACTOR SHALL NOTIFY THE OKLAHOMA ONE-CALL SYSTEM, INC. 48 HOURS PRIOR TO BEGINNING EXCAVATION. OKLAHOMA ONE-CALL SYSTEM, INC. "CALL OKIE1" 1-800-522-6543 OR 811.

THE USE OF OFFROAD OR OVERWEIGHT HAUL TRUCKS SHALL NOT BE ALLOWED DURING CONSTRUCTION OF THIS PROJECT.

THE CONTRACTOR SHALL NOTIFY THE ADAIR COUNTY BOARD OF COMMISSIONERS, CED 2 OFFICE, AND ODOT DIVISION 1, IN WRITING, FOURTEEN CALENDAR DAYS PRIOR TO BEGINNING CONSTRUCTION.

	REVISIONS DESCRIPTION	DATE
$\mathbb{A}$	ENVIRONMENTAL NOTES REVISED	10/11/17
$\overline{\mathbb{A}}$	SHEET NUMBER UDPATED	10/11/17
$\mathbb{A}$	TACK COAT QUANTITY UPDATED	10/11/17
$\triangle$	PRIME COAT QUANTITY UPDATED	10/11/17

GENERAL NOTES

AIR VENTS: 2" PVC PIPE SHALL BE PLACED VERTICALLY THROUGH THE DECK BETWEEN THE BEAMS AS SHOWN IN THE DETAIL SHOWN ON SHEET NO. BOO1, GENERAL PLAN AND ELEVATION.

ALL TREES, BRUSH AND OTHER DEBRIS THAT MIGHT INTERFERE WITH THE FLOW OF WATER SHALL BE CLEANED OUT TO THE RIGHT-OF-WAY LINE, AT EACH STRUCTURE AND BRIDGE, IN A MANNER APPROVED BY THE ENGINEER. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

ROADWAY SHALL REMAIN OPEN TO THROUGH TRAFFIC DURING THE CONSTRUCTION PERIOD.

PILE DRIVING AND CAPACITY -

THE FACTORED REACTION FOR EACH HP 10x42 PILE AT THE ABUTMENT IS 73.7 TONS ON BRIDGE "A".

THE FOLLOWING FORMULA (GATES EQUATION) SHALL BE USED TO DETERMINE THE AXIAL LOAD RESISTANCE OF THE DRIVEN FOUNDATION PILES.

AXIAL LOAD RESISTANCE =  $\emptyset$  [(0.875  $\sqrt{E}$  LOG<sub>10</sub>(10N))-50]

WHERE  $\phi$  = RESISTANCE FACTOR OF 0.4

E = ENERGY PRODUCED BY THE HAMMER PER BLOW IN FOOT-POUNDS. FOR GRAVITY AND SINGLE ACTING DIESEL HAMMERS. THE VALUE IS BASED ON THE ACTUAL RAM STROKE OBSERVED IN THE FIELD AND MEASURED IN FEET MULTIPLIED BY THE RAM WEIGHT IN POUNDS N = AVERAGE NUMBER OF HAMMER BLOWS PER INCH OF PILE PENETRATION FOR THE LAST 10 TO 20 BLOWS DELIVERED TO THE PILE HEAD.

THE ABOVE FORMULA IS ONLY APPLICABLE WHEN: - THE PILE DRIVING HAMMER HAS A FREE FALL (GRAVITY AND SINGLE ACTING HAMMERS ONLY). - THE HEAD OF THE PILE IS NOT BROOMED, CRUSHED OR OTHERWISE DAMAGED. - THE PENETRATION IS QUICK AND UNIFORM - THERE IS NO APPRECIABLE REBOUND OF THE HAMMER AND A FOLLOWER IS NOT USED.

THE NUMBER OF BLOWS PER INCH OF PILE PENETRATION MAY BE MEASURED EITHER DURING INITIAL DRIVING OR BY RE-DRIVING WITH A WARM HAMMER OPERATED AT FULL ENERGY AFTER A PILE SET PERIOD, AS DETERMINED BY THE ENGINEER. IF WATER JETS ARE USED IN CONNECTION WITH THE DRIVING, DETERMINE THE AXIAL LOAD RESISTANCE BY THE FORMULA ONLY AFTER THE JETS HAVE BEEN WITHDRAWN.





BRIDGE "A" PAY QUANTITIES								
115' X 26' CLEAR ROADWAY INTEGRA	L PCB S	SPAN ZERO I	DEGREE SKE	w				
DESCRIPTION	UNITS	ABUTS.	SUPSTR.	APPROACH	TOTALS			
RE EXCAVATION COMMON	CY	120.00			120.00			
ILL	CY	104.00			104.00			
D CONCRETE BEAMS (TYPE J BT)	LF		344.00		344.00			
SLAB	SY			115.00	115.00			
ROOVING	SY		282.40	88.80	371.20			
AIL (TR3)	LF	73.60	233.00		306.60			
STEEL	LB		600.00	220.00	820.00			
STEEL FIXED BEARING ASSEMBLY	EA		6.00		6.00			
ONCRETE	CY		129.00		129.00			
NCRETE	CY	48.20			48.20			
NCRETE	CY	9.30			9.30			
STEEL	LB	7,600.00	21,790.00		29,390.00			
ISHED (HP 10X42)	LF	416.00			416.00			
N (HP 10X42)	LF	80.00			80.00			
DLES	LF	304.00			304.00			
H-PILE (NON-BIDDABLE)	EA	1.00			1.00			
_AIN RIPRAP	TON	944.00			944.00			
LTER BLANKET	TON	239.00			239.00			
TED PIPE UNDERDRAIN ROUND	LF	52.00			52.00			
RF. PIPE UNDERDRAIN RND.	LF	50.00			50.00			
EXISTING BRIDGE STRUCTURE	LSUM	1.00			1.00			
ANCHOR UNIT (TYPE D-BF)	EA	4.00			4.00			
ANCHOR UNIT (TYPE A)	EA	4.00			4.00			
ON TRAFFIC CONTROL	LSUM	1.00			1.00			
ED ON ESTIMATED QUANTITY OF 2 DER TO MEET ULTIMATE PILE CAPA	1 L.F. CITY.	PLUS ADD	ITIONAL 5 L	.F. PER PILE	THAT MAY			

Х	26'	CLEAR	ROADWAY
N	SKE	NED ZE	RO
3	CON	ICRETE	RAILS.
N.	281	73 30	



	ſ				
<u>A A A</u>	<u>A</u>				
31 55					
DGE "A"					
888	U				
~					
- · · ·					
	/				
	1100				
	1095				
	1090				
	1085				
	1075				
	1070				
	1065				
GROUND	1060	WATER LEVELS			
	1055 .	▼ AFTER COMPLET	TION		
WEL E	1050				
KEAM	1045	BRIDGE "A"- 115' X INTEGRAL PCB SPAN	26' ( SKEW	CLEAR ROADWAY	
	1040	CENTERLINE STATION	28+7	.REIE KAILS. 3.30.	
	1035	EXISTING STRUCTURE SLAB SPAN BRIDGE.	- 5- (REMC	10' CONCRETE DVE)	
	1030	BALLARD CREEK			ADAIR COUNTY
	1025	BRIDGE	E "A"	GEOTECH	NICAL
	1020		INFO	RMATION	
		JOB PIECE	NO	29823(04)	_SHEET NO. <u>B002</u>









TYPICAL SECTION THRU BRIDGE SEAT



DETAIL OF CONSTRUCTION JOINTS

	PILE SCHEDULE								
SPAN	TOTAL NUMBER OF PILES	N SPACES	A	В	С	MAXIMUM FACTORED PILE LOAD			
110'	8	3	3'-4"	1'-8"	2'-10"	71.9 TON			
115'	8	3	3'-4"	1'-8"	2'-10"	73.7 TON			
120'	8	3	3'-4"	1'-8"	2'-10"	75.4 TON			
125'	9	4	3'-0"	0'-0"	2'-6"	68.6 TON			
130'	9	4	3'-0"	0'-0"	2'-6"	70.1 TON			
135'	9	4	3'-0"	0'-0"	2'-6"	71.6 TON			

		l	BAR L	IST -	ONE ABU	TMENT
	MARK	NO.	SIZE	FORM	LENGTH	LENGTH VARIATION
	BH1	8	#8	STR.	28'-8"	-
	BH2	12	#4	STR.	288.	-
	BV1	60	#5	STR.	6'-5"	-
	P1	18	#4	BNT.	4'-11"	-
	P2	12	#4	BNT.	7'-2"	-
	WT1	2	#4	BNT.	5'-2"	-
	WI2	2	#8	BNT.	11'-2"	-
D	WT3	10	#4	STR.	5'-7" AVG.	3'-7" TO 7'-7"
D	WT4	10	#8	BNT.	6'-11" AVG.	4'-11" TO 8'-11"
_	ADDIT	IONAL	BARS	TO BE	USED WITH 8	B PILE ABUTMENTS
	BH3	24	#4	BNT.	3'-7"	-
	BS1	48	#4	BNT.	12'-9"	-
	ADDIT	IONAL	BARS	TO BE	USED WITH S	PILE ABUTMENTS
	BH3	27	#4	BNT.	3'-7"	-
	BS1	46	#4	BNT.	12'-9"	

1 NO. INCLUDES TWO SETS OF 5 BARS

SUMMARY OF QUANTITIES - ONE	ABUT	MENT (2)
ITEM	UNIT	TOTAL
SUBSTRUCTURE EXCAVATION, COMMON	CY	30.00
CLSM BACKFILL	CY	52.00
CLASS A CONCRETE	CY	12.10
REINFORCING STEEL	LB	2,120.00
PILES, FURNISHED (HP 10X42)	LF	-
PILES, DRIVEN (HP 10X42)	LF	-
6" PERFORATED PIPE UNDERDRAIN	LF	26.00
6" NON-PERFORATED PIPE UNDERDRAIN	LF	-

2 EXCLUDES WINGS

# NOTES

ABUTMENT WING CONCRETE SHALL NOT BE POURED UNTIL THE ABUTMENT DIAPHRAGMS OF THE SUPERSTRUCTURE AND THE DECK SLAB CONCRETE HAVE ATTAINED A STRENGTH OF 3,000 PSI.

ALL WT WING REINFORCING STEEL TIED TO BRIDGE SEAT REINFORCING STEEL MUST BE IN PLACE PRIOR TO POURING THE BRIDGE SEAT CONCRETE.

BALLARD CREEK

ADAIR COUNTY

# **ABUTMENT DETAILS**

JOB PIECE NO. 29823(04) 



BALLARD	CREEK
---------	-------

ADAIR COUNTY

JOB PIECE NO. 29823(04) 

# STORM WATER MANAGEMENT PLANA

# SITE DESCRIPTION

## PROJECT LIMITS:

EVISED BY ODOT 07/13/2017

PROJECT LIES ALONG N-S SECTION LINE 475 WITHIN SECTIONS 28 AND 29, T-18-N, R-26-E, ADAIR COUNTY, OKLAHOMA.

PROJECT DESCRIPTION:
CONSTRUCTION OF A 115' PCB SPAN AND APPROACH ROADWAYS.
SUCCESTED SECUENCE OF FRASION CONTROL ACTIVITIES.
SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES.
VEGETATIVE STRIPPING, UNDERCUT AND STOCKPILE TOPSOIL.
ROADWAY EXCAVATION AND EMBANKMENT.
INSTALL SILT FENCE, DIKES WITHIN PROJECT LIMITS.
ABUTMENT CONSTRUCTION.
PLACE CHANNEL RIPRAP.
COMPLETE BRIDGE CONSTRUCTION.
CULVERT TRENCHING AND CONSTRUCTION.
VEGETATIVE MULCHING.
CONST. FINISHED ROADWAY PAVING.
SPREAD TOPSOIL.
INSTALL SOLID SLAB SOD.
SOIL TYPE: BOONE UNIT
TOTAL AREA OF THE 4.25 AC
STIMATED AREA TO BE DISTURBED: 4.25 AC
OFFSITE AREA TO BE DISTURBED:
TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION:0.54 AC
TOTAL IMPERVIOUS AREA POST-CONSTRUCTION:0.66 AC
POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE:0.44
LATITUDE & LONGITUDE
PROJECT WILL DISCHARGE TO:
NAME OF RECEIVING WATERS: BALLARD CREEK
ENSITIVE WATERS OR WATERSHEDS: YES $\times$ NO
303(d) IMPAIRED WATERS: YES $\times$ NO
IF YES, LIST IMPAIRMENT: ENTEROCOCCUS
LOCATED IN A TMDL: YES NO $\times$
LAKE THUNDERBIRD TMDL: YES NO $\times$
MS4 ENTITY YES NO $\times$
IF YES, LOCATION:
NOTE: THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

# EROSION AND SEDIMENT CONTROLS

# SOIL STABILIZATION PRACTICES:

- \_\_\_\_\_ TEMPORARY SEEDING
- \_\_\_\_\_ PERMANENT SODDING, SPRIGGING OR SEEDING
- X VEGETATIVE MULCHING
- \_\_\_\_\_ SOIL RETENTION BLANKET
- \_\_\_\_\_ PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

## STRUCTURAL PRACTICES:

- \_\_\_\_\_ STABILIZED CONSTRUCTION EXIT \_\_\_\_\_ TEMPORARY SILT FENCE \_\_\_X\_\_ TEMPORARY SILT DIKES
- \_\_\_\_\_ TEMPORARY FIBER LOG
- \_\_ DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- \_\_\_ DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- \_\_X\_\_ ROCK FILTER DAMS
- \_\_\_\_\_ TEMPORARY SLOPE DRAIN
- \_\_\_\_ PAVED DITCH W/ DITCH LINER PROTECTION
- \_ TEMPORARY DIVERSION CHANNELS
- TEMPORARY SEDIMENT BASINS
- \_\_\_\_ TEMPORARY SEDIMENT TRAPS
- \_ TEMPORARY SEDIMENT FILTERS
- \_\_\_\_X TEMPORARY SEDIMENT REMOVAL
- \_\_X\_\_ RIP RAP
- \_\_ INLET SEDIMENT FILTER
- \_\_\_\_\_ TEMPORARY BRUSH SEDIMENT BARRIERS
- \_\_\_ SANDBAG BERMS
- \_ TEMPORARY STREAM CROSSINGS

## OFFSITE VEHICLE TRACKING:

- \_\_\_\_X HAUL ROADS DAMPENED FOR DUST CONTROL
- \_\_\_\_X\_\_ LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- \_\_\_\_\_ EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

# THE PROGRESSION OF THE PROJECT.

## THE FOLLOWING SECTIONS OF THE BE NOTED:

# 103.05 BONDING REQUIREMENTS

# 104.10 FINAL CLEANING UP

220	MANAGEMENT OF EROSION, SE
221	TEMPORARY SEDIMENT CONTR

# IN ADDITION:

_									
	PEVISIONS								
	DESC	RIPTION	IX.		10113			DATE	
$\mathbb{A}$	SWMP	SHEET	UPDATED	ΤO	NEW	FORMAT		10/11/	17

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:
MAINTENANCE AND INSPECTION: ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.
WASTE MATERIALS:
PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.
HAZARDOUS MATERIALS:
PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.
GENERAL NOTES:
A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.
THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:
103.05BONDING REQUIREMENTS104.10FINAL CLEANING UP104.12CONTRACTOR'S RESPONSIBILITY FOR WORK104.13ENVIRONMENTAL PROTECTION106.08STORAGE AND HANDLING OF MATERIAL107.01LAWS, RULES AND REGULATIONS TO BE OBSERVED107.20STORM WATER MANAGEMENT220MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL221TEMPORARY SEDIMENT CONTROLINADDITION:
STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.
BALLARD CREEK ADAIR COUNTY
STORM WATER MANAGEMENT

JOB PIECE NO. 29823(04) SHEET NO. ROO1

PLAN



EROSION CONTROL QUANTITIES				
DESCRIPTION		UNITS	Q	
TEMPORARY SILT FENCE	(1)	LF	2,	
TEMPORARY SILT DIKE	(1)	LF		
SOLID SLAB SODDING		SY	20,	
VEGETATIVE MULCHING	(2)	AC		
ROCK FILTER DAM (TYPE 2)	(1)	CY		
CLASS C CONCRETE	(3)	CY		
TYPE 1 PLAIN RIPRAP		TON		
TYPE 1-A PLAIN RIPRAP		TON		
TYPE 1-A FILTER BLANKET		TON		





CRL



JOB PIECE NO. \_\_\_\_\_29823(04) Sheet No. \_\_\_\_

R004

























