



ABUT. 1

ABUT. 2

31169(04)

0200 BRIDGE 135' P.C. BEAM SPAN TYPE J, 26'-0" CL RDWY, TR3-2

SUMMARY OF PAY QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	ABUT 1	ABUT 2	RETAINING WALL #1	RETAINING WALL #2	SUPERSTR	WINGS	TOTAL
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	CY	65.00	65.00				80.00	210.00
501(G)	6309 CLSM BACKFILL	CY	60.00	60.00					120.00
503(A)	6281 PRESTRESSED CONCRETE BEAMS (TYPE J BT)	LF					404.00		404.00
504(A)	1304 APPROACH SLAB	SY	57.40	57.40					114.80
504(B)	1305 SAW-CUT GROOVING	SY	43.98	43.98			335.30		423.26
504(D)	6239 CONCRETE RAIL (TR3)	LF					276.40	70.80	347.20
506(A)	1322 STRUCTURAL STEEL	LB.					970.00		970.00
507(A)	6172 WEATHERING STEEL FIXED BEARING ASSEMBLY	EA	3.00						3.00
507(B)	6176 WEATHERING STEEL EXPANSION BEARING ASSEMBLY	EA		3.00					3.00
509(A)	1326 CLASS AA CONCRETE	CY					117.20		117.20
509(B)	1328 CLASS A CONCRETE	CY	25.50	25.50	36.70	29.40		30.40	147.50
510(A)	6334 RETAINING WALL	SY			103.90	83.20			187.10
511(A)	1332 REINFORCING STEEL	LB	3,440.00	3,440.00			25,420.00	5,000.00	37,300.00
511(B)	6010 EPOXY COATED REINFORCING STEEL	LB			5,470.00	4,390.00			9860.00
514(A)	6010 PILES, FURNISHED (HP 10X42)	LF						317.46	317.46
514(A)	6011 PILES, FURNISHED (HP 12X53)	LF	537.50	526.91				0.00	1064.41
514(B)	6292 PILES, DRIVEN (HP 10X42)	LF						317.46	317.46
514(B)	6294 PILES, DRIVEN (HP 12X53)	LF	537.50	526.91					1064.41
514(K)	6260 (PL)PILOT HOLES	LF		526.91					526.91
514(L)	6220 PILE SPLICE, H-PILE (NON-BIDDABLE)	EA							1.00
516(A)	6094 DRILLED SHAFTS 48" DIAMETER	LF			96.00	80.00			176.00
601(B)	1353 TYPE I-A PLAIN RIPRAP	TON	251.46	222.21					473.67
601(I)	6312 FILTER BLANKET (RIPRAP)	SY	310.44	274.33					584.78
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	LSUM							1.00
622(A)	4545 2" PIPE RAILING	LF			54.00	42.00			96.00

E-1844/DAIRY LANE ATOKA COUNTY
 SOUTHEAST #3 CIRCUIT ENGINEERING DISTRICT
 STAKING LAYOUT
 STATE JOB NO. 31169(04) SHEET NO. B005