
OKLAHON	IA DEPA	ARTMENT OF	TRAN	SPORTA	TION
FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL
	OKLA.				
DESCRIPTION		REVISIONS			DATE

Found existing local evidence, fences and such. Set a #4 Rebar with Cap 0.5' below the surface of the gravel road proportionately between Section Corners. Said point is one foot east and 32.5' south of existing fence corner to north. This point is also approximately 33.7 feet north of the end of the irrigation sprinkler to south. Corner as established appears to agree with local evidence and evidence of occupation has viewed from 2010 NAIP Imagery. I accepted said position assigned said corner ODOT Monument No. C–8–1211.

(9128)-

Set a #4 Rebar with Cap 0.5' below the surface of the gravel road on line between section corners and north of center brace post per parole evidence given by Claytie Recker in regard to north—south quarter line location. A point on line between section corners is close to the middle of the existing roadway. Corner as established appears to agree with local evidence and evidence of occupation has viewed from 2010 NAIP Imagery. I assigned said corner ODOT Monument No. C–8–1224.



2628.40′ N 89°29′02.02″ W

REF. 1 - SET 60 W SIDE CORNER POST 1.0"HIGH 30.52" S 48"49"54" E
REF. 2 - NEAR FACE GATE POST 76.71" S 26"13"53" W
REF. 3 - SET 60 N SIDE MARKER POST 0.6"HIGH 57.73" S 33"52"51" W

9028-

Found a PK Nail flush with the surface of the asphalt and two of the references per CCR by Randy Mosley, PLS 1082, dated January 31, 1990 and two of the references per CCR by Miles M. Wood, PLS 1384, dated June 30, 2003. He states that he found a PK Nail in location of Spike as per PLS 1082. According to DDOT SAP No. 775(2) Part 1 Plans dated 1951 and SWO 1704(1) Project SAP 775(2), Caddo County, SH 58 Field Book there were references marked in the headwalls of the side drain west of the intersection. The plans and field book denote that this structure had 45* wings, but the structure in place has 90* headwalls. The "X"'s found in said headwalls are in the area indicated on said plans and as denoted in said field book. Both references are within 0.7' and the computed position, based on said references, if accepted, would be 0.1 South and 0.7' west of found Monument which closely agrees with said references per recorded CCR's. Being no more different than described, I accepted PK Nail for corner and assigned it ODOT Monument No. C—8—1213.

Found an 80d Nail 0.2' below the surface of the asphalt road, by others, corner as found appears to agree with local evidence and evidence of occupation has viewed from 2010 NAIP Imagery. I accepted the 80d Nail for corner and assigned said corner ODOT Monument No. C-8-1222.

Mosley, PLS 1082, dated March 31, 1990. He states that he found a PK Nail and replaced it with a large spike. The PK Nail found closely fits his recorded references. Also found a reference, an "X" on top of a headwall, taken from the field book for ODOT SW01704(1) Survey, Project SAP775(2), completed in February 2, 1951 at Station 71+53.8, also refers to WPA Plans 7-84A dated 1919. Could not find the corresponding "X" on the other headwall, but if the one "X" found is per the above information, it appears that said monument found would be within less than 1.0 foot of the intersection of said reference and the existing centerline of SH58. Therefore I accepted the PK Nail found for the Southwest Corner of Section 27 and assigned it ODOT Measurest Na Center 13 (200).

REF. 1 - FOUND 60D SE SIDE PP 4"HIGH

2648.23

REF. 2 - FOUND 60D SW SIDE POWER POLE 1'HIGH 63.20' S 55°26'55" W REF. 3 - FOUND 60D NW SIDE POWER POLE 3'HIGH 67.27' N 44°27'30" W

SCALE 1" = 50

NOTE: REFERENCE'S SHOWN ARE NOT TO SCALE.

PLS	GSR		OKLAHOMA DEPARTMENT OF TRANSPORTATION SURVEY DIVISION
DRAWN	JMW		SURVET DIVISION
CHECKED			SURVEY DATA SHEET
APPROVED			
CREW	EIR	eno	SWO 4864 (I) PROJECT NO. 24092(04) SHEET NO. 5031

Found a #3 Rebar 1.3' below the surface of the roadway, by others, corner as found appears to

agree with local evidence and evidence of occupation has viewed from 2010 NAIP Imagery, I accepted the #3 Rebar for corner and assigned said corner ODOT Monument No. C-8-1223.