

REVISIONS		
REV. NO.	DESCRIPTION	DATE

SUMMARY OF FENCING						
SHEET NO.	STATION TO STATION	SIDE	FENCE	FENCE	NOTES	
			SWF (5 BW)	SWF (6 BW)		
			624(C)	624(C)		
			LF	LF		
R011	100+43.00 TO 101+52.00	LT.	109			
R011	100+40.00 TO 107+80.00	RT.	740			
R011	105+00.00 TO 105+89.00	LT.	89			
R011	106+11.00 TO 112+00.00	LT.	589			
R011	107+96.00 TO 114+00.00	RT.	604			
R012	114+00.00 TO 126+00.00	RT.	1,200			
R012	126+00.00 TO 129+00.00	RT.	300			
R013	129+00.00 TO 144+00.00	RT.	1,500			
R014	146+24.00 TO 154+23.00	LT.	799			
R014	144+00.00 TO 152+16.00	RT.	816			
R014	154+53.00 TO 159+00.00	LT.	447			
R015	159+00.00 TO 161+06.00	LT.	206			
R015	161+86.00 TO 163+50.00	LT.	164			
R015	163+50.00 TO 169+00.00	LT.	550			
R015	164+00.00 TO 165+48.00	RT.	148			
R015	165+81.00 TO 170+32.00	RT.	451			
R015	169+00.00 TO 173+85.00	LT.	485			
R016	174+66.00 TO 177+37.00	LT.	271			
R016	178+01.00 TO 179+50.00	LT.	149			
R016	179+50.00 TO 182+50.00	LT.	300			
R016	182+50.00 TO 189+00.00	LT.	650			
R016	183+50.00 TO 189+00.00	RT.	557			
R017	189+00.00 TO 192+47.00	LT.	347			
R017	189+00.00 TO 194+38.00	RT.	538			
R017	195+19.00 TO 201+00.00	LT.	581			
R017	195+08.00 TO 204+00.00	RT.	892			
R017	201+00.00 TO 204+00.00	LT.	300			
R018	204+00.00 TO 204+90.00	LT.	90			
R018	204+00.00 TO 204+75.00	RT.	75			
R018	205+57.00 TO 206+39.00	RT.	82			
R018	206+59.00 TO 212+00.00	RT.	541			
R018	209+96.00 TO 215+25.00	LT.	529			
R018	212+00.00 TO 215+00.00	RT.	300			
R018	215+00.00 TO 219+00.00	RT.	400			
R018	215+25.00 TO 219+00.00	LT.	375			
R019	219+00.00 TO 223+00.00	LT.	400			
R019	219+00.00 TO 231+12.00	RT.	1,212			
R019	223+00.00 TO 227+64.00	LT.	464			
R019	228+28.00 TO 233+47.00	LT.	519			
R019	233+60.00 TO 234+00.00	LT.	40			
R020	234+00.00 TO 241+47.00	LT.	747			OWNER TO HANG GATES. CONTRACTOR TO SET POSTS TO ACCOMMODATE 2-10' STEEL TUBE GATES.
R020	241+59.00 TO 245+50.00	LT.	413			
R021	249+00.00 TO 252+50.00	LT.	350			
R021	252+50.00 TO 257+50.00	LT.	500			
R021	258+13.00 TO 259+50.00	LT.	137			
R021	259+50.00 TO 262+41.00	LT.	298			
R021	262+54.00 TO 264+50.00	LT.	196			
R022	264+00.00 TO 265+00.00	LT.	100			
R022	265+00.00 TO 267+15.00	LT.	215			
R022	267+48.00 TO 279+00.00	LT.	1,152			
R023	279+00.00 TO 282+53.00	LT.	353			
R023	281+00.00 TO 282+12.00	RT.	134			
R023	282+57.00 TO 284+17.00	RT.	338			
R023	284+17.00 TO 294+00.00	RT.		983		
R023	282+95.00 TO 294+00.00	LT.	1,105			
R024	294+00.00 TO 297+89.00	LT.	389			
R024	294+00.00 TO 297+91.00	RT.		391		
R024	298+07.00 TO 309+00.00	RT.		1,093		
R024	298+14.00 TO 309+00.00	LT.	1,086			
R025	309+00.00 TO 310+01.00	LT.	101			
R025	309+00.00 TO 310+16.00	RT.		116		
R025	310+01.00 TO 310+21.00	LT.		20		
R025	312+63.00 TO 324+00.00	RT.		1,137		
R026	324+00.00 TO 326+91.00	RT.		291		
TOTAL **			26,951	4,112		

** INCLUDES ADDITIONAL 2% FOR GROUND MEASUREMENT.

SUMMARY OF SURFACING								
SHEET NO.	STATION TO STATION	STABILIZED	AGG. BASE	TBSC	TACK COAT	PRIME COAT	SUPER PAVE TYPE S3	SUPER PAVE TYPE
		SUBGRADE	TYPE 'A'	TYPE E			(PG 64-22 OK)	S4 (PG 64-22 OK)
		307(K)	303(A)	402(E)	407(B)	408	411(B)	411(C)
		SY	CY	TON	GAL	GAL	TON	TON
R011	100+10.65 TO 114+00	720.4	867.5	653.6	579.8	2,653.7	829.9	415.1
R012	114+00 TO 129+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R013	129+00 TO 144+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R014	144+00 TO 159+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R015	159+00 TO 174+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R016	174+00 TO 189+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R017	189+00 TO 204+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R018	204+00 TO 219+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R019	219+00 TO 234+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R020	234+00 TO 249+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R021	249+00 TO 264+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R022	264+00 TO 279+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R023	279+00 TO 294+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R024	294+00 TO 309+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R025	309+00 TO 324+00	777.8	792.2	705.6	626.0	2,865.0	896.0	448.1
R026	324+00 TO 329+08	263.4	268.3	239.0	212.0	970.3	303.4	151.8
TOTAL		11,873	12,227	10,771	9,556	43,734	13,677	6,841

SUMMARY OF EROSION CONTROL						
SHEET NO.	STATION TO STATION	TEMPORARY	TEMPORARY	SOLID SLAB	VEGETATIVE	TYPE I PLAIN
		SILT FENCE	SILT DIKE	SODDING	MULCHING	RIPRAP
		221 (C)	221 (F)	230(A)	233(A)	601(A)
		L.F.	EA.	S.Y.	AC.	TONS
R003	100+00.00 TO 129+00.00	335	29	17,400	7	82
R004	129+00.00 TO 159+00.00	1,100	20	10,854	4	0
R005	159+00.00 TO 189+00.00	1,202	30	12,962	5	111
R006	189+00.00 TO 219+00.00	1,632	24	13,574	6	389
R007	219+00.00 TO 249+00.00	0	30	12,052	5	0
R008	249+00.00 TO 279+00.00	927	24	12,778	5	0
R009	279+00.00 TO 309+00.00	633	29	9,293	4	0
R010	309+00.00 TO 339+00.00	655	17	8,712	4	41
TOTAL		6,484	203	97,623	40	623

SUMMARY OF GUARDRAIL			
STATION TO STATION	SIDE	BEAM GUARDRAIL	GUARDRAIL END
		(W-BEAM) SINGLE	TREATMENT (GET)
		623(A)	623(G)
	LT. RT.	L.F.	EA.
164+87.50 TO 167+37.50	X	150	2
173+50.00 TO 174+50.00	X	0	2
178+00.00 TO 181+75.00	X	275	2
202+50.00 TO 204+50.00	X	100	2
TOTAL		525	8

MAIL BOX & TURNOUT SCHEDULE							
SHEET NO.	STATION	AGG. BASE	PRIME	TACK	SUPERPAVE	SUPERPAVE	REMOVE AND
		TYPE 'A'	COAT	COAT	TYPE S3	TYPE S4	RESET MAILBOX
		303(A)			(PG 64-22 OK)	(PG 64-22 OK)	629(E)
		CY	GAL	GAL	TON	TON	EA
R014	154+10.00	3.7	5.6	1.7	4.98	2.49	1.00
R026	326+88.00	6.3	9.4	2.8	8.46	4.23	1.00
TOTAL		10.00	15.00	4.50	13.44	6.72	2.00

SUMMARY OF REMOVALS					
SHEET NO.	STATION TO STATION	REMOVAL OF	REMOVAL OF	REMOVE	SAWING
		CONC. DITCH	ASPHALT	EXISTING PIPE	PAVEMENT
		LINER	PAVEMENT		
		619(B)	619(B)	619(B)	619(B)
		L.F.	S.Y.	L.F.	L.F.
R011	100+10.65 TO 114+00	-	-	62	345
R012	114+00 TO 129+00	-	-	41	-
R013	129+00 TO 144+00	-	-	-	-
R014	144+00 TO 159+00	-	-	127	-
R015	159+00 TO 174+00	-	-	256	-
R016	174+00 TO 189+00	-	-	100	-
R017	189+00 TO 204+00	-	-	158	-
R018	204+00 TO 219+00	-	-	292	-
R019	219+00 TO 234+00	-	-	227	-
R020	234+00 TO 249+00	-	-	-	-
R021	249+00 TO 264+00	-	-	115	-
R022	264+00 TO 279+00	-	-	73	-
R023	279+00 TO 294+00	-	-	38	-
R024	294+00 TO 309+00	-	-	26	-
R025	309+00 TO 324+00	-	3,698	279	26
R026	324+00 TO 329+08	-	1,317	60	64
TOTAL		0	5,015	1,854	435

DESIGN		CALUMET ROAD	CANADIAN CO.
DRAWN		OKLAHOMA DEPARTMENT OF TRANSPORTATION	
CHECKED		SUMMARY SHEET (1)	
APPROVED			
SQUAD	MKEC		
		STATE JOB NO. 27858(04)	SHEET NO. AR02

N:\AF45-CALUMET RD-CANADIAN COUNTY DRAWINGS\SUMMARY SHEET 1.DWG 9/5/2017