TRAFFIC GENERAL CONSTRUCTION NOTES

THE CONTRACTOR SHALL PROVIDE A PERSON TO BE ON 24 HOUR CALL AS NEEDED AS DETERMINED BY THE ENGINEER. THIS PERSON SHALL HOLD A CURRENT CERTIFICATION FROM THE AMERICAN TRAFFIC SAFETY SERVICE ASSOCIATION (ATSSA) OR THE OKLAHOMA TRAFFIC ENGINEERING ASSOCIATION (OETA) AS A TRAFFIC CONTROL TECHNICIAN OR TRAFFIC CONTROL SUPERVISOR

ALL TEMPORARY TRAFFIC CONTROL DEVICES SHALL MEET ODOT'S "QUALITY STANDARDS FOR TEMPORARY TRAFFIC CONTROL DEVICES." CHANNELIZING DEVICES SHALL HAVE A MINIMUM HEIGHT OF 36 INCHES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF THE TEMPORARY TRAFFIC CONTROL DEVICES, AND SHALL BE RESPONSIBLE FOR REPAIRING OR REPLACING ANY DEVICE DURING CONSTRUCTION.

TRAFFIC PAY QUANTITY NOTES

- THE CONTRACTOR SHALL FURNISH AND INSTALL SUCH LIGHTS, SIGNS, BARRICADES, AND PROVIDE FLAGGERS NECESSARY FOR THE CONTROL, SAFETY, AND MAINTENANCE OF TRAFFIC WHEN (TC-1) INSTALLING, RELOCATING OR DELIVERING PORTABLE LONGITUDINAL BARRIER
- QUANTITY INCLUDES SUFFICIENT LENGTH OF PORTABLE LONGITUDINAL BARRIER TO PROVIDE (TC-2) FOR THE LONGEST SECTION SHOWN ON THE PLANS. THIS SAME BARRIER WILL BE USED ON OTHER DETOUR PHASES.
- INCLUDES AN ESTIMATED 1.500 L.F. (PAINT) (4" WIDE) WHITE 1.000 L.F. (PAINT)(4" WIDE) YELLOW STRIPE. (TC-17)
- ALL STRIPING TO BE PLACED ON TEMPORARY SURFACES OR ON SURFACES SCHEDULED TO BE (TC-20) REMOVED SHALL BE DONE WITH PAINT UNLESS OTHER WISE NOTED ON THE PLANS OR STANDARD DRAWINGS. TEMPORARY PAVEMENT MARKINGS PLACED ON FINISHED PAVEMENT OR EXISTING PAVEMENT TO REMAIN IN PLACE SHALL USE ONE OF THE FOLLOWING METHODS: •REMOVABLE PAVEMENT MARKING TAPE •CLASS A PAVEMENT MARKERS

- (TC-21) INCLUDED IN THE COST OF THIS ITEM SHALL BE INSTALLATION, MAINTENANCE, AND REMOVAL. THIS ITEM SHALL BE BID ACCORDINGLY.
- ALL CONSTRUCTION TRAFFIC CONTROL WILL BE IMPLEMENTED ACCORDING TO CONSTRUCTION PLANS. (TC-26) AND INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND COMPLIANT WITH APPLICABLE 0.D.O.T. STANDARD DRAWINGS, PRICE BID FOR THIS ITEM SHALL BE PAYMENT IN FULL FOR THE INSTALLATION, MAINTENANCE AND SUBSEQUENT REMOVAL OF ALL NECESSARY CONSTRUCTION TRAFFIC CONTROL DEVICES REQUIRED FOR COMPLETION OF THE PROJECT. ALL SIGNS AND BARRICADES WHICH ARE SHOWN WITH TYPE 'A' LIGHTS IN THE STANDARD DRAWINGS SHALL HAVE THE CORRESPONDING LIGHT ATTACHED DURING NON-DAYLIGHT HOURS.
- INCLUDED IN THIS ITEM ARE ALL S.C.S. (SPECIAL CONSTRUCTION SIGNING) SIGNS WHICH ARE BETWEEN (TC-30) 16.0 S.F. AND 32.99 S.F. ALSO INCLUDED IN THIS ITEM SHALL BE THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF THESE SIGNS.
- ALL CONSTRUCTION WORK ZONE SIGNS SHALL HAVE FLUORESCENT SHEETING. THE FLUORESCENT SHEETING (TC-33) SHALL MEET THE REQUIREMENTS OF ASTM D4956 (LATEST REVISION) THE MANUFACTURER SHALL FURNISH A TYPE 'D' CERTIFICATION IN ACCORDANCE WITH O.D.O.T. STANDARD SPECIFICATIONS (CURRENT EDITION) SUBSECTION 106.04. THE CERTIFICATION SHALL INCLUDE TEST RESULTS ON MATERIAL SUBMITTED FOR APPROVAL
- ANY USED CONSTRUCTION ZONE IMPACT ATTENUATOR AND CHANGEABLE MESSAGE SIGN TO BE PLACED ON THIS (TC-52) TO ASSURE THAT THEY ARE IN GOOD WORKING CONDITION PRIOR TO PLACEMENT ON THE PROJECT.
- (TC-70) THIS ITEM IS AN ESTIMATED QUANTITY TO BE USED AS DEEMED NECESSARY BY THE ENGINEER.
- TEMPORARY PAVEMENT MARKINGS SHALL BE IN PLACE THE SAME DAY THAT EXISTING PAVEMENT (TC-75) MARKINGS ARE REMOVED FROM ANY ROADWAY OPEN TO TRAFFIC, ALSO, ALL TEMPORARY PAVEMENT MARKINGS SHALL BE REMOVED PRIOR TO THE INSTALLATION OF FINAL STRIPING.
- INCLUDED IN THIS ITEM SHALL BE ONE (1) ADDITIONAL UNIT TO BE USED AS A STAND-BY OR REPLACEMENT. THIS STAND-BY UNIT SHALL BE IMMEDIATELY ACCESSIBLE TO REPLACE A DAMAGED, STOLEN OR (TC-80) MALEUNCTIONING UNIT. THE AMOUNT OF TIME BETWEEN THE REMOVAL OF THE DAMAGED UNIT AND THE INSTALLATION OF THE STAND-BY UNIT SHALL BE NO MORE THAN TWENTY-FOUR (24) HOURS.
- 250 CONSTRUCTION CALENDAR DAYS WERE USED TO COMPUTE THE SIGN DAY PAY ITEMS. THE (TC-84) AMOUNT OF CALENDAR DAYS USED TO COMPUTE THE SIGN DAY PAY ITEMS IS AN ESTIMATED QUANTITY ONLY, BASED ON THE CURRENT O.D.O.T. STANDARDS AND SUGGESTED CONSTRUCTION SEQUENCE FOR THIS PROJECT. THESE ESTIMATED SIGN DAY QUANTITIES MAY CHANGE AS THE PROJECT'S CONSTRUCTION TRAFFIC CONTROL IS MODIFIED DURING CONSTRUCTION.
- THESE SIGNS MUST BE ON THE OKLAHOMA DEPARTMENT OF TRANSPORTATION LIST OF APPROVED CHANGEABLE MESSAGE SIGNS. FOR A LIST OF THE APPROVED SIGNS GO TO THE OKLAHOMA DEPARTMENT OF TRANSPORTATION WEBSITE AT: http://www.okladot.state.ok.us/traffic/qpl/index.php (TC-85)

SPECIAL NOTES

PORTABLE CHANGEABLE MESSAGE SIGNS TO BE PLACED WHERE DEEMED NECESSARY BY THE ENGINEER. (SP-1)

(SP-2) PORTABLE CHANGEABLE MESSAGE SIGN(S) SHALL BE PLACED 14 DAYS PRIOR TO CONSTRUCTION.

(SP-3) TYPE "C" WARNING LIGHTS ARE NOT REQUIRED

	0300 TRAFFIC CONTROL					
	PAY ITEM	CODE NO.	DESCRIPTION		UNIT	QUANTITY
\triangle	823	8478	(SP) PORTABLE TRAFFIC SIGNAL SYSTEM	(TC-80,84)	SD	250.00
	857(A)	8839	CONSTRUCTION TRAFFIC STRIPE(PAINT)(4" WIDE)	(TC-17,20,70,75)	LF	2,500.00
	857(C)	8857	REMOVABLE PAVEMENT MARKING TAPE(8" WIDE)	(TC-21,70)	LF	72.00
\triangle	871(B)	8705	(SP)CONST.ZONE IMPACT ATTEN.	(TC-52,70,80)	SD	1,000.00
	877(B)	8484	DELIVER PORTABLE LONGITUDINAL BARRIER	(TC-1,2)	LF	875.00
	877(C)	8486	RELOCATION OF PORTABLE LONGITUDINAL BARRIER	(TC-1)	LF	875.00
\triangle	880(B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	(TC-26,33,84)	SD	2,000.00
\triangle	880(B)	8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	(TC-26,33,84)	SD	500.00
\triangle	880(B)	8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	(TC-26,30,33,84)	SD	2,500.00
\triangle	880(C)	8848	WING BARRICADES	(TC-26,84)	SD	1,000.00
\triangle	880(E)	8860	WARNING LIGHTS(TYPE A)	(TC-26,84)	SD	2,000.00
\triangle	880(F)	8878	DRUMS	(SP-3)(TC-26,84)	SD	5,000.00
\triangle	880(G)	8890	CHANNELIZER CONES	(TC-26,84)	SD	7,500.00
\triangle	882(A)	8306	PORT. CHANGEABLE MESSAGE SIGN	(SP-1,2)(TC-52,84,85)	SD	528.00

	REVISIONS
REV. NO.	DESCRIPTION
Δ	REVISED CALENDAR DAYS

9/20/17

PAY QUANTITY SCHEDULE

