


7/17/2017 p:\lapp-pws01-345-agency.OK\locat:ODOT\Projects\Documents\Projects\Division 7\JP27968-04\Roadway\Plan Sheets\27968 (04) -SUMMARY SHEET

SUMMARY OF TEMPORARY SEDIMENT CONTROL			
LOCATION		TEMPORARY SILT FENCE 221 (C)	TEMPORARY SILT DIKE 221 (F)
STATIONS	DESCRIPTION	FT	FT
107+00.00	ACROSS DITCH LT. OF C		7
109+00.00	ACROSS DITCH LT. OF C		7
119+25.00	ACROSS DITCH LT. OF C		7
124+00.00	ACROSS DITCH LT. OF C		7
129+00.00	ACROSS DITCH LT. OF C		7
132+00.00	ACROSS DITCH LT. OF C		7
VARIOUS LOCATIONS TO BE DETERMINED BY THE ENGINEER		1,000	28
TOTALS		1,000	70

SUMMARY OF GUARDRAIL								
LOCATION		LANE		BEAM GUARDRAIL W-BEAM SINGLE 623(A)	ANCHOR UNITS		TOTAL PANEL LENGTH FT.	DELINEATORS 853 EA.
STATION TO STATION	LEFT	RIGHT	G.E.T. (31') 623(G)		GUARDRAIL BRIDGE CONN-THRIE BEAM (31') 623(I)			
				L.F.	EA.	EA.		
115+48.95 TO 117+64.58		X		137.50	1	1	203.13	4
116+73.95 TO 117+64.58	X			25.00	1	1	90.63	2
119+55.64 TO 121+70.67	X			137.50	1	1	203.13	4
119+55.04 TO 120+45.67		X		25.00	1	1	90.63	2
TOTAL				325.00	4	4		12

SUMMARY OF EROSION CONTROL					
STATIONS		WORK AREA	PERMANENT	TEMPORARY	
			SOLID SLAB SODDING 230(A)	SEEDING METHOD 'B' 232(B)	VEGETATIVE MULCH 233(A)
			SQ. YD.	ACRES	ACRES
102+00.00 TO 117+93.98	1		31,850	6.58	6.58
119+25.64 TO 139+00.00	1		34,914	7.21	7.21
TOTAL			66,764	13.79	13.79

SUMMARY OF FENCE				
LOCATION		LANE	FENCE-STYLE SWF (5 BARBED WIRE) 624(C)	FENCE-STYLE SWF (6 BARBED WIRE) 624(C)
STATION TO STATION			L.F.	L.F.
101+00.00 TO 114+83.00	LT			1,411.19
115+83.00 TO 118+01.12	LT			218.21
126+52.02 TO 139+50.00	LT		1,288.50	
TOTAL			1,288.50	1,629.40



EROSION CONTROL TYPICAL SECTION

1 - SOLID SLAB SODDING
 TEMPORARY SEEDING AND VEGETATIVE MULCH SHALL BE USED FOR TEMPORARY EROSION CONTROL.

DESIGN	LS		OKLAHOMA DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION SUMMARY SHEET (ROADWAY) STATE JOB NO. 27968(04) SHEET NO. AX02. <small>US 277 COMANCHE COUNTY</small>
DRAWN			
CHECKED			
APPROVED			
SQUAD	GREEN		