•	REVISION	3
REV. NO.	DESCRIPTION	DATE
1407.110.	DEGGEN TOT	DA16

	APPROACH SLAB QUANTITIES (PHASE I)									
1	ITEM	UNIT	APPROACH SLAB NO. 1	APPROACH SLAB NO. 2	TOTAL					
	APPROACH SLAB	S.Y.	70.30	70.30	140.60					
	SAW-CUT GROOVING	S.Y.	66.70	66.70	133.40					
	CONCRETE RAIL (TR4)	L.F.	30.00	30.00	60.00					
	MECHANICAL SPLICE	EA.	31.00	31.00	62.00					
	WATER REPELLENT (VISUALLY INSPECTED)	S.Y.	14.0	14.0	28.0					


		BAR	LIST				BARI	_IST	
/	4PPR(SLABN	IO. 1	4	APPRO		SLAB N	O. 2
		(PHA	SE I)				(PHA:	SE I)	
MARK	SIZE	NO.	FORM	LENGTH	MARK	SIZE	NO.	FORM	LENGTH
EPOXY COATED REINFORCING				EPOXY COATED REINFORCING					
AT1	#4	31	STR.	20'-9"	AT1	#4	31	STR.	20'-9"
AT2	#4	31	STR.	20'-11"	AT2	#4	31	STR.	20'-11"
AL1	#4	22	STR.	29'-10"	AL1	#4	22	STR.	29'-10"
AL2	#9	33	STR.	29'-10"	AL2	#9	33	STR.	29'-10"
SR1	#5	92	BNT.	4'-1"	SR1	#5	92	BNT.	4'-1"


	APPROACH SLAB QUANTITIES (PHASE II)								
	ITEM	UNIT	APPROACH SLAB NO. 1	APPROACH SLAB NO. 2	TOTAL				
1	APPROACH SLAB	S.Y.	70.30	70.30	140.60				
	SAW-CUT GROOVING		66.70	66.70	133.40				
	CONCRETE RAIL (TR4)	L.F.	30.00	30.00	60.00				
	WATER REPELLENT (VISUALLY INSPECTED)	S.Y.	14.0	14.0	28.0				


	BAR LIST APPROACH SLAB NO. 1					BAR LIST APPROACH SLAB NO. 2				
	(PHASE II)					(PHASE II)				
MARK	MARK SIZE NO. FORM LENGTH						SIZE	NO.	FORM	LENGTH
EPO	EPOXY COATED REINFORCING					EPOXY COATED REINFORCING				ORCING
AT1	#4	31	STR.	20'-9"		AT1	#4	31	STR.	20'-9"
AT2	#4	31	STR.	20'-11"		AT2	#4	31	STR.	20'-11"
AL1	#4	22	STR.	29'-10"		AL1	#4	22	STR.	29'-10"
AL2	#9	33	STR.	29'-10"		AL2	#9	33	STR.	29'-10"
SR1	#5	92	BNT.	4'-1"		SR1	#5	92	BNT.	4'-1"

NOTE: FOR SR1 BAR BEND, SEE STD_TR4-2

(1) THE DEPARTMENT CONSIDERS THE COST OF CONCRETE, REINFORCING STEEL (INCLUDING SRI BARS), BACKER ROD, RAPID CURE JOINT SEALANT, POLYSTYRENE AND POLYETHYLENE SHEETING TO BE INCLUDED IN THE CONTRACT UNIT PRICE OF APPROACH SLAB. THERE IS AN ESTIMATED 50.8 C.Y. OF CLASS AA CONCRETE AND AN ESTIMATED 10,080 LB. OF EPOXY COATED REINFORCING STEEL IN EACH APPROACH SLAB.







BRIDGE "B" COMANCHE COUNTY Design MLC 07/16
U.S.-277 over SNAKE CREEK

DETAILS OF APPROACH SLABS

Check DAH 04/17
Squat HARJO
First: MOLLA-ESMAIL

STATE OF DEPARTMENT OF TRANSPORTATION OKLAHOMA JOBPIECENO. 27968(04) SHEETNO. B027