

FED. ROAD DIST. NO.	STATE	STATE JOB NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	OKLA	17020(05)		6	

DESCRIPTION	REVISIONS	DATE
△ REV QUAN & ADDED NOTE		10-06-17

0100 ROADWAY PAY QUANTITIES				
ITEM NO.	CODE NO.	DESCRIPTION	UNITS	QUANTITY
201(A)	0102	CLEARING AND GRUBBING (1)	LSUM	1.00
202(A)	0183	UNCLASSIFIED EXCAVATION (2)(R-1)	CY	10,825.00
202(D)	0184	UNCLASSIFIED BORROW (3)(R-4)	CY	312.00
205(A)	4229	TYPE A-SALVAGED TOPSOIL (R-5)(R-7)	LSUM	1.00
221(C)	2801	TEMPORARY SILT FENCE (H-1)(4)(5)(6)	LF	3,607.00
221(H)	0450	(PL)TEMPORARY INLET SEDIMENT FILTER (H-1)(4)(5)	EA	13.00
221(F)	0100	TEMPORARY SILT DIKE (H-1)(4)(5)	LF	300.00
230(A)	2806	SOLID SLAB SODDING (H-1)(7)(8)(R-7)(R-8)	SY	12,518.00
233(A)	2817	VEGETATIVE MULCHING (H-1)(9)(R-11)	AC	3.00
241	2832	MOWING (R-16)	AC	5.00
303(A)	2100	AGGREGATE BASE TYPE A	CY	34.00
307(K)	4300	STABILIZED SUBGRADE	SY	14,085.00
402(E)	0225	TRAFFIC BOUND SURFACE COURSE TYPE E (10)(11)(R-25)	TON	100.00
407(D)	0400	(SP) TRACKLESS TACK COAT (12)	GAL	247.00
408	5774	PRIME COAT (R-28)	GAL	4,930.00
411(B)	5940	SUPERPAVE, TYPE S3(PG 70-28 OK) (13)(R-32)	TON	278.00
411(B)	5945	SUPERPAVE, TYPE S3(PG 64-22 OK) (13)(R-32)	TON	282.00
411(C)	5955	SUPERPAVE, TYPE S4(PG 70-28 OK) (13)(R-32)	TON	185.00
412	5267	COLD MILLING PAVEMENT (28)	SY	9,937.00
414(B)	5725	DOWEL JOINTED P.C. CONCRETE PAVEMENT(PLACEMENT)	SY	10,640.00
414(G)	5275	P.C. CONCRETE FOR PAVEMENT (26)	CY	2,958.00
501(A)	0313	STRUCTURAL EXCAVATION UNCLASSIFIED (R-1)	CY	386.00
509(A)	0319	CLASS AA CONCRETE (R-1)	CY	620.00
509(C)	0322	CLASS A CONCRETE, SMALL STRUCTURES (R-1)	CY	20.00
509(D)	0325	CLASS C CONCRETE	CY	333.00
511(A)	0332	REINFORCING STEEL (R-1)	LB	85,948.00
609(B)	1513	1'-8" COMB. CURB & GUTTER (6" BARRIER) (14)	LF	3,918.00
610(A)	0602	4" CONCRETE SIDEWALK (15)	SY	2,829.00
610(B)	0604	6" CONCRETE DRIVEWAY (16)	SY	563.00
610(C)	0609	6" CONCRETE DIVIDING STRIP (27)	SY	120.00
611(G)	4012	SPECIAL INLET DRAIN (17)(18)	EA	0.00
611(G)	5117	INLET CIDES. 2 (2B) (18)(R-44)	EA	2.00
611(G)	5118	INLET CIDES. 2 (B-D) (18)(R-44)	EA	2.00
611(G)	5119	INLET CIDES. 2 (2D) (18)(R-44)	EA	1.00
611(G)	5125	INLET CIDES. 3 (2D) (18)(R-44)	EA	1.00
611(G)	5976	INLET W/SMALL JCT. BOX, CI, DES.2(2B) (18)(R-44)	EA	1.00
611(H)	5325	ADD'L DEPTH IN INLET CIDES. 2 (18)	VF	4.00
611(H)	5330	ADD'L DEPTH IN INLET CIDES. 3 (18)	VF	1.00
611(H)	5976	ADD'L DEPTH IN INLET W/SJB, CI, DES. 2(2B) (18)	VF	1.00
611(L)	0487	JUNCTION BOXES (19)(20)	CF	244.00
612(A)	0641	MANHOLES ADJUST TO GRADE (19)(20)	EA	4.00
612(E)	0647	VALVE BOXES ADJUST TO GRADE	EA	9.00
612(F)	0648	METER BOXES ADJUST TO GRADE	EA	1.00
612(G)	0650	FIRE HYDRANT RESET	EA	1.00
613(A)	0491	18" R.C.PIPE CLASS III (21)(22)	LF	31.00
613(A)	0493	30" R.C.PIPE CLASS III (21)(22)	LF	220.00
613(A)	0494	36" R.C.PIPE CLASS III (21)(22)	LF	23.00
613(A)	0582	18" R.C.PIPE CLASS IV (21)(22)	LF	41.00
613(A)	4504	19" X 30" R.C.PIPE ELLIPTICAL CLASS HE-III (21)(22)	LF	32.00
613(A)	4505	24" X 38" R.C.PIPE ELLIPTICAL CLASS HE-III (21)(22)	LF	469.00
613(L)	5820	24" X 38" PREFAB. CULVERT END SEC., ELLIPTICAL	EA	1.00
613(G)	1080	6" P.V.C. PIPE ROUND (21)(22)	LF	44.00
616(O)	0250	6" 90 DEGREE FITTING	EA	1.00
619(A)	0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS (23)(29)(R-48)(R-49)	LSUM	1.00
619(B)	4725	REMOVAL OF FENCE (R-49)(R-50)	LF	87.00
619(B)	4728	REMOVAL OF ASPHALT PAVEMENT (R-49)	SY	9,937.00
619(B)	4766	REMOVAL OF CONCRETE DRIVEWAY (R-49)(R-50)	SY	327.00
619(C)	0924	SAWING PAVEMENT (24)	LF	1,046.00
624(C)	4459	FENCE-STYLE SWF (5 BARBED WIRE) (R-52)	LF	81.00
629(E)	5048	REMOVE AND RESET MAILBOX	EA	4.00

0600 STAKING PAY QUANTITIES				
ITEM NO.	CODE NO.	DESCRIPTION	UNIT	QUANT.
642(B)	0096	CONSTRUCTION STAKING LEVEL II (25)	LSUM	1.00

0640 CONSTRUCTION PAY QUANTITIES				
ITEM NO.	CODE NO.	DESCRIPTION	UNIT	QUANT.
220	2800	SWPPP DOCUMENTATION AND MANAGEMENT	LSUM	1.00
641	1552	MOBLIZATION	LSUM	1.00

△ THIS PROJECT IS MANATORILY TIED WITH JP#17020(07). WHEN THIS PROJECT IS BID AS TIED TO JP# 17020(07) ALL MOBILIZATION, SWPPP AND STAKING ARE TO BE CARRIED IN JP# 17020(05).

10/23/2017 10:31:51 AM - P:\27712\131-27712-13001\CAD\SHEETFILES\PAY_QTY_NOTES.ROADWAY.DWG - SCHUMACHER, MIKE

DESIGN	Tt	OKLAHOMA DEPARTMENT OF TRANSPORTATION SUMMARY OF PAY QUANTITY (ROADWAY)
DRAWN	MJS	
CHECKED	Tt	
APPROVED	DNP	
SQUAD	Tt	
STATE JOB NO. 17020(05)		SHEET NO. 6
CITY PROJECT R-1311A		GARFIELD COUNTY