

FED. ROAD DIST. NO.	STATE	STATE JOB NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	OKLA	17020(05)		11	
DESCRIPTION			REVISIONS		DATE

SIGNING SUMMARY									
SHT. NO.	SIGN NO.	APPROXIMATE STATION	TYPE OF SIGNS	DESCRIPTION	850(A) SHEET ALUMINUM SIGNS	FOOTING DESIGN NO.	851(C) 2 1/2" SQUARE TUBE POST		
							A	B	
					SF		LF	LF	
W. CHESTNUT AVE.									
34	2	38+00, LT	R2-1(40)	SPEED LIMIT SIGN	5.00	A-3	11.5		
34	3	43+00, RT	R2-1(40)	SPEED LIMIT SIGN	5.00	A-3	11.5		
N. CLEVELAND ST.									
35	4	152+86, RT	W4-2(R)	LANE ENDS	9.00	A-3	11.5		
35	5	161+00, LT	W9-1(R)	RIGHT LANE ENDS	9.00	A-3	11.5		
35	6	155+75, LT	R2-1(35)	SPEED LIMIT SIGN	5.00	A-3	11.5		
35	7	156+48.33, RT	R4-7c	NARROW KEEP RIGHT	3.75	A-3	11.5		
35	8	157+80.26, RT	R4-7c	NARROW KEEP RIGHT	3.75	A-3	11.5		
35	9	158+66, RT	W9-1(R)	RIGHT LANE ENDS	9.00	A-3	11.5		
35	10	159+50, LT	R2-1(35)	SPEED LIMIT SIGN	5.00	A-3	11.5		
35	11	159+50, RT	R2-1(35)	SPEED LIMIT SIGN	5.00	A-3	11.5		
35	12	160+40, LT	W4-2(R)	LANE ENDS	9.00	A-3	11.5		
TOTAL					68.50		126.5		

STRIPING SUMMARY							
SHEET NO	STATION TO STATION	856(A)	856(A)	856(A)	856(A)	856(A)	856(B)
		TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE) SOLID WHITE LF	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE) SOLID YELLOW LF	TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE) SOLID WHITE LF	TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE) SOLID YELLOW LF	TRAFF. STRIPE(MULTI-POLY.)(24" WIDE) SOLID WHITE LF	TRAF.STR.(MULTI-POLY.)(SYM.WRD, ETC) SOLID WHITE EA
W. CHESTNUT AVE.							
34	33+00 TO 47+00	470	3,107	0	742	176	8
N. CLEVELAND ST.							
35	150+00 TO 163+00	1,443	2,130	274	254	263	9
SUB-TOTAL		1,913	5,237	274	996	439	17
TOTAL		7,150		1,270		439	17

TRAFFIC CONTROL SUMMARY															
PHASE	DESCRIPTION	857(A)	857(B)	857(B)	857(C)	857(E)	857(F)	880(B)	880(B)	880(B)	880(C)	880(C)	880(E)	880(G)	880(F)
		CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE) LF	CONSTRUCTION TRAFFIC STR.(PAINT)(ARROWS) EA	CONSTRUCTION TRAFFIC STR.(PAINT)(WORDS) EA	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE) LF	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1 EA	PAVEMENT MRKNG.REMOVAL (TRAF.STRP) LF	CONSTRUCTION SIGNS 0 TO 6.25 SF SD	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF SD	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF SD	CONSTRUCTION BARRICADES (TYPE III) SD	WING BARRICADES SD	WARNING LIGHTS(TYPE A) SD	CHANNELIZER CONES SD	DRUMS SD
1	CONSTRUCT SOUTH SIDE OF CHESTNUT AVE AND SOUTH LEG OF CLEVELAND ST.	1372	1	1	312	50	1,636	15200	2280	3990	1330	760	4750	-	10640
2	CONSTRUCT NORTHWEST SIDE OF CHESTNUT AVE AND NORTHWEST SIDE OF CLEVELAND ST.	1082	1	1	2454	75	1,018	5890	1140	1425	475	380	1710	4750	6080
3	CONSTRUCT NORTHEAST SIDE OF CLEVELAND ST AND NORTHEAST SIDE OF CHESTNUT AVE.	0	-	-	3542	75	3,542	5795	1140	1520	380	380	1995	3040	4655
TOTAL		2,454	2	2	6,308	200	6,196	26,885	4,560	6,935	2,185	1,520	8,455	7,790	21,375

DESIGN	Tt	OKLAHOMA DEPARTMENT OF TRANSPORTATION SUMMARY SHEET (TRAFFIC) STATE JOB NO. <u>17020(05)</u> SHEET NO. <u>11</u> CITY PROJECT R-1311A GARFIELD COUNTY
DRAWN	MJS	
CHECKED	Tt	
APPROVED	DNP	
SQUAD	Tt	

4/21/2017 5:27:43 PM - P:\27712131-27712-13001\CAD\SHEETFILES\SUMMARY SHEET 1.DWG - SCHUMACHER, MIKE