

REVISIONS		
NO.	DESCRIPTION	DATE

GENERAL CONSTRUCTION NOTES

SYMBOLS AND LEGENDS ARE DIAGRAMMATIC ONLY AND LOCATIONS SHALL BE ADJUSTED FOR EXISTING FIELD CONDITIONS, BUT NO MAJOR ALTERATIONS OR RELOCATIONS WILL BE MADE WITHOUT FIRST CONSULTING WITH THE ENGINEER.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE HE MAY INFLICT TO THE EXISTING UNDERGROUND UTILITIES WITHIN THE PROJECT AREA AS A RESULT OF HIS DIGGING, TRENCHING, BORING, ETC.... PRIOR TO DIGGING NEAR THE UTILITIES, THE CONTRACTOR SHALL CALL FOR A LIST OF ALL UNDERGROUND FACILITIES REGISTERED IN THE AREA OF CONSTRUCTION LISTED WITH THE FOLLOWING AGENCIES:
THE "OKIE" NOTIFICATION CENTER 811 OR (405)522-6543 OR WWW.CALLOKIE.COM OR THE LOCAL COUNTY CLERK'S OFFICE.

PAY QUANTITY NOTES

- (TP-1) PAYMENT FOR THIS ITEM WILL BE BASED ON PLAN QUANTITY. SEE THE 2009 SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.
- (1) POLYMER CONCRETE PULL BOXES SHALL BE USED.
- (2) THE DECORATIVE POLES TO BE FURNISHED ON THIS PROJECT SHALL BE PELCO AP-8347 FOR THE SINGLE 8' ARM MAJESTIC FLUTED 30' POLES AND PELCO AP-8348 FOR THE TWIN 8' ARM MAJESTIC FLUTED 30' POLES. ALL POLES WILL BE POWDER COATED PELCO P59 TEXTURED BLACK IN COLOR.
- (3) THE DECORATIVE POLE BASES TO BE FURNISHED ON THIS PROJECT SHALL BE PELCO AP-0816 STANDARD POLE BASES.
- (4) THE DECORATIVE LUMINAIRES TO BE FURNISHED ON THIS PROJECT SHALL BE PELCO HARRISBURG LIGHT FIXTURES, MODEL NO. AP-7501-136W-60LED-4K-480V-NPC-T3PL-P59.
- (5) A PEDESTAL STYLE SERVICE JUNCTION SHALL BE INSTALLED ON THIS PROJECT AS APPROVED BY THE ENGINEER.

PAY QUANTITIES


0300 LIGHTING			
ITEM	DESCRIPTION	UNIT	TOTAL
802(B) 8340	2" PVC SCH. 40 PLASTIC CONDUIT BORED	(TP-1) LF	1260.00
802(B) 8342	2" PVC SCH. 40 PLASTIC CONDUIT TRENCHED	(TP-1) LF	2690.00
803(A) 8065	PULL BOX (SIZE I)	(1) EA	31.00
804(A) 2915	STRUCTURAL CONCRETE	(TP-1) CY	13.92
804(B) 2916	REINFORCING STEEL	(TP-1) LB	801.60
806(C) 8270	30' MTG & HLMA (SPECIAL)	(2) EA	24.00
807 8092	BREAKAWAY BASE (DES. B)	(3) EA	24.00
809(A) 8090	ROADWAY LUMINAIRE	(4) EA	32.00
810(A) 3118	SERVICE POLE	(5) EA	1.00
811 8038	1/C NO. 4 ELECT. COND.	(TP-1) LF	8295.00
811 8046	1/C NO. 12 ELECT. COND.	(TP-1) LF	3200.00

12/14/2016 G:\Projects\T-2280 Cleveland S1 & Chestnut Ave - Enid, OK\CAD\R-318 BLVD QUANT LIGHT.dgn

R. Wayne Russell
R. WAYNE RUSSELL, P.E. # 16030
C.A. # 1160, RENEWAL 06-30-17

12-12-16
DATE

Traffic Engineering Consultants, Inc.
6000 S. Western, Suite 300 - Oklahoma City, OK 73139,
Ph: 405-720-7721, Fax: 405-720-9848, Web: www.tecok.com



Design	RWR	12/14/2016
Drawn	CCC	12/14/2016



LIGHTING PAY QUANTITIES AND NOTES

Project No. R-1311B Sheet No. 6

STATE JOB NO. 17020(07)

GARFIELD COUNTY