

FED. ROAD DIST. NO.	STATE	STATE JOB NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	OKLA	17020(07)		8	
DESCRIPTION			REVISIONS		DATE

SUMMARY OF DITCH TREATMENT									
P&P SHEET NO.	LOCATION			DESCRIPTION	CONCRETE LINER				509(D)
					DESIGN NO.	LENGTH	BOTTOM WIDTH	CURTAIN WALLS	CLASS C CONCRETE
	STATION	TO	STATION		L.F.	FT.	EA.	CY	
16	164+19.00	TO	164+38.00	PAVED FLUME TO FLAT BOTTOMED ENTRANCE TO CULVERT HEADWALL	DES 2A WITH VARYING WIDTH	31	10FT-13FT	2	6.91
TOTAL									6.91

SUMMARY OF EROSION CONTROL								
SHEET NO.	STATION TO STATION				221(C)	221(H)	233(A)	241
					TEMPORARY SILT FENCE	(PL)TEMPORARY INLET SEDIMENT FILTER	VEGETATIVE MULCHING	MOWING
	LF	EA	AC	AC				
N. CLEVELAND ST.								
14	161+30.00	TO	177+00.00	2,968.00	10	1.04	2.07	
15	177+00.00	TO	182+82.14	1,188.00	2	0.56	1.12	
TOTAL				4,156.00	12	1.60	3.19	

SUMMARY OF SECTION LINE RETURNS AND DRIVES														
P&P SHEET NO.	STATION	SURFACE	TYPE	TOTAL LENGTH FROM SHLDR TO RW	ST. RTN / DRIVEWAY AREA	SURFACE AREA		RADIUS				SURFACE WIDTH	610(B)	
						CONC AREA	TBSC AREA	EAST (FT)	WEST (FT)	SOUTH (FT)	NORTH (FT)		FT	SY
						SY	SY							
CLEVELAND STREET														
16	162+72.70	RT	CONCRETE	DRIVE	15	334	334			10	10	12	37.11	
16	163+12.11	RT	CONCRETE	DRIVE	14	339	339			10	10	15	37.67	
16	163+55.47	RT	CONCRETE	DRIVE	14	433	433			10	10	20	48.11	
17	170+75.00	RT	CONCRETE	DRIVE	31	1,728	1,728			30	30	46	192.00	
17	176+84.73	LT	CONCRETE	DRIVE	37	1,100	1,100			20	20	24	122.22	
TOTAL												437.11		

SUMMARY OF STRUCTURE ADJUSTMENTS							
SHEET NO.	LOCATION		DESCRIPTION	612(A)	612(E)	612(F)	
				MANHOLES ADJUST TO GRADE	VALVE BOXES ADJUST TO GRADE	METER BOXES ADJUST TO GRADE	
	EA	EA		EA			
N. CLEVELAND STREET							
16	161+30.17	OFFSET	10.41' LT	SANITARY SEWER	1		
16	162+51.19	OFFSET	23.91' RT	WATER		1	
16	163+71.58	OFFSET	36.10' RT	WATER		1	
16	165+15.34	OFFSET	15.10' LT	SANITARY SEWER	1		
16	168+53.79	OFFSET	20.73' LT	SANITARY SEWER	1		
16	168+68.71	OFFSET	16.70' RT.	WATER		2	
16	168+93.31	OFFSET	21.33' LT	SANITARY SEWER	1		
17	172+71.85	OFFSET	23.62' RT	SANITARY SEWER	1		
17	176+50.53	OFFSET	22.68' RT	SANITARY SEWER	1		
18	177+27.14	OFFSET	12.71' RT	WATER		2	
18	180+34.99	OFFSET	22.42' RT	SANITARY SEWER	1		
18	181+70.50	OFFSET	35.98' RT	WATER		1	
18	181+83.15	OFFSET	46.17' RT	WATER		1	
NOTE: CONTRACTOR TO FIELD VERIFY EXISTING UTILITY LOCATIONS							
TOTAL				7	7	1	

SUMMARY OF SURFACING QUANTITIES															
P&P SHEET NO.	TYP. SEC. NO.	STATION TO STATION		230(A)	307(K)	407(D)	408	411(B)	411(B)	411(C)	414(B)	414(G)	609(B)	610(A)	
				SOLID SLAB SODDING	STABILIZED SUBGRADE	(SP) TRACKLESS TACK COAT	PRIME COAT	SUPERPAVE, TYPE S3(PG 70-28 OK)	SUPERPAVE, TYPE S3(PG 64-22 OK)	SUPERPAVE, TYPE S4(PG 70-28 OK)	DOWEL JOINTED P.C. CONCRETE PAVEMENT(PLACEMENT)	P.C. CONCRETE FOR PAVEMENT	1'-8" COMB. CURB & GUTTER (6" BARRIER)	4" CONCRETE SIDEWALK	
				SY	SY	GAL	GAL	TON	TON	TON	SY	CY	LF	SY	
CLEVELAND STREET															
16	1,2	161+30.00	TO	169+00.00	1,637.69	4,175.28		1,461.35			4,296.0	1,194.00	2,069.16	999.00	
17	1,2	169+00.00	TO	177+00.00	3,374.61	5,122.62		1,792.92			5,089.0	1,414.00	2,203.91	1,260.00	
18	1,2,3	177+00.00	TO	182+82.14	2,709.44	3,656.16	40.69	1,279.66	45.33	45.82	29.95	3,374.0	938.00	1,549.54	879.00
TOTAL				7,721.75	12,954.07	40.69	4,533.92	45.33	45.82	29.95	12,759.00	3,546.00	5,822.61	3,138.00	

SUMMARY OF REMOVAL ITEMS							
SHEET NO.	DESCRIPTION			619(B)	619(B)	619(C)	629(E)
				REMOVAL OF CONCRETE PAVEMENT	REMOVAL OF ASPHALT PAVEMENT	SAWING PAVEMENT	REMOVE AND RESET MAILBOX
	SY	SY	LF	EA			
N. CLEVELAND STREET							
27	161+30.00	TO	177+00.00	883.00	5,375.00	850.00	1
28	177+00.00	TO	182+81.97		1,596.00	127.00	
TOTAL				883.00	6,971.00	977.00	1

SUMMARY OF EARTHWORK						
P & P SHEET NO.	STATION TO STATION		202(A)	EMBANKMENT +15%	202(D)	EXCESS EXCAVATION
			UNCLASSIFIED EXCAVATION		UNCLASSIFIED BORROW	
	CY	CY	CY	CY		
CLEVELAND STREET						
16	161+30.00	TO	169+00.00	494.08	2,994.18	2,500.10
17	169+00.00	TO	177+00.00	44.96	5,505.42	5,460.46
18	177+00.00	TO	182+82.14	83.64	6,572.47	6,488.83
TOTAL				622.68	15,072.07	14,449.39

DESIGN	TT	OKLAHOMA DEPARTMENT OF TRANSPORTATION SUMMARY SHEETS (ROADWAY) STATE JOB NO. <u>17020(07)</u> SHEET NO. <u>8</u>
DRAWN	CWT	
CHECKED	JDH	
APPROVED	JDH	
SQUAD	Tt	

CITY PROJECT R-1311B

4/21/2017 6:24:13 PM - P:\2771\21\13\13-2771-2-1001\CAD\SHSHEET\FILES\CLEVELAND BLVD PLANS\IPAY QUANTITIES NOTES ROADWAY.DWG - SCHUMACHER, MIKE