

FED. ROAD DIST. NO.	STATE	STATE JOB NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	OKLA	17020(07)		9	
DESCRIPTION			REVISIONS		DATE

SIGNING SUMMARY								
SHT. NO.	SIGN NO.	APPROXIMATE STATION	TYPE OF SIGNS	DESCRIPTION	850(A) SHEET ALUMINUM SIGNS	FOOTING DESIGN NO.	851(C) 2 1/2" SQUARE TUBE POST	
							A	B
					SF		LF	LF
N. CLEVELAND ST.								
31	1	169+50, RT	R2-1(35)	SPEED LIMIT SIGN	5.00	A-3	11.5	
31	2	169+50, LT	R2-1(35)	SPEED LIMIT SIGN	5.00	A-3	11.5	
31	3	171+27, RT	W4-2(R)	LANE ENDS	9.00	A-3	11.5	
31	4	175+77, RT	W1-3(L)	HORIZONTAL ALIGNMENT	6.25	A-3	11.5	
31	5	175+77, RT	W13-1(P)	ADVISORY SPEED (PLAQUE)	2.25			
32	6	179+50, LT	R2-1(35)	SPEED LIMIT SIGN	5.00	A-3	11.5	
32	7	182+00, T	W10-1	GRADE CROSSING ADVANCED WARNING	7.06	A-3	11.5	
TOTAL					39.56		69.0	

STRIPING SUMMARY									
SHEET NO	STATION TO STATION	856(A)	856(A)	856(A)	856(A)	856(A)	856(A)	856(B)	
		TRAFFIC STRIPE(MULTI-POLY)(4" WIDE) SOLID WHITE LF	TRAFFIC STRIPE(MULTI-POLY)(4" WIDE) SOLID YELLOW LF	TRAFFIC STRIPE(MULTI-POLY)(8" WIDE) SOLID WHITE LF	TRAFFIC STRIPE(MULTI-POLY)(8" WIDE) SOLID YELLOW LF	TRAFF. STRIPE(MULTI-POLY)(24" WIDE) SOLID WHITE LF	TRAF.STR.(MULTI-POLY)(SYM,WRD, ETC) SOLID WHITE EA		
N. CLEVELAND ST.									
31	161+30.00 TO 177+00.00	790	1,451	0	48	0	12		
32	177+00.00 TO 182+82.14	1,327	688	2,371	35	37	3		
SUB-TOTAL		2,117	2,139	2,371	83	37	15		
TOTAL		4,256		2,454		37	15		

TRAFFIC CONTROL SUMMARY													
PHASE	DESCRIPTION	857(A) CONSTRUCTION TRAFF.STR.(PAINT) (4" WIDE) LF	857(C) REMOVABLE PAVEMENT MARKING TAPE(4" WIDE) LF	857(E) (PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1 EA	857(F) PAVEMENT MRKNG.REMOVAL (TRAF.STRP) LF	880(B) CONSTRUCTION SIGNS 0 TO 6.25 SF SD	880(B) CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF SD	880(B) CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF SD	880(C) CONSTRUCTION BARRICADES(TYPE III) SD	880(C) WING BARRICADES SD	880(E) WARNING LIGHTS(TYPE A) SD	880(G) CHANNELIZER CONES SD	880(F) DRUMS SD
1	CONSTRUCT STORM SEWER					224		84		28	28	238	
2	CONSTRUCT NORTHBOUND LANES	600	600	100		1,440		540		180	180	4,230	
3	CONSTRUCT SOUTHBOUND LANES	3,920	600	100	1,200	1,710	180	810	180	180	540	4,860	
4	CONSTRUCT MEDIAN LANE AND ISLAND				4,520	1,020	240	840	240	120	360	720	5,340
TOTAL		4,520	1,200	200	5,720	4,394	420	2,274	420	508	1,108	10,048	5,340

4/21/2017 6:24:27 PM - P:\2771\21\131-2771\2-13001\CAD\SHSHEETFILES\CLEVE BLVD PLANS\PAV QUANTITIES NOTES ROADWAY.DWG - SCHUMACHER, MIKE

DESIGN	TT	OKLAHOMA DEPARTMENT OF TRANSPORTATION
DRAWN	CWT	
CHECKED	JDH	
APPROVED	JDH	
SQUAD	Tt	
SUMMARY SHEET (TRAFFIC)		
STATE JOB NO. <u>17020(07)</u>		SHEET NO. <u>9</u>
CITY PROJECT R-1311B		GARFIELD COUNTY