

SUMMARY OF STRIPING		
STATION TO STATION	TRAFFIC STRIPE (PLASTIC) (8" WIDE) 855(A)	TRAFFIC STRIPE (PLASTIC) (24" WIDE) 855(A)
	LF	LF
SIDEWALK NO. 1		
STA. 100+15.21 TO STA. 105+00.00	52	51
STA. 105+00.00 TO STA. 110+00.00	137	107
STA. 110+00.00 TO STA. 115+00.00	124	94
STA. 115+00.00 TO STA. 120+00.00	263	253
STA. 120+00.00 TO STA. 125+00.00	82	81
STA. 125+00.00 TO STA. 129+00.00	57	51
STA. 129+00.00 TO STA. 131+21.89	91	192
SIDEWALK NO. 2		
STA. 200+04.53 TO STA. 205+00.00	54	42
STA. 205+00.00 TO STA. 210+00.00	41	32
STA. 210+00.00 TO STA. 214+71.90	178	147
SIDEWALK NO. 3		
STA. 300+18.03 TO STA. 305+00.00		
STA. 305+00.00 TO STA. 310+00.00	68	83
STA. 310+00.00 TO STA. 315+00.00		
STA. 315+00.00 TO STA. 320+00.00	114	80
STA. 320+00.00 TO STA. 325+00.00		
STA. 325+00.00 TO STA. 325+76.69	63	53
TOTALS	1324	1266

SUMMARY OF SURFACING									
STATION TO STATION	AGGREGATE BASE TYPE A	TACK COAT	PRIME COAT	SUPERPAVE, TYPE S3 (PG 64-22 OK)	SUPERPAVE, TYPE S4 (PG 64-22 OK)	P.C. CONCRETE PAVEMENT (PLACEMENT)	CONC. CURB (6" BARRIER - INTEGRAL)	4" CONCRETE SIDEWALK	TACTILE WARNING DEVICE-NEW
	303(A) CY	407(B) GAL	408 GAL	411(B) TON	411(C) TON	414(A) SY	609(A) LF	610(A) SY	610(I) SF
SIDEWALK NO. 1									
STA. 100+15.21 TO STA. 105+00.00	21							185	20
STA. 105+00.00 TO STA. 110+00.00	20							180	30
STA. 110+00.00 TO STA. 115+00.00	26							233	30
STA. 115+00.00 TO STA. 120+00.00	21							189	20
STA. 120+00.00 TO STA. 125+00.00	25							217	20
STA. 125+00.00 TO STA. 129+00.00	105	28	20	12	6			198	20
STA. 129+00.00 TO STA. 131+21.89	15							132	40
SIDEWALK NO. 2									
STA. 200+04.53 TO STA. 205+00.00	107	19	13	9	5			449	20
STA. 205+00.00 TO STA. 210+00.00	30							267	20
STA. 210+00.00 TO STA. 214+71.90	76	18	13	8	4			209	30
SIDEWALK NO. 3									
STA. 300+18.03 TO STA. 305+00.00	21						147	188	
STA. 305+00.00 TO STA. 310+00.00	172					97	162	239	30
STA. 310+00.00 TO STA. 315+00.00	20							176	
STA. 315+00.00 TO STA. 320+00.00	28							246	20
STA. 320+00.00 TO STA. 325+00.00	27							235	
STA. 325+00.00 TO STA. 325+76.69	99					64	47	27	20
TOTALS	813	65	46	29	15	161	356	3370	320

SUMMARY OF REMOVALS						
LOCATION	REMOVAL OF ASPHALT PAVEMENT 619(B)	REMOVAL OF CONCRETE PAVEMENT 619(B)	REMOVAL OF CURB AND GUTTER 619(B)	REMOVAL OF CONCRETE DRIVEWAY 619(B)	REMOVAL OF ASPHALT DRIVEWAY 619(B)	SAWING PAVEMENT 619(C)
	SY	SY	LF	SY	SY	LF
SIDEWALK NO. 1						
STA. 100+15.21 TO STA. 105+00.00			21	18		73
STA. 105+00.00 TO STA. 110+00.00			23			23
STA. 110+00.00 TO STA. 115+00.00			24	578		122
STA. 115+00.00 TO STA. 120+00.00			15	22		47
STA. 120+00.00 TO STA. 125+00.00				34		54
STA. 125+00.00 TO STA. 129+00.00	56				41	135
STA. 129+00.00 TO STA. 131+21.89						
SIDEWALK NO. 2						
STA. 200+04.53 TO STA. 205+00.00	38			30		104
STA. 205+00.00 TO STA. 210+00.00						
STA. 210+00.00 TO STA. 214+71.90	36	7	28	278		65
SIDEWALK NO. 3						
STA. 300+18.03 TO STA. 305+00.00		136		355		411
STA. 305+00.00 TO STA. 310+00.00	97		55	61		241
STA. 310+00.00 TO STA. 315+00.00				436		508
STA. 315+00.00 TO STA. 320+00.00			29			29
STA. 320+00.00 TO STA. 325+00.00			9	138		169
STA. 325+00.00 TO STA. 325+76.69		64	48			81
TOTALS	227	207	252	1950	41	2063

SUMMARY OF DRIVEWAYS										
LOCATION	TYPE	RADIUS	LENGTH	WIDTH	AGGREGATE BASE TYPE A 303(A)	6" CONCRETE DRIVEWAY 610(B)	ASPHALT DRIVEWAY 610(G)			
		FT	FT	FT	CY	SY	TON			
SIDEWALK NO. 1										
101+04.49	RT	COMMERCIAL	25	10	15	3	18			
113+16.56	LT	RESIDENTIAL	10	13	12	3	18			
113+72.35	LT	RESIDENTIAL	10	13	19	5	27			
114+03.23	LT	RESIDENTIAL	10	13	13	3	19			
116+91.72	LT	RESIDENTIAL	5	14	11	4	21			
124+33.20	LT	ALLEY	10	20	12	6	34			
127+92.22	LT	RESIDENTIAL	15	15	18	68		14		
SIDEWALK NO. 2										
202+16.85	LT	RESIDENTIAL	10	18	12	5	30			
206+87.75	LT	ALLEY	10	20	20	8		17		
211+88.55	LT	RESIDENTIAL	5	25	10	5	30			
SIDEWALK NO. 3										
300+99.89	LT	COMMERCIAL	15/5	19	20	9	51			
301+48.51	LT	COMMERCIAL	5/10	19	23	9	55			
301+94.10	LT	COMMERCIAL	10/15	19	23	10	63			
303+21.14	LT	COMMERCIAL	15/5	17	35	12	75			
304+04.35	LT	COMMERCIAL	10/15	17	32	13	77			
309+63.76	LT	COMMERCIAL	15/5	19	28	10	61			
310+25.00	LT	COMMERCIAL	5/15	19	30	9	62			
310+75.27	LT	COMMERCIAL	12	19	23	10	58			
311+94.39	LT	COMMERCIAL	12	19	24	10	61			
312+66.85	LT	COMMERCIAL	25/30	19	40	20	121			
313+85.57	LT	COMMERCIAL	15	19	24	11	67			
314+59.56	LT	COMMERCIAL	15	19	24	11	66			
322+64.68	LT	COMMERCIAL	15/25	19	30	15	89			
323+96.30	LT	RESIDENTIAL	10	18	20	8	49			
TOTALS						267	1152	31		

DESIGN	LKN	7/7/17
DRAWN	TJW	7/7/17
CHECKED	SKF	7/7/17
APPROV.	SKF	7/7/17
SQUAD	CGE	

PLOTTED: Friday, July 07, 2017 @ 04:22PM
 C:\projects\17-058\17-058.dwg - TAE_S17001.dwg - 17-058 QUANTITIES AND NOTES.dwg