

REVISIONS		
REV. NO.	DESCRIPTION	DATE

28857(04) 0200 BRIDGE "A"				
PAY QUANTITIES				
SH-28 OVER SALT CREEK 85'-100'-85' TYPE IV P.C. BEAM SPANS, 30' R.F. SKEW 40'-0" CLEAR ROADWAY WITH CONCRETE TRAFFIC RAIL (TR4)				
ITEM NO.		DESCRIPTION	UNIT	QUANTITY
501(B)	1307	SUBSTRUCTURE EXCAVATION COMMON (BR-1)	C.Y.	250.00
501(G)	6309	CLSM BACKFILL (BR-1)	C.Y.	288.00
503(A)	1313	PRESTRESSED CONCRETE BEAMS (TYPE IV) (BR-1)	L.F.	1,345.00
504(A)	1304	APPROACH SLAB (BR-1)	S.Y.	381.40
504(B)	1305	SAW-CUT GROOVING (BR-1)	S.Y.	1,579.90
504(C)	6250	SEALED EXPANSION JOINT (BR-1)	L.F.	48.90
504(D)	6245	CONCRETE RAIL (TR4) (BR-1)	L.F.	711.00
506(A)	1322	STRUCTURAL STEEL (BR-1)	LB.	1,575.00
507(A)	6170	STAINLESS STEEL FIXED BEARING ASSEMBLY (BR-1)	EA.	10.00
507(B)	6174	STAINLESS STEEL EXPANSION BEARING ASSEMBLY (BR-1)	EA.	20.00
509(A)	1326	CLASS AA CONCRETE (BR-1)	C.Y.	331.80
509(B)	1328	CLASS A CONCRETE (BR-1)	C.Y.	206.90
509(D)	1331	CLASS C CONCRETE	C.Y.	12.00
511(B)	6010	EPOXY COATED REINFORCING STEEL (BR-1)	LB.	124,270.00
514(A)	6010	PILES, FURNISHED (HP 10X42)	L.F.	84.00
514(A)	6011	PILES, FURNISHED (HP 12X53)	L.F.	378.00
514(B)	6292	PILES, DRIVEN (HP 10X42)	L.F.	84.00
514(B)	6294	PILES, DRIVEN (HP 12X53)	L.F.	378.00
514(K)	6260	(PL) PILOT HOLES	L.F.	330.00
514(L)	6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	EA.	1.00
515(A)	6013	WATER REPELLENT (VISUALLY INSPECTED) (BR-1)	S.Y.	1,301.00
516(A)	6094	DRILLED SHAFTS 48" DIAMETER	L.F.	82.00
516(C)	6200	CROSSHOLE SONIC LOGGING	EA.	1.00
523(A)	6550	SEALER CRACK PREPARATION (BR-1)	L.F.	46.50
523(B)	6560	SEALER RESIN (BR-1)	GAL.	0.60
601(B)	1353	TYPE I-A PLAIN RIPRAP	TON	1,550.00
601(C)	1355	TYPE I-A FILTER BLANKET	TON	295.00
613(H)	6204	6" PERFORATED PIPE UNDERDRAIN ROUND (BR-1)	L.F.	96.00
613(I)	6207	6" NON-PERF. PIPE UNDERDRAIN RND.	L.F.	60.00
619(D)	1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	L.SUM	1.00

(BR-1): PAYMENT FOR THIS ITEM WILL BE BASED ON THE PLAN QUANTITIES ONLY. SEE SECTION 109.01.B OF THE OKLAHOMA STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

28857(04) 0600 STAKING				
PAY QUANTITIES				
ITEM NO.		DESCRIPTION	UNIT	QUANTITY
642(B)	0096	CONSTRUCTION STAKING LEVEL II	L.SUM	1.00

28857(04) 0640 CONSTRUCTION				
PAY QUANTITIES				
ITEM NO.		DESCRIPTION	UNIT	QUANTITY
220	2800	SWPPP DOCUMENTATION AND MANAGEMENT	L.SUM	1.00
640(A)	1398	FIELD OFFICE	EA.	1.00
641	1399	MOBILIZATION	L.SUM	1.00

Monday, July 31, 2017 4:10:45 PM
V:\12-716E SH-28 Salt Creek JP_28857\STRUCTURAL\DWG\Salt Creek - PO & NOTES.dwg

DESIGN	MBS	5/14	SH-28 OVER SALT CREEK BRIDGE "A"	NOWATA COUNTY
DETAIL	SLP	5/14		
CHECK	MBS	3/15		
GUY ENGINEERING SERVICES, INC.				
GENERAL NOTES AND SUMMARY OF PAY QUANTITIES (BRIDGE) (SHEET NO. 2 OF 2)			STATE JOB PIECE NO. 28857(04)	SHEET NO. AB02