

FED. ROAD DIST. NO.	STATE	JOB/PIECE NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
6	OKLA.	28878(04)			

DESCRIPTION	REVISIONS	DATE

SUMMARY OF SURFACING QUANTITIES					
SHEET NO.	C.R.L. STATION TO STATION	TACK COAT	SUPERPAVE, TYPE S4 (PG 70-28 OK)	SUPERPAVE, TYPE S4 (PG 64-22 OK)	
		GAL	411(C) TON	411(C) TON	
12	475+38.00 TO 486+11.00	1,216	943	549	
<b>TOTALS:</b>		<b>1,216</b>	<b>943</b>	<b>549</b>	

\* FOR CONTRACTOR INFORMATION ONLY. TO BE INCLUDED IN PRICE BID FOR ASPHALT.

SUMMARY OF GUARDRAIL WIDENING								
C.R.L. STATION TO STATION			TACK COAT	PRIME COAT	SUPERPAVE, TYPE S4 (PG 64-22 OK)	BEAM GUARDRAIL W-BEAM SINGLE	GUARDRAIL END TREATMENT (31")	GUARDRAIL BRIDGE CONN-THRE BEAM (31")
			GAL	GAL	411(C) TON	623(A) LF	623(G) EA	623(I) EA
482+10.87 TO 487+62.00	LT		17	83	51	237.5	1	1
482+10.87 TO 485+83.00	RT		11	52	32	437.5	1	1
<b>TOTALS:</b>			<b>28</b>	<b>135</b>	<b>83</b>	<b>675</b>	<b>2</b>	<b>2</b>

\* FOR CONTRACTOR INFORMATION ONLY. TO BE INCLUDED IN PRICE BID FOR ASPHALT.

SUMMARY OF REMOVALS				
SHEET NO.	C.R.L. STATION TO STATION	COLD MILLING PAVEMENT	REMOVAL OF ASPHALT PAVEMENT	REMOVAL OF GUARDRAIL
		412 SY	619(B) SY	619(B) LF
12	475+38.00 TO 486+11.00	5,078	609	1,187
<b>TOTALS:</b>		<b>5,078</b>	<b>609</b>	<b>1,187</b>

SUMMARY OF EROSION CONTROL											
C.R.L. STATION TO STATION		TEMPORARY						PERMANENT			
		SILT FENCE	SEDIMENT FILTER	SILT DIKE	SEEDING METHOD B	VEGETATIVE MULCHING	* FERTILIZING (10-20-10)	* FERTILIZING (0-46-0)	SOLID SLAB SODDING	* FERTILIZING (10-20-10)	* WATERING
475+38.00 TO 486+11.00		1,265	1	56	0.24	0.24	0.04	0.02	1,169	0.12	46.7
<b>TOTALS:</b>		<b>1,265</b>	<b>1</b>	<b>56</b>	<b>0.24</b>	<b>0.24</b>	<b>0.04</b>	<b>0.02</b>	<b>1,169</b>	<b>0.12</b>	<b>46.7</b>

\* FOR CONTRACTORS INFORMATION ONLY, COST TO BE INCLUDED IN THE PRICE BID FOR OTHER WORK.

SUMMARY OF EARTHWORK QUANTITIES								
C.R.L. STATION TO STATION	*UNCLASSIFIED EXCAVATION 202(A)		EMBANKMENT 15%		*UNCLASSIFIED BORROW 202(C)		WASTE	
	PHASE 1	PHASE 2	PHASE 1	PHASE 2	PHASE 1	PHASE 2	PHASE 1	PHASE 2
475+38.00 TO 486+11.00	-	-	30	300	30	300	-	-
<b>TOTALS:</b>		-	-	30	300	30	300	-

\*FOR CONTRACTOR INFORMATION ONLY, COST TO BE INCLUDED IN PRICE BID FOR EARTHWORK

REMOVAL OF STRUCTURES & OBSTRUCTIONS		
C.R.L. STATION TO STATION	DESCRIPTION	
478+00.00 TO 479+38.13	CONCRETE MEDIAN BARRIER	

SUMMARY OF BARRIER QUANTITIES								
SHEET NO.	C.R.L. STATION TO STATION	STANDARD	LENGTH	42" F-SHAPED PARAPET	CLASS A CONCRETE (LONG. BAR. DES. 1-A)	REINFORCING STEEL	(SP) IMPACT ATTENUATOR	REMARKS
				504(E) LF	509(B) CY	511(A) LBS	871(A) EA	
12	476+75.00 RT TO 479+38.13 RT	FSHP-42-2	264	264	0	0	1	
12	478+00.00 MED TO 479+38.13 MED	CLB-1	138	0	27	577	0	
<b>TOTALS:</b>				<b>264</b>	<b>27</b>	<b>577</b>	<b>1</b>	

DESIGN	HBV	7/17	OKLAHOMA DEPARTMENT OF TRANSPORTATION US-64/SH-51 OVER SHERIDAN RD.  <b>SUMMARY SHEET (ROADWAY)</b>
DRAWN	HBV	7/17	
CHECKED	NAB	7/17	
APPROVED			
SQUAD	<b>GARVER</b>		
COUNTY	TU.SA	HIGHWAY	SH-51
STATE JOB NO.		28878(04)	SHEET NO. 7

L:\2021\2037096 - 000T EC-144 Task Order - 6\Drawings\28878(04)\_SumRoadway.dgn 9:34:35 AM 6/2/2017